



CONSTRUCTION NOTES:

- ① REMOVE AND DISPOSE OF EXISTING FENCE (INCIDENTAL).
- ② EXTEND BARRIER CURB, TIE INTO EXISTING CURB.
- ③ REMOVE EXISTING TREES.
- ④ SAWCUT EXISTING EDGE OF SLAB AS DIRECTED BY CONTRACT ADMINISTRATOR.
- ⑤ BARRIER CURB TO MODIFIED BARRIER CURB TRANSITION.
- ⑥ REMOVE EXISTING BERM.
- ⑦ CONNECT TO EXISTING MANHOLE.
- ⑧ ALL DIMENSIONS MEASURED TO BACK OF CURB.
- ⑨ ADJUST ALL MANHOLES AND VALVES.
- ⑩ ALL CATCHBASINS AS PER SD-024 UNLESS OTHERWISE NOTED.
- ⑪ PROPOSED CONCRETE SIDEWALK ON 100mm - 19mm DOWN LIMESTONE BASE.
- ⑫ 250mm - DR35 SEWER SERVICE.
- ⑬ 27m - 600mm - 1.6mm GAUGE CORRUGATED STEEL PIPE.
- ⑭ RAILROAD CROSSING AS PER SD-231A.
- ⑮ RAILROAD SIDEWALK CROSSING AS PER SD-231B.
- ⑯ PLACE SUITABLE SITE MATERIAL IN EXISTING DITCH AS PER COW 3170-14.
- ⑰ REMOVE EXISTING CULVERT.
- ⑱ LOWER EXISTING CULVERT TO INVERTS SHOWN AND EXTEND 2m S.

CAMEL SYS STREET

LOCATION APPROVED UNDERGROUND STRUCTURES		B.M.	DATE
NO.	ISSUED FOR BIDDING	30-005 ELEV. 233.321	F.B. 1988
0			

NO.	REVISIONS	DATE	BY
0	ISSUED FOR BIDDING	04.04.16	

WARDROP | Engineering Inc.

DESIGNED GMD	CHECKED BY
DRAWN GMD/MR4/PS	APPROVED BY
HOR. SCALE: 1 : 250	RELEASED FOR CONSTRUCTION
VERTICAL: 1 : 10	DATE

CONSULTANT DRAWING NO. 031294-01-00

Winnipeg THE CITY OF WINNIPEG
PLANNING, PROPERTY AND DEVELOPMENT

2004 SAINT BONIFACE INDUSTRIAL PARK ROADWORKS
CAMEL SYS STREET
STA. 6+50 TO STA. 8+00

APREGN
Certificate of Authorization
Wardrop Engineering Inc.
No. 195 Expiry: April 30, 2004

CITY DRAWING NUMBER	SHEET 5 OF 16
	C0005