



- CONSTRUCTION NOTES:
- 1 REMOVE AND DISPOSE OF EXISTING FENCE (INCIDENTAL).
 - 2 EXTEND BARRIER CURB, TIE INTO EXISTING CURB.
 - 3 REMOVE EXISTING TREES.
 - 4 SAWCUT EXISTING EDGE OF SLAB AS DIRECTED BY CONTRACT ADMINISTRATOR.
 - 5 BARRIER CURB TO MODIFIED BARRIER CURB TRANSITION.
 - 6 REMOVE EXISTING BERM.
 - 7 CONNECT TO EXISTING MANHOLE.
 - 8 ALL DIMENSIONS MEASURED TO BACK OF CURB.
 - 9 ADJUST ALL MANHOLES AND VALVES.
 - 10 ALL CATCHBASINS AS PER SD-024 UNLESS OTHERWISE NOTED.
 - 11 PROPOSED CONCRETE SIDEWALK ON 100mm - 19mm DOWN LIMESTONE BASE.
 - 12 250mm - DR35 SEWER SERVICE.
 - 13 27m - 800mm - 1.6mm GAUGE CORRUGATED STEEL PIPE.
 - 14 RAILROAD CROSSING AS PER SD-231A.
 - 15 RAILROAD SIDEWALK CROSSING AS PER SD-230 (PLANKING TO BE SUPPLIED AND INSTALLED BY CN).
 - 16 PLACE SUITABLE SITE MATERIAL IN EXISTING DITCH AS PER COW 3170-R4.
 - 17 REMOVE EXISTING CULVERT.
 - 18 LOWER EXISTING CULVERT TO INVERTS SHOWN AND EXTEND 2m S.

LOCATION APPROVED UNDERGROUND STRUCTURES

SUPPLY U/G STRUCTURES	DATE

REVISIONS

NO.	ISSUED FOR BIDDING	DATE	BY	DATE
0	ISSUED FOR BIDDING			

WARDROP Engineering Inc.

DESIGNED GMD	CHECKED BY
DRAWN GMD/MRA	APPROVED BY
HOR. SCALE: 1 : 250	RELEASED FOR CONSTRUCTION
VERTICAL: 1 : 10	

Winnipeg THE CITY OF WINNIPEG PLANNING, PROPERTY AND DEVELOPMENT

2004 SAINT BONIFACE INDUSTRIAL AREA ROADWORKS
CAMEL SYS STREET
STA. 12+50 TO STA. 14+00

CONSULTANT DRAWING NO. 031294-01-00

APEGIN Certificate of Authorization
Wardrop Engineering Inc.
No. 195 Expiry: April 30, 2004

CITY DRAWING NUMBER

SHEET	9	OF	16
C0009			