

PART E
SPECIFICATIONS

PART E - SPECIFICATIONS

GENERAL

E1. GENERAL

E1.1 These Specifications shall apply to the Work.

E2. GOODS

E2.1 The Contractor shall supply structural steel in accordance with the requirements hereinafter specified.

E2.2 Structural Steel shall conform to CSA Standard CAN/CSA-G40.20 and CAN/CSA-G40.21, Grade 300W and fabricated in accordance with CSA S16.1,

E2.3 Steel beams shall be W530X101 sections and each one shall measure 11.5 m in length.

E3. DELIVERY

E3.1 Goods shall be delivered within twenty-one (21) Calendar Days, f.o.b. destination, freight prepaid, to:

Water and Waste
598 Plinquet Street
Winnipeg, Manitoba

E3.2 The Contractor shall stack the structural steel at the location listed in Clause E3.1 as instructed by the Contract Administrator.

- (a) the Contractor shall supply all necessary equipment and labour to unload the structural steel;
- (b) the Contractor shall supply the material for stacking of the structural steel on skids, spacers, timbers or blocking, and it shall lie flat above the ground.