

PART E
SPECIFICATIONS

PART E - SPECIFICATIONS

GENERAL

E1. APPLICABLE SPECIFICATIONS, STANDARD DETAILS AND DRAWINGS

E1.1 *The City of Winnipeg Standard Construction Specifications* in its entirety, whether or not specifically listed on Form B: Prices, shall apply to the Work.

E1.1.1 *The City of Winnipeg Standard Construction Specifications* is available in Adobe Acrobat (.pdf) format on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division internet site at <http://www.winnipeg.ca/matmgt>.

E1.1.2 The version in effect three (3) Business Days before the Submission Deadline shall apply.

E1.1.3 Further to GC:2.4(d), Specifications included in the Bid Opportunity shall govern over *The City of Winnipeg Standard Construction Specifications*.

E1.2 The following Drawings are applicable to the Work:

Drawing No. Drawing

U212-04-01 McPhillips Underpass – Asphalt Resurfacing and Related Works

E2. TRAFFIC CONTROL

E2.1 General

The Contractor shall supply, erect, and maintain all applicable traffic control devices in accordance with the provision contained in the latest edition of the "Manual of Temporary Traffic Control in Work Areas on City Streets, 2003 Edition," issued by the City of Winnipeg.

E2.2 Construction Methods

No traffic lanes may be closed between the times of 06:30 to 09:00 hours and 15:30 to 17:30 hours except as follows: There will be no time restrictions for the closure of the northbound curb lane for the work in that lane. At least one lane in each direction must be maintained at all times.

E2.3 Measurement and Payment

The provision of traffic control will not be measured and will be paid for at the Contract Lump Sum Price for Traffic Control in accordance with this Specification, accepted by the Contract Administrator.

E3. PAVEMENT REMOVAL

E3.1 Further to Standard City of Winnipeg Specification CW 3110-R7, the pavement in the underpass is expected to be constructed of bricks with an asphalt overlay. No concrete pavement is expected. Therefore, the payment of pavement removal will be for brick and asphalt.