



- NOTES**
- CONTRACTOR TO LOCATE ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.
  - CONTRACTOR TO CONFIRM ALL DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.
  - CONTRACTOR TO STAKE OUT LOCATION OF ALL WORKS FOR APPROVAL BY CONTRACT ADMINISTRATOR AND CITY OF WINNIPEG PRIOR TO ANY CONSTRUCTION OR REMOVALS.
  - CONSTRUCTION ACCESS TO BE LIMITED TO THE ROUTES SPECIFIED ON SITE BY CONTRACT ADMINISTRATOR.
  - ALL DIMENSIONS ARE IN METRIC UNLESS OTHERWISE NOTED. DECIMAL NUMBERS INDICATE METERS.
  - CONTRACTOR TO REPAIR ALL ON AND OFF SITE SODDED AREAS, SHRUB BEDS, TREES, CONCRETE, ROAD PAVING AND CURBS ETC., DAMAGED DURING CONSTRUCTION TO CONTRACT ADMINISTRATOR'S SATISFACTION AND TO THE CITY OF WINNIPEG STANDARDS AT HIS OWN COST.
  - REFER ALSO TO WRITTEN SPECIFICATIONS.
  - REFER TO LAYOUT PLAN FOR LAYOUT OF ALL PATHWAYS, SODDED AREAS, PAVED AREAS, AND FENCING.
  - EXISTING TREES TO BE PROTECTED TO CITY OF WINNIPEG STANDARDS
  - IF POWER EQUIPMENT IS TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:
    - NOTIFY ALL UTILITIES OF THE PROPOSED
    - TAKE PRECAUTION TO AVOID DAMAGE TO ALL UTILITIES.

- LEGEND**
- 11. SLOPE TOLERANCES:
    - PATHWAY
      - MIN. CROSS SLOPE 1%
      - MAX. CROSS SLOPE 2%
      - MAX. LONGITUDINAL 5%
    - SODDED AREA
      - MIN. 1%
      - MAX. 25%
  - 12. DEPTH OF PLAYGROUND STONE VARIES FROM 235mm (EAST SIDE OF SWINGS) TO 365mm. THE MINIMUM DEPTH AT PLAYSTRUCTURE IS 250mm.
  - 13. MAINTAIN EXISTING GRADES WITHIN 2m RADIUS OF ALL EXISTING TREES.
  - 14. ABANDON EXISTING CATCH BASIN AND LDS. REFER TO SS1.

- EXISTING GRADE
- INTERPOLATED EXISTING GRADE
- EXISTING CATCH BASIN TO REMAIN
- EXISTING CATCH BASIN TO BE ABANDONED
- PROPOSED CATCH BASIN
- 31.000 PROPOSED GRADE
- 31.85 PROPOSED SUBGRADE AT PLAYGROUND
- T.C. TOP OF CURB
- B.C. BOTTOM OF CURB
- CB RIM CATCH BASIN RIM
- CB INV CATCH BASIN INVERT
- 1% DIRECTION DRAINAGE AND PERCENT SLOPE
- CENTRE LINE OF SWALE
- CURB
- WWS EXISTING WASTE WATER SEWER
- HYDRO HYDRO
- WM EXISTING WATER MAIN
- LDS EXISTING LDS
- GAS EXISTING GAS LINE
- WM PROPOSED WATER MAIN
- LDS PROPOSED LDS

1	ISSUED FOR TENDER	12/08/04	SR
No.	Revisions	Date	By
25-05-04		1:250	
Designed By	Drawn By	Checked By	
D.G.M.	K.R.	D.G.M.	



**APEGM**  
 Certificate of Authorization  
 Stantec Consulting Ltd.  
 No. 1301 Expiry: April 30, 2005

**McGOWAN RUSSELL**  
 Client  
 CITY OF WINNIPEG

**BURROWS CENTRAL  
 PARK RENOVATION  
 PROJECTS**



Sheet Title  
**BOYD PARK  
 SITE SERVICING PLAN**  
 Project No. 111207200 Drawing No. SS1