



- NOTE:**
- ALL MATERIALS & CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATION.
 - CONTRACTOR IS RESPONSIBLE FOR CONFIRMING LOCATION OF ALL UTILITIES PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
 - STORM SEWER PIPE TO BE PVC SDR-35, OR C-76-3 UNLESS OTHERWISE NOTED.
 - ALL 600 mm AND 450 mm STORM SEWER TO BE CORED, UNLESS OTHERWISE NOTED.
 - SAWCUT ALL ASPHALT AND CONCRETE AT LIMITS.
 - TRANSVERSE JOINT SPACING TO BE 5.0m EXCEPT WHERE SHOWN OTHERWISE.
 - CONTRACTOR TO PROTECT ALL SURVEY BARS FROM DAMAGE.

EXISTING LEGEND-PLAN		PROPOSED		EXISTING LEGEND-PLAN		PROPOSED	
WATERMAIN	HYDRANT	HP	HP	M.T.S.	HYDRO POLE		
LAND DRAINAGE SEWER	VALVE			PROPERTY LINE	BARRIER CURB		
WASTE WATER SEWER	MANHOLE			LIGHT STANDARD	CONCRETE SIDEWALK		
CATCH BASIN	CURB INLET			ASPHALT PAVEMENT	LIP CURB		
UTILITIES ADJUSTED	SUBDRAIN			200 REIN. CONC. PAV'T			
GAS							

LOCATIONS APPROVED UNDERGROUND STRUCTURES

CONTRACTOR TO RELOCATE FENCING & CONSTRUCT TEMPORARY STANDPIPE ACCESS/BYPASS ROUTE AT THE START OF THE PROJECT. PHASE 1 CHEVRIER ROADWORKS TO BE COMPLETED & STANDPIPE ACCESS RESTORED TO ORIGINAL CONDITION BEFORE CONTRACTOR SHALL BE ALLOWED TO PROCEED WITH REMAINDER OF ROADWORKS.

CONTRACTOR TO CONSTRUCT & MAINTAIN TEMPORARY GRAVEL ACCESS ROAD TO THE SATISFACTION OF THE CONTRACT ADMINISTRATOR.

TEMPORARILY RELOCATE FENCES DURING CHEVRIER ROAD CLOSURE TO MAINTAIN CONTINUOUS PUBLIC ACCESS TO STANDPIPE AT ALL TIMES. FENCES TO BE RESTORED TO ORIGINAL LOCATION AND IN AS GOOD OR BETTER CONDITION AFTER CONSTRUCTION.

NSLEA Engineers & Planners Inc.
 Suite 111-93 Lombard Avenue Winnipeg, Manitoba R3B 3B1
 Phone (204) 943-3178 Facsimile (204) 943-4948

DESIGNED BY **MS** CHECKED BY **KVC**
 DRAWN BY **MS** APPROVED BY **RMB**
 RELEASED FOR CONSTRUCTION

HOR. SCALE **1:250**
 VERTICAL **1:25**

DATE **JANUARY 23 2004**

K.S. VAN CAMP
 Member
 10351
 REGISTERED PROFESSIONAL ENGINEER

CONSULTANT ACAD DWG. NO.
41282-C-07

THE CITY OF WINNIPEG
 PUBLIC WORKS DEPARTMENT
 ENGINEERING SERVICES DIVISION

2004 LOCAL IMPROVEMENTS PROGRAM

PAVEMENT CONSTRUCTION
CHEVRIER BOULEVARD
 6+10.000 TO 7+50.000

CITY DRAWING NUMBER
 SHEET **7** OF **9**
 Bid Opportunity No.
65-2004