

PART E

SPECIFICATIONS

PART E - SPECIFICATIONS

GENERAL

E1. GENERAL

E1.1 These Specifications shall apply to the Work.

E2. GOODS

E2.1 The Contractor shall supply and deliver joint sealant (applied hot) in accordance with the requirements hereinafter specified.

E2.2 Item No. 1 – joint sealant (applied hot) shall be a **low modulus Type IV** material conforming to ASTM Standard 6690-01, Specification for Joint and Crack Sealants, Hot-Poured, for Concrete and Asphalt Pavements and with the City of Winnipeg Standard Construction Specifications, **CW3250-R6** and Approved Products for Surface Work.

E3. DELIVERY

E3.1 Goods shall be delivered on an "as required" basis during the term of the Contract, f.o.b. destination, freight prepaid to:

Public Works Department
Central Stores
1277 Pacific Ave.
Winnipeg, MB

E3.1.1 Goods shall be delivered within five (5) Business Days of the placing of an order, except where otherwise agreed at the time of ordering.

E3.2 Goods shall be delivered between 7:30 a.m. and 3:00 p.m. on Business Days.

E3.3 The Contractor shall deliver the joint sealant on pallets by flatbed trailer or truck.

E3.4 The Contract Administrator or his designate will advise the Contractor if they require delivery of a full or partial truckload on an open flatbed trailer or truck, the load shall be not exceed 18 pallets, each holding no more than 40 boxes/container.

E4. PACKAGING

E4.1 The joint sealant material shall be wrapped in polyethylene in 20 – 30 kilogram boxes supplied in rigid boxes/containers.

E4.2 The rigid box/containers shall consist of:

- (a) steel pails with lids; or
- (b) corrugated cardboard cartons, enclosed on all sides and designed and constructed to allow unsupported stacking to a height of 1.5 metres.

E4.3 The polyethylene inner wrapper shall be of a composition that will not adversely affect the operation of the melting equipment of the City.