




CP-H30A	Plant Master PLC Communication Panel				
Rev.	Comments	Jumper or Internal Cable	Conductor #	Cable	Cable Information
0	Plant Control Network Receive	PP2: 13	01	01	C-CP-H30A-C03 12-Strand 62.5/125 um Multi-mode TO CP-O11A
0	Plant Control Network Transmit	PP2: 14	02	02	
0	Spare		03	03	
0	Spare		04	04	
0	Spare		05	05	
0	Spare		06	06	
0	Spare		07	07	
0	Spare		08	08	
0	Spare		09	09	
0	Spare		10	10	
0	Spare		11	11	
0	Spare		12	12	
0	Plant Control Network Transmit	PP2: 01	13	01	C-CP-O11A-C01 12-Strand 62.5/125 um Multi-mode TO CP-O11A
0	Plant Control Network Receive	PP2: 02	14	02	
0	Spare		15	03	
0	Spare		16	04	
0	Spare		17	05	
0	Spare		18	06	
0	Spare		19	07	
0	Spare		20	08	
0	Spare		21	09	
0	Spare		22	10	
0	Spare		23	11	
0	Spare		24	12	

NOTES:  <p>Certificate of Authorization Earth Tech Canada Inc. No. 730 Expiry: April 30, 2006.</p>	B.M. ELEV.			 		ENGINEER'S SEAL		THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION	
				DESIGNED BY	SWT	CHECKED BY	SWT		
				DRAWN BY	SWT	APPROVED BY	AHL	WATER TREATMENT PLANT PLANT UTILITIES MECHANICAL AND ELECTRICAL	
				SCALE: NTS		RELEASED FOR CONSTRUCTION BY: R. SOROKOWSKI		CITY FILE NUMBER SHEET 12 OF 88	
	NO. REVISIONS			DATE	BY	DATE	2006/03/29	DATE	2006/03/29