




LCP-P35 DAF Basin 5 VFD Control Panel							
Comments	Jumper or Internal Cable	Conductor #	Cable	Cable Information			
				Switch 1			
Floculator FLC-P501A	RJ-45 To Floculator FLC-P501A	01					
Floculator FLC-P502A	RJ-45 To Floculator FLC-P502A	02					
Floculator FLC-P503A	RJ-45 To Floculator FLC-P503A	03					
Floculator FLC-P504A	RJ-45 To Floculator FLC-P504A	04					
Floculator FLC-P505A	RJ-45 To Floculator FLC-P505A	05					
Floculator FLC-P506A	RJ-45 To Floculator FLC-P506A	06					
Skimmer DF-P500A	RJ-45 To Skimmer DF-P500A	07					
		08	RJ-45	C-LCP-P35-C01	4-Pair #24 AWG - Cat 5E TO CP-P32		

NOTES: 1. Panel Supplied by the City.	B.M. ELEV.			 		ENGINEER'S SEAL		<b>THE CITY OF WINNIPEG</b> <b>WATER AND WASTE DEPARTMENT</b> <b>ENGINEERING DIVISION</b>				
				DESIGNED BY	SWT	CHECKED BY	SWT			WATER TREATMENT PLANT PLANT UTILITIES MECHANICAL AND ELECTRICAL		
				DRAWN BY	SWT	APPROVED BY	AHL	CITY FILE NUMBER				
				SCALE: <b>NTS</b>		RELEASED FOR CONSTRUCTION BY:	R. SOROKOWSKI	SHEET 52 OF 63				
	 Certificate of Authorization Earth Tech Canada Inc. No. 730 Expiry: April 30, 2006.			0	ISSUED FOR TENDER	06/03/29	SWT	CITY DRAWING NUMBER 1-0601H-J-A0552-001-00B				
			NO.	REVISIONS	DATE	BY	DATE	2006/03/29	DATE	2006/03/29	AUTOMATION / I AND C PLANT COMMUNICATION CABLE TERMINATION DIAGRAMS	
							CONSULTANT DRAWING NO.		WH-A0552			

Monday, April 03, 2006