



COLUMN SCHEDULE	
MARK	DESCRIPTION
P1	3-2x4 P.T. BUILT-UP POST (SEE TYPICAL POST BASE DETAIL) 1 1/4"
P2	3-2x6 P.T. BUILT-UP POST (SEE TYPICAL POST BASE DETAIL) 1 1/4"

BUILDING PLAN
1/8" = 1'-0"

NOTE: - ALL LUMBER SHALL BE PRESSURE TREATED
- ALL PLYWOOD SHALL BE EXTERIOR GRADE PRESSURE TREATED
- ALL EXPOSED WOOD CONSTRUCTION SHALL RECEIVE TWO COATS ACRYLIC LATEX PAINT. COLOUR TO BE SELECTED BY OWNER.

BEAM SCHEDULE	
MARK	DESCRIPTION
B1	2-2x12 P.T. BUILT-UP BEAM
B2	3 1/2" WIDE x 11 7/8" HIGH 2.0E PSL PARALLAM BEAM (TREATED)

No.	Date	Revisions	By
3	FEB 14, 2006	RE-ISSUED FOR TENDER	BF
2	FEB 10, 2006	RE-ISSUED FOR TENDER	BF
1	FEB 6, 2006	ISSUED FOR TENDER	BF

APEGM
Certificate of Authorization
Crosier Kilgour & Partners Ltd.
No. 235 Expiry: April 30, 2006

PROVINCE OF MANITOBA
B. FLISAK
Member
22454
REGISTERED PROFESSIONAL ENGINEER

CROSIER KILGOUR & PARTNERS LTD.
Consulting Structural Engineers
300-275 Carlton Street, Winnipeg, MB R3C 5R6
Tel: (204) 943-7501 Fax: (204) 943-7507

The Contractor shall check & verify all dimensions and shall report any errors or omissions to the Contract Administrator.

Project PUBLIC SAFETY BUILDING TEMPORARY PEDESTRIAN WALKWAY ENCLOSURE WINNIPEG, MANITOBA						Sheet No. S-1
Drawing Title BUILDING PLAN						
Design BF	Drawn JMN	Checked BF	Scale AS NOTED	Date FEB 6, 2006	File 2006-0031	

