



**SCOPE OF WORK**

SCOPE OF WORK TO INCLUDE THE FOLLOWING WORK ITEMS:

1. Removal and salvage existing metal handrail c/w balusters & supports - shall be modified to suit new location.
2. Remove existing ceiling mounted Exit Light and replace with new LED Type Exit Light to location designated by the Contract Administrator.
3. Removal and disposal of existing interior aluminum framing, glazing, glazing components, aluminum doors and hardware.
4. Remove and relocate existing force flow unit heater in Vestibule.
5. Remove and relocate 2 existing Telephone stations.
6. Removal and disposal of existing exterior window base.
7. Removal and disposal of existing exterior aluminum framing, glazing and components.
8. Remove existing wood blocking beneath exterior door threshold - supply and install new pressure treated wood blocking to suit (caulk & make watertight seal).
9. Removal and disposal of existing exterior aluminum manual/automatic doors, glazing and hardware.
10. Remove existing metal bench and turn over to City of Winnipeg.
11. Remove and relocate existing recessed speaker in ceiling panels.
12. Supply and install new recessed speaker to match existing.
13. Remove existing water fountain and turn over to City of Winnipeg.
14. Remove and relocate existing Fire Alarm Pull Station.
15. Remove and relocate existing junction box in wall.
16. Removal of existing 2 x 4 ceiling panels - replace with new acoustical ceiling panels (white colour) into existing ceiling grid system. Existing suspended ceiling grid system to be washed, cleaned and replaced if damaged during construction.

**DEMOLITION PLAN**  
NOT TO SCALE

PAN AM POOL 25 POSEIDON BAY WINNIPEG, MANITOBA		A1
DATE: april 10, 2006	SCALE: NTS	
DEMOLITION PLAN		

 <b>Winnipeg</b> <i>Embrace the Spirit - Vivez l'esprit</i>	<b>THE CITY OF WINNIPEG</b> PUBLIC WORKS DEPARTMENT BUILDING SERVICES DIVISION 100 MAIN STREET WINNIPEG, MANITOBA R3C 1A4 PHONE: (204) 986-7266 FAX: (204) 986-7311
---	--