



FOR CONTINUATION
SEE DRAWING SP0.01

DRAWING NOTES

- 1 REMOVE EXISTING WAS PUMPS, PIPING AND ALL APPURTENANCES AS MARKED.
- 2 REMOVE EXISTING RAS PUMPS. MODIFY CONCRETE PADS TO SUIT NEW PUMPS.
- 3 REMOVE RAS PIPING AND ALL APPURTENANCES AS MARKED.
- 4 REMOVE AND REPLACE EXISTING FLUSHING WATER PUMP, MODIFY PUMP BASE AND PIPING CONNECTIONS AS REQUIRED FOR NEW PUMP.
- 5 CAP WAS & SCUM LINES INSIDE PUMP ROOM.
- 6 REMOVE EXISTING SCUM PUMPS, PIPING AND ALL APPURTENANCES AS MARKED.
- 7 REMOVE EXISTING 900# MIXED LIQUOR PIPING, VALVE AND FITTINGS AS MARKED. REFER TO FIGURE A ON DRAWING SP2.09
- 8 SHORE EXISTING FRP DOME AS REQUIRED DURING REMOVAL AND REPLACEMENT OF CLARIFIER MECHANISM.

DEMOLITION PLAN
1:100



B.M. ELEV.	NO.	REVISIONS	DATE	BY
	00	ISSUED FOR TENDER	06/04/26	PJY

 A Tyco International Ltd. Company		DESIGNED BY: KS	CHECKED BY: KM
		DRAWN BY: PJY	APPROVED BY: JEH
HOR. SCALE: 1:100 VERTICAL SCALE:		RELEASED FOR CONSTRUCTION BY: J. VEILLEUX	
DATE: 2005/10/06		DATE: 2006/04/26	

ENGINEER'S SEAL
ORIGINAL SIGNED BY
J.E. HUTCHISON
2006/04/26
CONSULTANT DRAWING NO.
SP0.02

THE CITY OF WINNIPEG
 WATER AND WASTE DEPARTMENT
 ENGINEERING DIVISION

WEWPC
 BIOLOGICAL NUTRIENT REMOVAL UPGRADE
 CONTRACT 3

PROCESS
 AREA S - SECONDARY CLARIFIERS
 LOWER LEVEL DEMOLITION PLAN

CITY FILE NUMBER
 SHEET OF
 CITY DRAWING NUMBER