

**FORM A: BID**  
(See B8)

1. Project Title PLAYGROUND REDEVELOPMENT AT VERBENA PARK AND PRIMROSE PARK

2. Bidder

\_\_\_\_\_  
Name of Bidder

\_\_\_\_\_  
Street

\_\_\_\_\_  
City

\_\_\_\_\_  
Province

\_\_\_\_\_  
Postal Code

\_\_\_\_\_  
Facsimile Number

(Mailing address if different)

\_\_\_\_\_  
Street or P.O. Box

\_\_\_\_\_  
City

\_\_\_\_\_  
Province

\_\_\_\_\_  
Postal Code

The Bidder is:

(Choose one)

a sole proprietor

a partnership

a corporation

carrying on business under the above name.

3. Contact Person

The Bidder hereby authorizes the following contact person to represent the Bidder for purposes of the Bid.

\_\_\_\_\_  
Contact Person

\_\_\_\_\_  
Title

\_\_\_\_\_  
Telephone Number

\_\_\_\_\_  
Facsimile Number

4. Definitions

All capitalized terms used in the Contract shall have the meanings ascribed to them in the General Conditions

5. Offer

The Bidder hereby offers to perform the Work in accordance with the Contract for the Total Bid Price, in Canadian funds, set out on Form B: Prices, appended hereto.

Template Version: C320050301

6. Commencement of the Work      The Bidder agrees that no Work shall commence until he is in receipt of a Purchase Order from the Award Authority authorizing the commencement of the Work.

7. Contract      The Bidder agrees that the Bid Opportunity in its entirety shall be deemed to be incorporated in and to form a part of this offer notwithstanding that not all parts thereof are necessarily attached to or accompany this Bid Submission.

8. Addenda      The Bidder certifies that the following addenda have been received and agrees that they shall be deemed to form a part of the Contract:

No.	Dated
_____	_____
_____	_____
_____	_____

9. Time      This offer shall be open for acceptance, binding and irrevocable for a period of thirty (30) Calendar Days following the Submission Deadline.

10. Signatures      In witness whereof the Bidder or the Bidder's authorized official or officials have signed this

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

Signature of Bidder or  
Bidder's Authorized Official or Officials

\_\_\_\_\_  
(Print here name and official capacity of individual whose signature appears above)

\_\_\_\_\_  
(Print here name and official capacity of individual whose signature appears above)

**FORM B: PRICES**  
 (See B9)

PLAYGROUND REDEVELOPMENT AT VERBENA PARK AND PRIMROSE PARK

**ALTERNATIVE 1 – AWARD AS A WHOLE**  
 UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT OF MEASURE	APPROX. QUANTITY	UNIT PRICE (Unit Price per UNIT OF MEASURE indicated)
<b>SECTION A: PRIMROSE PARK</b>					
<b>A1: North Swing Set</b>					
1.	Site Excavation - Excavate for new play area to depth of 100 mm	E9	CM	12	_____
2.	Supply and Install concrete edging	E12	LM	40	_____
3.	Supply and Install play stone (250 mm depth)	E13	CM	28	_____
<b>A2: New South Play Area</b>					
4.	Remove and dispose existing swing set and existing safety surfacing below snail climber	E8	LS	1	_____
5.	Supply and install topsoil (75 mm) and sodding at the existing swing area	E16	SM	60	_____
6.	Site Excavation - Excavate for new play area to depth of 100 mm	E9	CM	17	_____
7.	Supply and Install concrete edging	E12	LM	56	_____
8.	Supply and Install play stone (250 mm depth)	E13	CM	40	_____
<b>A3: Site Work</b>					
9.	Remove and dispose existing concrete path	E8	SM	142	_____
10.	Supply and install new 1.95 M wide gravel path	E10	SM	215	_____
11.	Supply and install topsoil (75 mm) and sodding at the removed path	E16	SM	74	_____
12.	Supply and install topsoil (75 mm) and seeding around the concrete edging	E17	SM	40	_____
13.	Restore the existing sand box and add sand	E14	LS	1	_____
14.	Supply and install "Tache" style backless bench with the anchor	E15	EA	1	_____
15.	Supply and install Ornamental Metal slat waste receptacle. SCD-119	E15	EA	1	_____
16.	Supply and Install American Basswood (65 mm Cal.)	E18	EA	5	_____
17.	Annual tree maintenance	E19	Year	2	_____

Name of Bidder \_\_\_\_\_

**FORM B: PRICES**  
 (See B9)

PLAYGROUND REDEVELOPMENT AT VERBENA PARK AND PRIMROSE PARK

**ALTERNATIVE 1 – AWARD AS A WHOLE**  
 UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT OF MEASURE	APPROX. QUANTITY	UNIT PRICE (Unit Price per UNIT OF MEASURE indicated)
<b>SECTION A: PRIMROSE PARK continued</b>					
<b>A4: Play Equipment</b>					
18.	Supply and install 2.1 to 2.4 M two bay swing set with two baby seats and two senior seats	E20	EA	1	_____
19.	Supply and install new Kompan “Moments-Zaggy” spring rider	E20	EA	1	_____
<b>SECTION B: VERBENA PARK</b>					
<b>B1: Site Work</b>					
20.	Remove and dispose of existing play sand (200 mm depth)	E8	CM	69	_____
21.	Remove and dispose of existing timber edging	E8	LM	84	_____
22.	Supply and Install play stone (250 mm depth)	E13	CM	58	_____
23.	Supply and Install concrete edging	E12	LM	65	_____
24.	Supply and install topsoil (75 mm) and sodding over the excavated area	E16	SM	127	_____
25.	Asphalt repairs at the excavated area	E11	SM	4	_____
26.	Restore the existing sand box and add sand	E14	EA	1	_____
27.	Supply and install “Tache” style picnic table with gravel base and the anchor	E15	EA	1	_____
28.	Supply and install deciduous trees:				
	a. American Basswood (65 mm Cal.)	E18	EA	5	_____
	b. Amur chokecherry (65 mm Cal.)	E18	EA	2	_____
29.	Supply and install coniferous trees:				
	a. Colorado Spruce (1.5 M)	E18	EA	3	_____
30.	Annual tree maintenance	E19	Year	2	_____
<b>B2: Play Equipment</b>					
31.	Supply and install 1.5 M tall metal slide	E20	EA	1	_____
32.	Supply and install Kompan “Elements-Stinger” spring rider	E20	EA	1	_____
33.	Supply and install Kompan “Elements-Navigator”	E20	EA	1	_____

Name of Bidder \_\_\_\_\_

**FORM B: PRICES**  
 (See B9)

PLAYGROUND REDEVELOPMENT AT VERBENA PARK AND PRIMROSE PARK

**ALTERNATIVE 2- AWARD BY SECTION**

UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT OF MEASURE	APPROX. QUANTITY	UNIT PRICE (Unit Price per UNIT OF MEASURE indicated)
<b>SECTION A: PRIMROSE PARK</b>					
<b>A1: North Swing Set</b>					
1.	Site Excavation- Excavate for new play area to depth of 100 mm	E9	CM	12	_____
2.	Supply and Install concrete edging	E12	LM	40	_____
3.	Supply and Install play stone (250 mm depth)	E13	CM	28	_____
<b>A2: New South Play Area</b>					
4.	Remove and dispose existing swing set and existing safety surfacing around snail climber	E8	LS	1	_____
5.	Supply and install topsoil (75 mm) and sodding at the existing swing area	E16	SM	60	_____
6.	Site Excavation-Excavate for new play area to depth of 100 mm	E9	CM	17	_____
7.	Supply and Install concrete edging	E12	LM	56	_____
8.	Supply and Install play stone (250 mm depth)	E13	CM	40	_____
<b>A3: Site Work</b>					
9.	Remove and dispose existing concrete path	E8	SM	142	_____
10.	Supply and install new 1.95 M wide gravel path	E10	SM	215	_____
11.	Supply and install topsoil (75 mm) and sodding at the removed path	E16	SM	74	_____
12.	Supply and install topsoil (75 mm) and seeding around the concrete edging	E17	SM	40	_____
13.	Restore the existing sand box and add sand	E14	LS	1	_____
14.	Supply and install "Tache" style backless bench with the anchor	E15	EA	1	_____
15.	Supply and install Ornamental Metal slat waste receptacle. SCD-119	E15	EA	1	_____

Name of Bidder \_\_\_\_\_

**FORM B: PRICES**  
 (See B9)

PLAYGROUND REDEVELOPMENT AT VERBENA PARK AND PRIMROSE PARK

**ALTERNATIVE 2- AWARD BY SECTION**

UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT OF MEASURE	APPROX. QUANTITY	UNIT PRICE (Unit Price per UNIT OF MEASURE indicated)
<b>SECTION A: PRIMROSE PARK continued</b>					
<b>A3: Site Work continued</b>					
16.	Supply and Install American Basswood (65 mm Cal.)	E18	EA	5	_____
17.	Annual tree maintenance	E19	Year	2	_____
<b>A4: Play Equipment</b>					
18.	Supply and install 2.1 to 2.4 M two bay swing set with two baby seats and two senior seats	E20	EA	1	_____
19.	Supply and install new Kompan "Moments-Zaggy" spring rider	E20	EA	1	_____

Name of Bidder \_\_\_\_\_

**FORM B: PRICES**  
 (See B9)

PLAYGROUND REDEVELOPMENT AT VERBENA PARK AND PRIMROSE PARK

**ALTERNATIVE 2- AWARD BY SECTION**

UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT OF MEASURE	APPROX. QUANTITY	UNIT PRICE (Unit Price per UNIT OF MEASURE indicated)
<b>SECTION B: VERBENA PARK</b>					
<b>B1: Site Work</b>					
20.	Remove and dispose of existing play sand (200 mm depth)	E8	CM	69	_____
21.	Remove and dispose of existing timber edging	E8	LM	84	_____
22.	Supply and Install play stone (250 mm depth)	E13	CM	58	_____
23.	Supply and Install concrete edging	E12	LM	65	_____
24.	Supply and install topsoil (75 mm) and sodding over the excavated area	E16	SM	127	_____
25.	Asphalt repairs at the excavated area	E11	SM	4	_____
26.	Restore the existing sand box and add sand	E14	EA	1	_____
27.	Supply and install "Tache" style picnic table with gravel base and the anchor	E15	EA	1	_____
28.	Supply and install deciduous trees				
	a. American Basswood (65 mm Cal.)	E18	EA	5	_____
	b. Amur chokecherry (65 mm Cal.)	E18	EA	2	_____
29.	Supply and install coniferous trees:				
	a. Colorado Spruce (1.5 M)	E18	EA	3	_____
30.	Annual tree maintenance	E19	Year	2	_____
<b>B2: Play Equipment</b>					
31.	Supply and install 1.5 M tall metal slide	E20	EA	1	_____
32.	Supply and install Kompan "Elements-Stinger" spring rider	E20	EA	1	_____
33.	Supply and install Kompan "Elements-Navigator"	E20	EA	1	_____

Name of Bidder \_\_\_\_\_