



- NOTES:**
- COORDINATE EXACT OPENING SIZE WITH SUPPLIER OF WEIR GATE. REFER TO DETAIL 1 ON DRAWING P14.03.
 - COORDINATE EXACT PENETRATION SIZE AND LOCATION WITH SUPPLIER OF DECANTERS. (PROVIDE SEAL TO SUIT)
 - ADJUST SUPPORT TO PROVIDE 100 TO 150 mm CLEAR SPACE BETWEEN MET PIPE AND FINISHED SBR ROOF.
 - PROVIDE FLEXIBLE CONNECTION ON EACH ELBOW.
 - REFER TO STRUCTURAL DRAWINGS FOR HATCH DETAILS.

<p>Certificate of Authorization Earth Tech Canada Inc. No. 730 Expiry: April 30, 2007</p>	B.M. ELEV.	<p>A Tyco International Ltd. Company</p>	ENGINEER'S SEAL	<p>THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION</p>	
			DESIGNED BY: YL		ORIGINAL SIGNED BY: J.E. HUTCHISON
			DRAWN BY: SRP		2006/05/15
			SCALE: 1:125		CONSULTANT DRAWING NO. P13.02
	NO. REVISIONS	DATE BY	RELEASED FOR CONSTRUCTION BY: K. MARTENS	CITY FILE NUMBER	
	00 ISSUED FOR TENDER	06/05/15 GLG	DATE 2006/01/16	DATE 2006/05/15	SHEET OF
					CITY DRAWING NUMBER
					PROCESS PROCESS TANKS MAIN LEVEL PLAN