



**NOTE:**  
OIL AND GAS RESISTANT  
GASKETS TO BE USED  
ON ST. ANNE'S RENEWAL

ADDRESS & SERVICE	SIZE (mm) & TYPE (STREET)	STOP COCK SHORT & LONG MEASUREMENT	CORPORATION LOCATION	REMARKS
200 ST. ANNE'S ROAD RESIDENTIAL	20 COPPER	3.51m NSL BUILDING	OFF S/C	REPAIRED JAN/02
208 ST. ANNE'S ROAD COMMERCIAL	50 COPPER	4.95 mSL INMAN	N/A	
215 ST. ANNE'S ROAD COMMERCIAL	50 N/A	6.31m NSL BUILDING	N/A	
258 ST. ANNE'S ROAD COMMERCIAL	50 COPPER	37.19m SSL KINGSWOOD	N/A	
258 ST. ANNE'S ROAD COMMERCIAL	50 COPPER	1.2m SSL BUILDING	N/A	
258 ST. ANNE'S ROAD COMMERCIAL	50 COPPER	1.46m SSL INMAN	N/A	

- CONSTRUCTION NOTES:**
- EXPOSE EXISTING WATERMAIN AND CONFIRM INVERTS PRIOR TO CONSTRUCTION.
  - CONFIRM LOCATION OF ALL SERVICES.
  - INSTALL WATERMAIN BY TRENCHLESS METHODS.
  - TRENCHES AND EXCAVATIONS WITHIN 1 METER OF PAVED AREAS SHALL BE CLASS 3 BACKFILL.
  - ALL MATERIALS SHALL CONFORM TO CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
  - MINIMUM COVER SHALL BE 2.4m.
  - REPLACE ALL EXISTING LEAD SERVICES FROM PROPOSED MAIN TO PL.
  - NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY WATER SHUTDOWNS OR DISRUPTIONS OF SERVICE.
  - ALL LARGE DIAMETER WATER SERVICES CONNECTIONS SHALL BE SUPPLIED WITH MIN. 38 mm TEMPORARY SERVICE CONNECTIONS.
  - LAMP STANDARDS, UTILITY POLES AND ANCHORS IN CONFLICT WITH PROPOSED WATERMAIN INSTALLATION MAY REQUIRE TEMPORARY SUPPORT/REMOVAL OR REPLACEMENT AT THE CONTRACTOR'S EXPENSE.



**WARNING**

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:  
1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.  
2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.  
SEE PROVINCIAL REGULATION 140/92 FOR DETAILS

**NOTE:**  
STATIONS ALONG WEST R. OF ST. ANNE'S ROAD

Bench Mark N.E. Cor. St. Anne's Rd. & Bank Ave., Tblt. in W. Conc. foundation of St. Vital Baptist Church, 1.0 m N. & 0.1 m below brick of S.W. Cor. of Bldg.

150_WM	WATERMAIN	150_WM	HYDRO	150_WM	WATERMAIN	150_WM
⊕	HYDRANT	⊕	M.T.S.	⊕	HYDRANT, VALVE	⊕
⊙	VALVE	⊙	CONCRETE	⊙	LAND DRAINAGE SEWER	⊙
⊖	LAND DRAINAGE SEWER	⊖	ASPHALT	⊖	WASTE WATER SEWER	⊖
⊗	WASTE WATER SEWER	⊗	SIDEWALK	⊗	EX. GROUND PROFILE	⊗
○	MANHOLE	○	PROPERTY LINE	□	NORTH OR WEST GUTTER	□
□	CATCH BASIN	□	SURVEY BAR	○	SOUTH OR EAST GUTTER	○
▽	CURB INLET	▽	DITCH	◇	NORTH OR WEST R.	◇
+	JUNCTIONS	+	ELEVATION	◇	SOUTH OR EAST R.	◇
○	SIGN	○	CURB STOP	△	NORTH OR WEST DITCH	△
○	GAS	○	ANODE	△	SOUTH OR EAST DITCH	△
---	EXISTING	---	LEGEND-PLAN	---	LEGEND-PROFILE	---

**LOCATION APPROVED UNDERGROUND STRUCTURES**

SUPV. U/G STRUCTURES COMMITTEE DATE

**NOTE:**  
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

NO.	REVISIONS	DATE	BY

**Stantec Consulting Ltd.**  
905 Waverley Street, Winnipeg, Manitoba  
Tel 204-489-5900 Fax 204-453-9012

DESIGNED BY: JKH  
CHECKED BY: WWB  
DRAWN BY: JKH  
APPROVED BY: HAK

HOR. SCALE: 1:250  
VERTICAL: 1:50

RELEASED FOR CONSTRUCTION: DATE

NO. REVISIONS DATE BY DATE 06.06.01

ENGINEER'S SEAL

ORIGINAL SEALED BY H.A. KATZ P. ENG. 06/02/06

CONSULTANT DRAWING NO. C-209

**THE CITY OF WINNIPEG**  
WATER AND WASTE DEPARTMENT  
ENGINEERING DIVISION

**2006 WATERMAIN RENEWALS**  
ST. ANNE'S ROAD  
INMAN AVE TO CRYSTAL AVE  
STA 0+77 TO STA 2+00

SHEET 9 OF 11  
CAD FILE DRAWING NUMBER 0910C-209675.dwg  
CITY DRAWING NUMBER D-9032

V:\1110\Drawings\11100010\Drawings\11100010.dwg By: jphs 2006-06-05 01:04PM