

PART 1 GENERAL

- .1 This section specifies requirements for demolishing, salvaging and removing wholly or in part, various items designated to be removed or partially removed and for backfilling resulting trenched, holes, and pits.
- 1.1 Related Sections
 - .1 Excavating, Trenching and Backfilling Section 31 23 16
- 1.2 Protection
 - .1 Protect existing objects designated to remain and materials designated for salvage. In event of damage immediately replace or make repairs subject to the Contract Administrator's approval of and at no additional cost to the project.

PART 2 PRODUCTS

- 2.1 Not Used
 - .1 Not used.

PART 3 EXECUTION

- 3.1 Preparation
 - .1 Inspect site and verify with Contract Administrator objects designated for removal and objects to be preserved.
 - .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.
- 3.2 Removal
 - .1 Remove objects, including trees indicated on the drawing.
 - .2 Do not disturb adjacent items designated to remain in place.
 - .3 In removal of pavements, curbs and gutters:
 - .1 Square up adjacent surfaces to remain in place by saw cutting or other approved method.
 - .2 Protect adjacent joints and load transfer devices.
 - .3 Protect underlying granular materials.
 - .4 When removing pipes under existing or future pavement area, excavate at least 300 mm below pipe level.
 - .5 Provide for suppression of dust generated by removal process.
- 3.3 Disposal of Material
 - .1 Dispose of materials not designated for salvage or re-use in Work, off site.
- 3.4 Backfill
 - .1 In paved area, backfill with granular material and shape excavation to elevations shown on the drawings in accordance with Section 31 23 16.
 - .2 In areas not to be paved, backfill and shape excavation to elevation shown on drawings with common backfill approved by Contract Administrator and in accordance with Section 31 23 16.

- 3.5 Restoration
 - .1 Upon completion of Work, remove debris, trim surfaces and leave Work site clean.
 - .2 Reinstate areas and existing Works outside areas of demolition to conditions that existed prior to commencement of Work.