



Rev.	Comments	Jumper or Internal Cable	Conductor #	Cable	Cable Information	
0	Local Operator Workstation		01	RJ-45	C-WTPWST11 01-C01	4-Pair #24 AWG - Cat 5E TO WTPWST11 01
0	Spare		02			
0	Spare		03			
0	Spare		04			
0	Spare		05			
0	Spare		06			
2	Plant Monitoring Network	PP1: 05, 06	07-Sx			
2	Plant Monitoring Network	PP1: 30, 29	08-Sx			
2	Spare		09			
2	Spare		10			
2	Spare		11			
2	Spare		12			
2	Spare		13			
2	Spare		14			
2	Spare		15			
2	Spare		16			
2	Spare		17			
2	Spare		18			
2	Spare		19			

NOTES:
 1. Panel and Cabling are not in Contract 742-2005. Drawing Issued for Information Only.
 2. Panel and Cabling are in Contract 498-2006.



APEGM
 Certificate of Authorization
 Earth Tech Canada Inc.
 No. 730 Expiry: April 30, 2006.

B.M.	ELEV.			
5	498-2006 ADDENDUM 6	06/10/13	BT	
4	498-2006 ADDENDUM 2	06/09/22	BT	
3	FOR CONSTRUCTION	06/07/28	BT	
2	GENERAL REVISIONS	06/07/13	BT	
1	742-2005 ADDENDUM 6	06/05/29	SWT	
0	ISSUED FOR TENDER	06/03/29	SWT	
NO.	REVISIONS	DATE	BY	

DESIGNED BY	SWT	CHECKED BY	SWT
DRAWN BY	SWT	APPROVED BY	AHL
SCALE:		RELEASED FOR CONSTRUCTION BY:	
NTS		R. SOROKOWSKI	
DATE	2006/03/29	DATE	2006/03/29

ENGINEER'S SEAL

ORIGINAL SIGNED BY
 S.W. TORMEY
 2006/03/29

CONSULTANT DRAWING NO.
 WH-A0622

THE CITY OF WINNIPEG

WATER AND WASTE DEPARTMENT

ENGINEERING DIVISION

WATER TREATMENT PLANT PLANT UTILITIES MECHANICAL AND ELECTRICAL	CITY FILE NUMBER
	SHEET 122 OF 130
AUTOMATION / I AND C PLANT COMMUNICATION CABLE TERMINATION DIAGRAMS	CITY DRAWING NUMBER
	1-0601H-J-A0622-001-05B