



565-2006 ADDENDUM 1

NORTHWOOD COMMUNITY CENTRE FIELD REHABILITATION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: September 22, 2006
BY: Jurgen Friesen
TELEPHONE NO. (204) 986-3781

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20060821

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 565-2006 Bid Submission with 565-2006 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B (R1): Add Item No. 4. – Concrete Boxes

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, September 28, 2006.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D10.1 to read The Contractor shall achieve Substantial Performance By June 25, 2007.

Revise D11.1 to read The Contractor shall achieve Total Performance By July 1, 2007.

PART E – SPECIFICATIONS

Revise: E12.1 (a)(i) to read: Approximately 62 lineal metres of existing **concrete** sidewalk located on the east perimeter of Work Site between school additions and as shown on the drawings.

Add: E13.1 (c) Topsoil and Sod will also include any grading work required to bring finished sod elevations to finished design elevations.

Add: E13.3 (g) Condition and preparation of existing grade will include removal of all weeds and turf that already has established in the interim.

Add: E18.0 **Concrete Boxes**

Add: E18.1 Description

(a) Concrete Boxes will be supplied and installed around all vented areas of the building as shown on the drawings. Concrete boxes will be non-reinforced and measure 600 mm (2') x 600 mm (2') x 300 mm (1') – 150 mm thick. Concrete curb boxes will be supplied and installed in the location and to design elevation as shown on the drawings. Concrete boxes will be placed on a 100 (4") mm base of 20 mm (3/4") crushed limestone down.

(b) Concrete curb boxes will be done in accordance with City of Winnipeg Standard Construction Specification CW 3310 – R8 “ Portland Cement Concrete Pavement Works.

Add: **E18.2 Materials**

(a) As specified in CW 3310-R8

Add: **E18.3 Construction Methods**

(a) As specified in CW 3310-R8

Add: **E18.4 Measurement and Payment**

(a) Measurement and Payment for concrete boxes will be on a per unit basis paid for at the Contract Unit Price for “Concrete Boxes”. Price will be payment in full for supplying all materials and performing all operation herein described all other items incidental to the Work included in this Specification.

DRAWINGS

Replace: Drawing N10-Q with Drawing N10-Q_R1