


1 POOL EQUIPMENT ROOM PARTIAL PLAN
M-1 SCALE: 3/8" = 1'-0"

KEY NOTES

- 1 SEE SCHEMATICS AND ELEVATION FOR PIPING DETAILS.
- 2 CONTRACTOR TO INCREASE SIZE OF EXISTING CONCRETE PAD TO ACCOMMODATE NEW BOILERS. NEW PAD ELEVATION TO BE 12" ABOVE FLOOR. CONCRETE TO HAVE 28-DAY COMPRESSIVE STRENGTH OF AT LEAST 20 MPA. DOWEL INTO THE EXISTING FLOOR WITH 10 M DOWELS, EPOXY GROUTED, APPROXIMATELY 18" ON CENTRE. REINFORCE THE PAD WITH 6" X 6" WELDED WIRE MESH.
- 3 DISCONNECT, REMOVE AND DISPOSE OF THE EXISTING POOL HEATERS. LOCATE BOILERS IN APPROXIMATELY THE SAME LOCATION AS OLD BOILERS. SPACING AND LOCATION OF BOILERS SHALL FACILITATE MAINTENANCE, INCLUDING REMOVAL OF BOILER ELEMENTS.
- 4 3" EXISTING PVC PIPING TO POOL. DISCONNECT AND REMOVE ALL EXISTING PIPING WHERE NEW PIPING IS SHOWN.
- 5 NEW PVC PIPING. CONNECT TO CLOSEST EXISTING PIPE AND DROP TO CONNECT TO HX-1 (SEE ELEVATION AND SCHEMATIC).



0 07-06-11 FOR TENDER & CONSTRUCTION

No. DATE ISSUANCE



APEGM
Certificate of Authorization
Epp Siepman Engineering Inc.
No. 4035 Date: 2007-06-11

epp siepman engineering inc.
mechanical engineers
303-100 Osborne St. South p 204.453.1080
Winnipeg, MB f 204.453.1335
R3L 1Y5 ese@eppsiepman.com

CITY OF WINNIPEG BUILDING SERVICES

Project
CINDY KLASSEN RECREATION COMPLEX
POOL BOILER INSTALLATION
BID OPPORTUNITY # 434-2007

Sheet Title
POOL EQUIPMENT ROOM PARTIAL PLAN

AS NOTED
0733 ese **M-1**