



1 POOL EQUIPMENT ROOM SECTION
 M-2 SCALE: 3/8" = 1'-0"

KEY NOTES

- 1 FROM MAKE UP WATER SUPPLY.
- 2 MOUNT FROM CEILING WITH THREADED ROD AND SUPPORT PLATFORM (STEEL). MOUNT LOW ENOUGH TO FACILITATE ACCESS FROM AN 8' STEP LADDER (MAINTAIN SERVICE CLEARANCE TO ALL EQUIPMENT).
- 3 SEE PLAN AND SCHEMATIC DRAWING FOR LOCATION OF SUPPLY AND RETURN PIPING FROM POOL.
- 4 REFER SCHEMATIC DRAWING FOR DETAILS.
- 5 NEW SUPPLY / RETURN PIPING TO POOL LOOP.
- 6 EXISTING SUPPLY / RETURN PIPING FROM POOL LOOP.
- 7 NEW CONCRETE PAD ELEVATION TO BE 12" ABOVE EXISTING FLOOR.

0 07-06-11 FOR TENDER & CONSTRUCTION

No. DATE ISSUANCE
 Seal



APEGM
 Certificate of Authorization
Epp Siepman Engineering Inc.
 No. 4035 Date: 2007-06-11

epp siepman engineering inc.
 mechanical engineers
 303-100 Osborne St. South p 204.453.1080
 Winnipeg, MB f 204.453.1335
 R3L 1Y5 ese@eppsiepman.com

CITY OF WINNIPEG BUILDING SERVICES

Project
 CINDY KLASSEN RECREATION COMPLEX
 POOL BOILER INSTALLATION
 BID OPPORTUNITY #434-2007

Sheet Title
POOL EQUIPMENT ROOM SECTION

AS NOTED
 0733 **M-2**