



MAIN FLOOR PLAN - PLUMBING RENOVATION
SCALE: 1/4"=1'-0"

PLUMBING DEMOLITION NOTES

REMOVE ALL EXISTING PLUMBING LINES, FIXTURES AND VALVES BACK TO SOURCE.

PLUMBING RENOVATION NOTES:

SUPPLY & INSTALL, UNLESS OTHERWISE NOTED.

- 1 CONTINUE ON DRAWING M5.
- 2 NEW PLUMBING VENT THROUGH ROOF. PENETRATION THROUGH ROOF SHALL BE WATER TIGHT AND IN ACCORDANCE TO THE LATEST BUILDING CODE AND ROOFING STANDARD.

NOTES :
SEE NOTES ON DRAWING M1.

NO.	REVISION/DESCRIPTION	BY	DATE
SEALS			

ORIGINAL STAMPED BY: DOUG PALEY, P. ENG.
DATE: 2007.10.17

DRAWN BY	CHECKED BY	APPROVED
RCP/DTA <td></td> <td></td>		
DATE: 2007.10.11	USER APPROVAL	

CITY OF WINNIPEG
PLANNING, PROPERTY & DEVELOPMENT DEPARTMENT
CIVIC ACCOMMODATIONS DIVISION
300 - 65 GARRY ST. R3C 4K4

PROJECT
COMMUNITY POLICE SERVICE CENTRE
1400 HENDERSON HWY.

SHEET TITLE
MAIN FLOOR PLAN
PLUMBING
DEMOLITION AND RENOVATION

SCALE	PROJECT NO.	SHEET NO.
AS SHOWN	2004-023	M6