



### LIMITS OF WORK

EXISTING PARKING LOT  
 LOCATION FOR CONSTRUCTION ACCESS, LOCATION TO BE CONFIRMED ON SITE WITH CONTRACT ADMINISTRATOR PRIOR TO STARTING CONSTRUCTION

SUPPLY AND INSTALL ONE NEW WOOD BOLLARDS (BY OTHERS, N.I.C.)

SUPPLY AND INSTALL TWO NEW WOOD BOLLARDS (BY OTHERS, N.I.C.)

SUPPLY & INSTALL TOPSOIL AND SOD IN EXCAVATED AREA OUTSIDE OF NEW LIMESTONE PATHWAY FEATHER INTO EXISTING GRADE

SUPPLY AND INSTALL NEW 1.8m WIDE CRUSHED LIMESTONE PATH AS PER CW 3150-R4. REFER TO DWG 1/D1 FOR DETAIL. EXACT LOCATION TO BE DETERMINED ON SITE WITH CONTRACT ADMINISTRATOR. FLARE PATH AT ROADWAY EDGE. REPAIR SOD AT PATH EDGE

UPGRADE EXISTING SINGLE BAY INFANT SWINGS TO MEET CSA STANDARDS (BY OTHERS, N.I.C.)

FEATHER NEW PATH INTO EXISTING PATHWAY AT PROPERTY LINE

UPGRADE EXISTING TWO-BAY SENIOR SWINGS TO MEET CSA STANDARDS (BY OTHERS, N.I.C.)  
 SUPPLY & INSTALL TOPSOIL AND SOD IN AREAS WHERE REMOVED PLAY SURFACE IS OUTSIDE OF NEW PLAY AREA

ACCESS POINT TO ACCESSIBLE PLAY STRUCTURE

EXISTING CB

## NOTES

### GENERAL NOTES

- ALL EXISTING TREES, SHRUBS, SIDEWALKS, CURBS, SOD, UTILITIES AND PAVING TO BE PROTECTED (UNLESS OTHERWISE NOTED) DURING CONSTRUCTION TO CITY OF WINNIPEG STANDARDS. CONTRACTOR TO MAKE GOOD ALL DAMAGED AREA DURING CONSTRUCTION BOTH ON AND OFF SITE TO CITY OF WINNIPEG STANDARDS AT THE CONTRACTORS COSTS
- MAINTAIN EXISTING GRADE AND DRAINAGE PATTERNS. ENSURE POSITIVE DRAINAGE
- LAYOUT TO BE APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO ANY CONSTRUCTION OR REMOVAL
- ALL NOTES IN GREY INDICATE WORK TO BE COMPLETED BY OTHERS UNDER SEPARATE CONTRACT
- PLAY AREAS A, B & C LIMITS SHOWN ARE A MAXIMUM ONLY
- PLAY SURFACE AND PLAY EQUIPMENT TO BE SUPPLIED AND INSTALLED BY PLAY EQUIPMENT CONTRACTOR. FINAL DESIGN, LAYOUT AND EXTENTS OF PLAY AREAS TO BE PROVIDED BY PLAY EQUIPMENT CONTRACTOR.
- 90° ANGLES (OR LESS) FORMED BY TIMBER EDGING ON INSIDE OF PROTECTIVE SURFACING ZONE TO BE AVOIDED
- EXCAVATE AREAS A, B & C TO DEPTH REQUIRED FOR PROTECTIVE SURFACING INSTALLATION, ENSURE SUBGRADE GRADE TO DRAIN (MIN. 1%) PRIOR TO INSTALLATION OF PLAY SURFACE
- SUPPLY & INSTALL TIMBER EDGING FOR AREAS A, B & C AS PER PLAY EQUIPMENT CONTRACTOR'S LAYOUT AND WRITTEN SPECIFICATIONS
- REFER ALSO TO WRITTEN SPECIFICATIONS

### LEGEND

- PROPERTY LINE
- LIMITS OF WORK
- APPROXIMATE LIMITS OF NEW PLAY AREAS AVAILABLE
- EXISTING TREES
- CONSTRUCTION ACCESS LOCATION
- APPROXIMATE AREAS OF NEW TOPSOIL AND SOD

**1** DORGE PARK - PROPOSED SITEPLAN  
 DP2 SCALE 1:200

NOT FOR CONSTRUCTION

All measurements in millimeters, unless otherwise noted.



LANDSCAPE ARCHITECT'S SEAL



**THE CITY OF WINNIPEG**  
 DEPARTMENT OF PLANNING,  
 PROPERTY AND DEVELOPMENT

NO.	REVISIONS	DATE	BY

DESIGNED BY	JW	CHECKED BY	DM
DRAWN BY	WF/JW	APPROVED BY	DM
HOR. SCALE:	AS SHOWN	RELEASED FOR CONSTRUCTION:	
VERTICAL:		DATE	2007.09.21

PROJECT TITLE	CITY OF WINNIPEG PLAYGROUND RENOVATIONS SITE WORKS AND FURNISHINGS
SHEET OF	02 OF 10
COMPUTER FILE NAME	7036-SITE-DP.DWG
CITY DRAWING NUMBER	<b>SW-DP2</b>

PROJECT TITLE	CITY OF WINNIPEG PLAYGROUND RENOVATIONS SITE WORKS AND FURNISHINGS
SHEET OF	02 OF 10
COMPUTER FILE NAME	7036-SITE-DP.DWG
CITY DRAWING NUMBER	<b>SW-DP2</b>