



876-2007 ADDENDUM 2

FORT ROUGE PARK OUTFALL PIPE REPLACEMENT AND RIVERBANK STABILITY IMPROVEMENT

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: December 11, 2007
BY: Roy Houston, P.Eng.
TELEPHONE NO. (204) 896-1209

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

Add: E26.1.4 Monitoring Movement of Shoring

The Contractor shall submit to the Contract Administrator a plan for monitoring the movement of trench shoring during construction a minimum of two (2) Working Days prior to the installation of trench shoring. The monitoring plan shall be by approved survey methods for vertical or horizontal movement of the shoring, acceptable to the Contract Administrator. Costs for monitoring shall be incidental to the installation of the trench shoring.