

ADDENDUM 4 BID OPPORTUNITY 95-2007

WINNIPEG WATER TREATMENT PROGRAM – CONSTRUCTION OF PLANT INTERIOR FINISHES

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: July 6, 2007
BY: Gord Smith, P. Eng.
TELEPHONE NO. (204) 986-4249

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20050506

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace 95-2007_Addendum_3-Bid_Submission with 95-2007_Addendum_4-Bid_Submission. Form G2(R1) has been replaced by Form G2(R2).

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, July 20, 2007.

PART D - SUPPLEMENTAL CONDITIONS

Revise: D2.2(d) to read: Painting of interior plant areas, including exterior doors and bollards within the plant area.

Revise: D2.2(e) to read: Supply and installation of FRP platforms, stairs and handrails to area WC.

Add: D2.2(g) Supply and installation of all exterior louvers.

Add: D2.2(h) Supply and installation of window treatment, partitions and welding curtains.

Add: D2.3 Temporary hoarding, heating & lighting

Add: D2.3.1 The Contractor shall provide hoarding, heating and ventilation as required for the performance of the Work. The permanent HVAC systems will be placed into operation during the final stages of the Work. The Contractor shall provide temporary lighting as required for the performance of the Work including lighting for access and egress. The permanent lighting will be placed into operation during the final stages of the Work.

Add: D2.4 Temporary Protection

Add: D2.4.1 Aluminum stair treads to all stairs shall be protected with an 11/16" thick plywood cover for the duration of the construction period. Aluminum handrails and toe boards (including stair handrails) shall be provided with a suitable protective tape wrap to protect the surface for the duration of the construction period. All protective material shall be removed upon completion of the Work as directed by the Contract Administrator.

Revise: D17.1(b) to read: February 29, 2008 – Completion of the second and third floor offices in area WA.

- Revise: D17.1(c) to read: December 21, 2007 – Complete installation of stairs 2 to 6 and stair 9, including tread and handrail protection. Refer to D2.4 included in this Addendum for details of required protection.
- Revise: D17.1(d) to read: April 8, 2008 – Complete installation of all required handrails in areas WA, WF, WR, WO, WM, and WI. Refer to D2.4 included in this Addendum for details of required protection.
- Revise: D20.1(c) to read: Critical stages as detailed in D17.1(b), (c) and (d) – Two thousand six hundred dollars (\$2,600.00);