

NOTES :

**GENERAL NOTES**

- ① PROVIDE INSTALL 80mm X 150mm LAMACOID WITH INFORMATION AS DETAILED IN THIS DRAWING

NOTE 1

INCOMING FEEDER	B2-1 P-8 HIGH TEMP LOOP CIRCULATOR PUMP 0.75 HP 15A CB STARTER SIZE 1	SPARE
	B2-2 P-10 BUILDING LOOP PUMP 1.5 HP 15A CB STARTER SIZE 1	SPARE
T.V.S.S.	B2-3 P-11 BUILDING LOOP PUMP 1.5 HP 15A CB STARTER SIZE 1	SPARE
	B2-4 P-12 FLUID COOLER PUMP 0.4 HP 15A CB STARTER SIZE 1	SPARE
SPARE	B2-5 P-13 PHC PUMP 0.4 HP 15A CB STARTER SIZE 1	SPARE
	SPARE	SPARE

100 mm HOUSEKEEPING PAD

① MCC-B - NEW MOTOR CONTROL CENTER  
N.T.S.

0	ISSUED FOR ADDENDUM 2	ES	2008.12.11
NO.	REVISION/DESCRIPTION	BY	DATE

SEALS



DRAWN BY	DL	CHECKED BY	APPROVED
DATE	2008.12.11	USER APPROVAL	

CITY OF WINNIPEG  
PLANNING, PROPERTY AND  
DEVELOPMENT DEPARTMENT  
CIVIC ACCOMMODATIONS DIVISION  
300 - 65 GARRY ST. R3C 4K4

PROJECT  
CONFEDERATION BUILDING  
SUPPLEMENTARY HEATING UPGRADES  
PHASE 1 - CITY BID OPP. NO. 757-2008  
457 MAIN STREET, WINNIPEG, MANITOBA



**APEGM**  
Certificate of Authorization  
Earth Tech Canada Inc.  
No. 730 Expiry: April 30, 2009



© 2008 EARTH TECH (CANADA) INC. ALL RIGHTS RESERVED.  
THIS DOCUMENT IS PROTECTED BY COPYRIGHT LAW AND MAY NOT BE USED, REPRODUCED OR MODIFIED IN ANY MANNER OR FOR ANY PURPOSE EXCEPT WITH THE WRITTEN PERMISSION OF EARTH TECH (CANADA) INC. DOING BUSINESS AS AECOM (AECOM) OR A PARTY TO WHICH ITS COPYRIGHT HAS BEEN ASSIGNED. AECOM ACCEPTS NO RESPONSIBILITY, AND DENIES ANY LIABILITY WHATSOEVER, TO ANY PARTY THAT USES, REPRODUCES, MODIFIES, OR RELIES ON THIS DOCUMENT WITHOUT AECOM'S EXPRESS WRITTEN CONSENT.

SHEET TITLE  
ELECTRICAL  
MOTOR CONTROL CENTER  
MCC-B

SCALE	PROJECT NO.	SHEET NO.
AS SHOWN	105111	E04