



- REFERENCE NOTES:**
- A. BASELINE IS CENTERED BETWEEN NORTHBOUND AND SOUTHBOUND GUTTER BACK OF CURB
 - B. LEGAL PLAN - L.B.I.S.
 - C. EARTH TECH FIELD BOOK No. 4574
 - D. PAVEMENT DIMENSIONS ARE TO BACK OF CURB
 - E. ALL WORK TO CONFORM TO CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS
- CONSTRUCTION NOTES:**
1. PLANE EXISTING ASPHALT AND CONSTRUCT NEW 80mm ASPHALTIC CONCRETE OVERLAY.
 2. CONSTRUCT NEW 200mm PLAIN DOWELLED CONCRETE. PAVEMENT C/W ASPHALTIC CONCRETE OVERLAY.
 3. CONSTRUCT NEW MONOLITHIC CONCRETE MEDIAN SLAB.
 4. CONSTRUCT NEW MONOLITHIC CONCRETE SPLASH STRIP.
 5. CONSTRUCT NEW MONOLITHIC CONCRETE MODIFIED SPLASH STRIP.
 6. CONSTRUCT NEW MONOLITHIC CONCRETE BARRIER CURB AND SIDEWALK.
 7. CONSTRUCT NEW MONOLITHIC CONCRETE BULLNOSE.
 8. CONSTRUCT NEW CONCRETE SIDEWALK.
 9. INSTALL NEW CURB AND GUTTER INLET C/W CATCHBASIN (SD-024) AND CONNECT NEW 250mm LEAD TO EXISTING LEAD.
 10. ABANDON EXISTING CATCHBASIN.
 11. ABANDON EXISTING DRAINAGE INLET.
 12. INSTALL NEW CURB AND GUTTER INLET C/W CATCHPIT (SD023) AND CONNECT TO EXISTING CATCHBASIN.
 13. REMOVE EXISTING PATIO BLOCK SPLASH STRIP.
 14. ADJUST EXISTING CATCHBASIN/MANHOLE TO GRADE.
 15. CONSTRUCT NEW CONCRETE SAFETY MEDIAN.
 16. CONSTRUCT NEW CONCRETE MEDIAN SLAB.
 17. CONSTRUCT NEW TREE WELL C/W BARK MULCH, WEED BARRIER FABRIC AND CONCRETE BARRIER CURB (SEPARATE).

APEGM
 Certificate of Authorization
 Earth Tech Canada Inc.
 No. 730 Expiry: April 30, 2008

METRIC
 WHOLE NUMBERS INDICATE MILLIMETRES
 DECIMALIZED NUMBERS INDICATE METRES

| EXISTING | LEGEND - PLAN | PROPOSED | EXISTING | LEGEND - PLAN | PROPOSED | EXISTING | LEGEND - PROFILE | PROPOSED |
|--------------|---------------------|--------------|-------------------|---------------|----------|----------|------------------|----------|
| 150 mm W.M. | WATERMAIN | 150 mm W.M. | HYDRO | — | — | — | — | — |
| 300mm L.D.S. | LAND DRAINAGE SEWER | 300mm L.D.S. | M.T.S. | — | — | — | — | — |
| 250mm W.W.S. | WASTEWATER SEWER | 250mm W.W.S. | CONCRETE | — | — | — | — | — |
| — | MANHOLE | — | ASPHALT | — | — | — | — | — |
| — | CATCH BASIN | — | PROPERTY LINE | — | — | — | — | — |
| — | CURB INLET | — | SURVEY BAR | — | — | — | — | — |
| — | JUNCTIONS | — | ELEVATION | — | — | — | — | — |
| — | TEST HOLE (07-R-03) | — | TREE | — | — | — | — | — |
| — | GAS | — | SIDEWALK RAMP | — | — | — | — | — |
| — | — | — | CONCRETE SIDEWALK | — | — | — | — | — |
| — | — | — | FENCE | — | — | — | — | — |

LOCATION APPROVED UNDERGROUND STRUCTURES
 SUPV. U/G STRUCTURES DATE COMMITTEE
 NOTE:
 LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

| | | |
|---------------|--|---------------|
| B.M. 54-003 | TBLT IN E. CONC FOUNDATION OF ST. VITAL CIVIC OFFICE 604 ST MARY'S W. SIDE OF FRONT ENTRANCE | ELEV. 232.245 |
| 0 | ISSUED FOR TENDER | MAR 6/08 KWR |
| A | ISSUED FOR REVIEW | FEB 25/08 BC |
| NO. REVISIONS | DATE | BY |

EarthTech
 A Tyco International Ltd. Company

| | | | |
|-------------|--------|-------------------------------|-----------------|
| DESIGNED BY | RC | CHECKED BY | KWR/BC |
| DRAWN BY | RC/RAM | APPROVED BY | ORIGINAL SIGNED |
| HOR. SCALE: | 1:250 | RELEASED FOR CONSTRUCTION BY: | ORIGINAL SIGNED |
| VERTICAL: | 1:10 | DATE | MARCH 6, 2008 |

ENGINEER'S SEAL
 PROVINCE OF MANITOBA
 ORIGINAL SIGNED
K.W. RAE
 MAR 6/08
 REGISTERED PROFESSIONAL ENGINEER

THE CITY OF WINNIPEG
 PUBLIC WORKS DEPARTMENT
 TRANSPORTATION ENGINEERING DIVISION

ST. MARY'S ROAD
 ST. ANNE'S ROAD TO FERMOY AVENUE
 CONCRETE REPAIRS AND ASPHALT RESURFACING

CITY DRAWING NUMBER P-3292-07
 SHEET 7 OF 12

PLAN PROFILE
 STA 6+90 TO STA 8+40

CONSULTANT DRAWING NO. CT07