



280-2009 ADDENDUM 1

BAYVIEW AND HATCHER PARK PLAYGROUND EQUIPMENT

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: June 9, 2009
BY: **Aaron Hirota**
TELEPHONE NO. (204) 956-0396

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 280-2009 Bid Submission with 280-2009 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Replace 280-2009 Bid Submission with 280-2009 Addendum 1 Bid Submission.

PART B – BIDDING PROCEDURES

Revise: B16.5.3 (a): "6 points – Uniqueness of components as compared to similar playground components within walking distance (400m) of the park."

Revise: B16.7: "Notwithstanding B8.1, the Bidder shall bid on item 5 and/or item 7 on Form B (R1): Prices."

Add: B16.8: "Notwithstanding B17.2, the City shall not be obligated to award a Contract to the responsible Bidder submitting the lowest evaluated responsive Bid and shall have the right to choose the alternative which is in its best interests. If the Bidder has not bid on both alternatives, he shall have no claim against the City if his partial Bid is rejected in favour of an award of the Contract on the basis of an alternative upon which he has not bid."

PART E – SPECIFICATIONS

Replace: All references to "Form B" with "Form B (R1)"

Revise: E1.3 to read: The following are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
L1.1	Bayview Park – Playground Plan
L1.2	Hatcher Park – Playground Plan
L1.3	Millennium Park – Playground Plan
SCD 651	Pedra Single timber Edging Detail

- Revise: E2.1.3 (a) to read: "Excavate and legally dispose of turf areas, topsoil and subgrade materials to the limits shown on Drawings L1.1, L1.2 and L1.3 to the depths required to achieve finish grade for."
- Add: E2.1.3 (a) (iii): "Safety surfacing within proposed Millennium Park Play Area."
- Revise: E2.2.6 (a) to read: "Safety Surfacing in Bayview Park, Hatcher Park and Millennium Park Play Areas – to accommodate a surfacing in accordance with CSA standards, design submission and required depth."
- Revise: E5.5 (a) to read: "Approximately 25-30% of play equipment budget;"
- Revise: E5.6 (a) to read: "Approximately 50-55% of play equipment budget;"
- Add: E5.7 "Millennium Park Play Area."
- Add: E5.7 (a) "Approximately 15-20% of play equipment budget;"
- Add: E5.7 (b) "Play equipment for Millennium Park to be a Mini Rotating Net with Deck and the interchangeable cross joints option model #ERN820D as supplied by:
Playworks Manitoba
contact: Jeff Kuby,
(204) 414-2990, jeff@playworks.ca"
- Add: E6.4.1 (a) (iii) "Supply and Install Millennium Park play equipment," on Form B (R1) Prices."
- Add: E10 "PLAYGROUND STONE

Description

E10.1 The Work comprises the furnishings of all labour, equipment services and materials required to complete the installation of playground stone within the play structure and swing areas as indicted on the drawings.

General

E10.2 Contractor shall visit the Site and verify all data and dimensions and report any errors, omissions or discrepancies to the Contract Administrator prior to any installation.

Material

E10.3 Playground stone shall be 6mm, composition shall be Typical Birds Hill glacial till material, approximately 70% limestone and 30% granite. Stone shall be washed and screened.

Sieve Analysis:

Sieve Size	Cumulative % Passing
10 mm	100
5 mm	80-90
2.5 mm	5-25
1.25 mm	2-15
.08 mm	0-1

Construction Methods

E10.4 Playground Stone shall be installed within all the play areas, as defined by the edging, to a minimum installed compacted depth of 250mm.

E10.5 The installation of the Playground Stone shall be done immediately after the play structure has been installed.

E10.6 Installation shall be done by equipment sized to suit the Work being done and the stone shall be spread by hand in the immediate vicinity of the play structures so as not to damage the same. The play structures shall be swept clean as required after installation of the stone.

E10.7 Playground stone to be installed as per, CSA Standards, play equipment manufacturer's specifications and as directed by Contract Administrator on Site.

Method of Measurement

E10.8 Playground Stone will be measured on an area basis. The quantity to be paid for will be the actual number of square meters supplied and installed in accordance with this Specification and accepted by the Contract Administrator, as computed from the measurements made by the Contract Administrator.

Basis of Payment

E10.9 Playground Stone shall be paid for at the Contract Unit Price per square meter for 'Remove existing sand and replace with playground stone' measured as specified herein, which price shall be payment in full for supplying all materials and performing all operations herein described and all other items incidental to the Work included in this specification."

DRAWINGS

Add: 280-2009 _Drawing_ L1.3 Millennium Park – Playground Plan