



General Notes

1. All existing trees, sidewalks, curbs, catch basins, culverts, survey markers, to remain are to be protected during construction. Any damage to them is to be made good by the Contractor. Maintain positive drainage into all catch basins and curb inlets.
2. Contractor is to limit operations to the area within the area of work shown on the drawing. Should areas outside of this limit be damaged during the course of construction, Contractor is to make good the damage at his own expense
3. Drawing is METRIC with dimensions shown in meters unless marked otherwise. Layout is to be performed with metric measure. Soft conversion of dimension will not be permitted.
4. Grades shown are relative grades only. They are based upon a grade of 100.00 meters at the top of the play curb. Grade indications should be taken as conceptual.
5. Top of curb elevation (100.00m) is to be set on site by Contract Administrator after layout is complete.
6. Surface of the play area (mud grade) is to slope gently to the center alignment shown. Center alignment is to correspond to location of Multi-flo drain tile and is to have slope as indicated.

1 Site Grading
L-8 Scale: 1:100

1 4/8/09 For Bid Opportunity

No.	Date	Issue Notes

Drawing No.

L-8 of 9

**Pinehurst Byron Park
 Playground Renovation
 Site Grading**

