



429-2009 ADDENDUM 1

Supply and Install Fuel Tanks and Retrofit Existing Fuel Tanks at Various City Owned Golf Fuel Sites

ISSUED: June 25, 2009
BY: Ajaleigh Williams
TELEPHONE NO. (204) 986-7879

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- Revise: E2.1 (k) to read: All electrical and related trenching (including backfilling and compacting after trenching) required to make the fuel site operational shall be included in the cost of this bid opportunity.
- Add: E2.1 (m) to read: Construct a compacted and level base for the tank to sit on.
- Add: E2.1 (n) to read: Supply and install a fill rite model 701 pump and meter or equivalent.
- Revise: E2.2. (b) to read: Replace the existing manual hose dispenser unit with a fill rite model 701 pump and meter or equivalent.
- Revise: E2.2 (i) to read: All electrical and related (including backfilling and compacting after trenching) required to make the fuel site operational shall be included in the cost of this bid opportunity.
- Revise: E3.1 (k) to read: All electrical and related (including backfilling and compacting after trenching) required to make the fuel site operational shall be included in the cost of this bid opportunity.
- Add: E3.1 (m) to read: Construct a compacted and level base for the tank to sit on.
- Add: E3.1 (n) to read: Supply and install a fill rite model 701 pump and meter or equivalent.
- Revise: E3.2 (a) to read: Replace the existing manual hose dispenser unit with a fill rite model 701 pump and meter or equivalent.
- Revise: E3.2 (h) to read: All electrical and related (including backfilling and compacting after trenching) required to make the fuel site operational shall be included in the cost of this bid opportunity.
- Revise: E4.1 (b) to read: Replace the existing manual hose dispenser unit with a fill rite model 701 pump and meter or equivalent.
- Revise: E4.1 (i) to read: All electrical and related (including backfilling and compacting after trenching) required to make the fuel site operational shall be included in the cost of this bid opportunity.
- Add: E4.1 (k) to read: Power will be picked up from the building to the South of the existing tank, a cut-off switch will be installed in the Building so power can be cut off from the pump during off-hours.