

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 03 03 00 Cast-in-place Concrete

1.2 REFERENCES

- .1 Manual of Uniform Traffic Control Devices for Canada
- .2 City of Winnipeg – Manual of Temporary Traffic Control in Work Areas on City Streets, most current edition.

Part 2 Products

2.1 MATERIALS

- .1 Sign supports.
 - .1 Steel posts
 - .1 Schedule 40 galvanized steel pipe to CAN3-Z245.1
 - .2 Cast in concrete pile
 - .3 38mm nominal diameter
 - .4 O.D.= 48.3mm
 - .5 Wall thickness = 3.7 mm
 - .2 Warning Sign
 - .1 Fully reflectorized white sign with black letters
 - .2 Rounded corners but conforming to the nominal dimensions for height and width shown on the drawings.
 - .3 Consistent with City of Winnipeg requirements for “Warning and Information Signs” outlined in Section 5.00 of the “Manual of Temporary Traffic Control in Work Areas on City Streets”.

Part 3 Execution

3.1 INSTALLATION

- .1 All sign locations to be confirmed with the Contract Administrator prior to installation.

END OF SECTION