



# 923-2009 ADDENDUM 1

## GUNN ROAD RECONSTRUCTION – CORDITE DRAIN CULVERT REPLACEMENT AT DAY STREET AND GUNN ROAD

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: January 15, 2010  
BY: Kevin Amy  
TELEPHONE NO. (204) 488-5743

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20070419

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

---

### **PART A – BID SUBMISSION**

Replace: 923-2009 Bid Submission with 923-2009 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1):           Item B.3 – Change to reinforcing steel quantity.
- Item B.9 – Change to erosion control blanket quantity.
- Item B.10 – Change to silt fence quantity.

### **PART E – SPECIFICATIONS**

Revise: E9.3.6 to read:       The Contractor shall provide rough grading to all disturbed surfaces within the construction area to the requirements of the “Preparation of Existing Grade” of Specification CW 3450. The Contractor shall be responsible to cover all unvegetated surfaces of the embankments with an erosion control blanket, erect silt fences or use other suitable methods to prevent soil erosion into the creek, both during and after construction of the culvert up until the time of final landscaping restoration to be done by others. Landscaping by others will be done once the Works of this Contract on the creek embankment has been completed. Erosion control blankets are to be installed on the bottom of the ditch and the slopes of the excavation in place of the removed CSP culverts during Phase II of the Work. The erosion control blanket it to be supplied, placed, measured and paid for in accordance with E19 and silt fences are to be supplied, placed, measured and paid for in accordance with E13.

Revise: E19.4.1 to read:       Supplying and placing Erosion Control Blanket will be measured on a square metre basis. The area to be measured shall be the total number of square metres of Erosion Control Blanket supplied and placed in accordance with this Specification, acceptable to the Contract Administrator, as computed from Site measurements. This item of work will be paid for at the Contract Unit Price per square metre for “Supply and Install Erosion Control Blanket” performed in accordance with this Specification and accepted by the Contract Administrator.

## **DRAWINGS**

Replace: 923-2009 \_Drawing\_C365-10-01-R0 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-01-R1.  
923-2009 \_Drawing\_C365-10-02-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-02-R3.  
923-2009 \_Drawing\_C365-10-03-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-02-R3.  
923-2009 \_Drawing\_C365-10-04-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-04-R3.  
923-2009 \_Drawing\_C365-10-05-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-05-R3.  
923-2009 \_Drawing\_C365-10-05-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-05-R3.  
923-2009 \_Drawing\_C365-10-06-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-06-R3.  
923-2009 \_Drawing\_C365-10-07-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-07-R3.  
923-2009 \_Drawing\_C365-10-08-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-08-R3.  
923-2009 \_Drawing\_C365-10-09-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-09-R3.  
923-2009 \_Drawing\_C365-10-10-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-10-R3.  
923-2009 \_Drawing\_C365-10-11-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-11-R3.  
923-2009 \_Drawing\_C365-10-12-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-12-R3.  
923-2009 \_Drawing\_C365-10-13-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-13-R3.  
923-2009 \_Drawing\_C365-10-14-R2 with 923-2009 \_Addendum\_1 \_Drawing\_C365-10-14-R3.  
Add: 923-2009 \_Drawing\_ 923-2009 \_Addendum\_1 \_Drawing\_C365-10-15-R0.