

923-2009 ADDENDUM 2

GUNN ROAD RECONSTRUCTION – CORDITE DRAIN CULVERT REPLACEMENT AT DAY STREET AND GUNN ROAD

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: January 18, 2010
BY: Kevin Amy
TELEPHONE NO. (204) 488-5743

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 923-2009 Bid Submission with 923-2009 Addendum 2 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R2): Item C.4 – Change to item description.

PART E – SPECIFICATIONS

Revise: E18 to read:

E18. PRECAST CONCRETE TRAFFIC BARRIERS

E18.1 Description

- (a) The Work to be covered this item shall include all operations relating to the installation and removal of precast concrete traffic barriers.
- (b) The Work to be done by the Contractor under this Specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies and all things necessary for and incidental to the satisfactory performance and completion of the Work as hereinafter specified.

E18.2 Materials

E18.2.1 Precast Concrete Traffic Barriers

- (a) The precast concrete traffic barriers and connecting pins shall be supplied by the City of Winnipeg. The precast concrete barriers are located at the City of Winnipeg Bridge Yard, 849 Ravelstone Avenue.
- (b) A City of Winnipeg standard drawing CW-315 of the precast barrier is included in Appendix C.

E18.3 Equipment

- (a) The Contractor is responsible for supplying suitable equipment for loading, hauling, placing, and maintaining the precast barriers both at the City Bridge Yard and the construction site.

E18.4 Construction Methods

E18.4.1 Mobilizing Barriers from City Bridge Yard

- (a) The Contractor shall contact Mike Terleski at 794-8510 to arrange a suitable time and date to pick up the precast concrete barriers. The Contractor shall provide a minimum of 2 days notice.
- (b) The contractor shall be responsible for all operations and equipment related to loading and hauling the equipment.
- (c) A detail materials transmittal shall be prepared and signed.
- (d) Existing damage on the barriers shall be noted and recorded on the transmittal to the satisfaction of the Contract Administrator. Any damage not recorded will be assumed to have occurred as a result of the Contractor's operations and will be restored at his expense.

E18.4.2 Placing Barriers on Site

- (a) The precast concrete barriers shall be placed at the locations shown on the Drawings. The barriers shall be properly aligned, seated firmly to the sub-surface and pinned together to the satisfaction of the Contract Administrator.

E18.4.3 Maintaining Barriers on Site

- (a) The Contractor shall maintain the barriers on site to the satisfaction of the Contract Administrator until Total Performance is achieved.
- (b) Prior to Total Performance, the barrier installation shall be inspected for damage or missing components that has occurred during construction operations. The Contractor shall repair any such damage and replace missing components to the satisfaction of the Contract Administrator.

E18.4.4 Removal of Barriers

- (a) Removal of the precast barriers will be undertaken by others during completion of the Gunn Road reconstruction.

E18.5 Measurement and Payment

- (a) The installation and maintenance of the Precast Concrete Traffic Barriers will be measured on a unit basis. The total number to be measured shall be the total number of Precast Concrete Traffic Barriers installed and maintained in accordance with this Specification, acceptable to the Contract Administrator. This item of work will be paid for at the Contract Unit Price each for "Installation and Maintenance of Precast Concrete Traffic Barriers," performed in accordance with this Specification and accepted by the Contract Administrator.