


DAY ST

19.8 FULLY DETERIORATED
OVALITY = 8.0%

84.0 PARTIALLY DETERIORATED
OVALITY = 3.0%

HORTON AVENUE (EAST)



MH ID S-MH40012706
MH OPENING - 521Ø
MH RISERS - 750Ø
MH BASE - 1200Ø

103.80 OF 200 CONC WWS
TO BE LINED
SEWER ID S-MA40014078

2.0 OF 200 PVC SEWER
REPAIR (SD-022A) INCLUDING
2 SERVICE CONNECTIONS.
(TO BE DONE BY OTHERS)

MH ID S-MH40012743
MH OPENING - 521Ø
MH RISERS - 750Ø
MH BASE - 1200Ø

TO BE LINED
(SEE DWG. 9183)

FOR CONTINUATION
SEE DWG 9183

SEWER JUNCTION INFORMATION
FROM SEWER VIDEO INSPECTION
SEWER ID S-MA40014078

DISTANCE FROM MH ID S-MH40012743				
2.2	W	150Ø	SOUTH	JN
2.6	W	150Ø	NORTH	JN
11.2	W	150Ø	SOUTH	CN
12.0	W	150Ø	SOUTH	JN
25.1	W	150Ø	SOUTH	JN
26.6	W	150Ø	NORTH	JN
39.7	W	150Ø	SOUTH	JN
40.6	W	150Ø	SOUTH	CN
41.3	W	150Ø	NORTH	JN
47.3	W	150Ø	SOUTH	CN
52.9	W	150Ø	NORTH	JN
75.5	W	150Ø	SOUTH	CNI
78.3	W	150Ø	NORTH	CN
83.6	W	150Ø	SOUTH	JN

LEGEND:

52.0 | MEASUREMENT TO REPAIR FROM REFERENCE MH SHOWN THUS...

METRIC

WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

ENGINEER'S SEAL

ORIGINAL
SIGNED BY
S.R.J.
COURNOYER
10/03/08

BID OPPORTUNITY: 145-2010
FILENAME : 9184.dwg
PLOT DATE : 2010 03 09

B.M. ELEV.	FIELD BOOK #:	CITY OF WINNIPEG WATER AND WASTE ENGINEERING DIVISION		THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT	
POSTED TO LBIS		DESIGNED BY: SC	CHECKED BY: SC	2010 SEWER RENEWALS BY CIPP LININGS, CONTRACT 19 HORTON AVENUE (EAST) 1ST MH E OF DAY STREET TO MH AT DAY STREET	
		DRAWN BY: CJH	APPROVED BY: KZ	SHEET 10 OF 33 CITY DRAWING NUMBER 9184	
		HOR. SCALE: 1:500 VERTICAL	RELEASED FOR CONSTRUCTION		
NO.	REVISIONS	DATE	BY	DATE	2010 03 08