



**THE CITY OF WINNIPEG**

# **BID OPPORTUNITY**

**BID OPPORTUNITY NO. 271-2010**

**2010 RESIDENTIAL STREET RENEWALS – DE BOURMONT AVENUE,  
BERRYDALE AVENUE AND FARNHAM ROAD**

## TABLE OF CONTENTS

### PART A - BID SUBMISSION

Form A: Bid	1
Form B: Prices	4
Form G1: Bid Bond and Agreement to Bond	12
Form G2: Irrevocable Standby Letter of Credit and Undertaking	14

### PART B - BIDDING PROCEDURES

B1. Contract Title	1
B2. Submission Deadline	1
B3. Site Investigation	1
B4. Enquiries	1
B5. Addenda	1
B6. Substitutes	2
B7. Bid Components	3
B8. Bid	3
B9. Prices	4
B10. Qualification	4
B11. Bid Security	5
B12. Opening of Bids and Release of Information	6
B13. Irrevocable Bid	6
B14. Withdrawal of Bids	6
B15. Evaluation of Bids	7
B16. Award of Contract	8

### PART C - GENERAL CONDITIONS

C0. General Conditions	1
------------------------	---

### PART D - SUPPLEMENTAL CONDITIONS

#### General

D1. General Conditions	1
D2. Scope of Work	1
D3. Contract Administrator	2
D4. Contractor's Supervisor	2
D5. Notices	2
D6. Furnishing of Documents	3

#### Submissions

D7. Authority to Carry on Business	3
D8. Safe Work Plan	3
D9. Insurance	3
D10. Performance Security	4
D11. Subcontractor List	4
D12. Equipment List	4
D13. Detailed Work Schedule	4

#### Schedule of Work

D14. Commencement	4
D15. Working Days	5
D16. Restricted Work Hours	5
D17. Work By Others	5
D18. Sequence of Work	5
D19. Substantial Performance	6
D20. Total Performance	6
D21. Liquidated Damages	6
D22. Scheduled Maintenance	7

**Control of Work**

D23. Job Meetings	7
D24. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	7

**Warranty**

D25. Warranty	7
H1: Performance Bond	8
Form H2: Irrevocable Standby Letter of Credit	10
Form J: Subcontractor List	12
Form K: Equipment	13

**PART E - SPECIFICATIONS**

**General**

E1. Applicable Specifications and Drawings	1
E2. Geotechnical Report	1
E3. Office Facilities	1
E4. Protection Of Existing Trees	2
E5. Traffic Control	2
E6. Traffic Management	3
E7. Refuse and Recycling Collection	3
E8. Water Obtained From the City	3
E9. Surface Restorations	4
E10. Infrastructure Signs	4
E11. Crack and Sealing of Existing Concrete Pavement	4
E12. Supply and Installation of Moisture Barrier/Stress Absorption Geotextile Fabric	5
E13. Patching of Existing Pavement	7
E14. Recycled Concrete Base Course Material	8
E15. 100MM Crushed Sub-Base Material with Geotextile Fabric and Geogrid For Unstable Sub-Grades	9
E16. Supply and Install Detectable Warning Surface Tiles	10

**Appendix 'A' - Geotechnical Report**

## **PART B - BIDDING PROCEDURES**

### **B1. CONTRACT TITLE**

- B1.1 2010 RESIDENTAL STREET RENEWALS – DE BOURMONT AVENUE, BERRYDALE AVENUE AND FARNHAM ROAD

### **B2. SUBMISSION DEADLINE**

- B2.1 The Submission Deadline is 12:00 noon Winnipeg time, May 11, 2010.
- B2.2 Bids determined by the Manager of Materials to have been received later than the Submission Deadline will not be accepted and will be returned upon request.
- B2.3 The Contract Administrator or the Manager of Materials may extend the Submission Deadline by issuing an addendum at any time prior to the time and date specified in B2.1.

### **B3. SITE INVESTIGATION**

- B3.1 Further to C3.1, the Bidder may view the Site without making an appointment.

### **B4. ENQUIRIES**

- B4.1 All enquiries shall be directed to the Contract Administrator identified in D3.1.
- B4.2 If the Bidder finds errors, discrepancies or omissions in the Bid Opportunity, or is unsure of the meaning or intent of any provision therein, the Bidder shall notify the Contract Administrator of the error, discrepancy or omission, or request a clarification as to the meaning or intent of the provision at least five (5) Business Days prior to the Submission Deadline.
- B4.3 Responses to enquiries which, in the sole judgment of the Contract Administrator, require a correction to or a clarification of the Bid Opportunity will be provided by the Contract Administrator to all Bidders by issuing an addendum.
- B4.4 Responses to enquiries which, in the sole judgment of the Contract Administrator, do not require a correction to or a clarification of the Bid Opportunity will be provided by the Contract Administrator only to the Bidder who made the enquiry.
- B4.5 The Bidder shall not be entitled to rely on any response or interpretation received pursuant to B4 unless that response or interpretation is provided by the Contract Administrator in writing.

### **B5. ADDENDA**

- B5.1 The Contract Administrator may, at any time prior to the Submission deadline, issue addenda correcting errors, discrepancies or omissions in the Bid Opportunity, or clarifying the meaning or intent of any provision therein.
- B5.2 The Contract Administrator will issue each addendum at least two (2) Business Days prior to the Submission Deadline, or provide at least two (2) Business Days by extending the Submission Deadline.
- B5.2.1 Addenda will be available on the Bid Opportunities page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt/bidopp.asp>
- B5.2.2 The Bidder is responsible for ensuring that he has received all addenda and is advised to check the Materials Management Division website for addenda regularly and shortly before the Submission Deadline, as may be amended by addendum.

B5.3 The Bidder shall acknowledge receipt of each addendum in Paragraph 10 of Form A: Bid. Failure to acknowledge receipt of an addendum may render a Bid non-responsive.

## **B6. SUBSTITUTES**

B6.1 The Work is based on the Plant, Materials and methods specified in the Bid Opportunity.

B6.2 Substitutions shall not be allowed unless application has been made to and prior approval has been granted by the Contract Administrator in writing.

B6.3 Requests for approval of a substitute will not be considered unless received in writing by the Contract Administrator at least five (5) Business Days prior to the Submission Deadline.

B6.4 The Bidder shall ensure that any and all requests for approval of a substitute:

- (a) provide sufficient information and details to enable the Contract Administrator to determine the acceptability of the Plant, Material or method as either an approved equal or alternative;
- (b) identify any and all changes required in the applicable Work, and all changes to any other Work, which would become necessary to accommodate the substitute;
- (c) identify any anticipated cost or time savings that may be associated with the substitute;
- (d) certify that, in the case of a request for approval as an approved equal, the substitute will fully perform the functions called for by the general design, be of equal or superior substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance;
- (e) certify that, in the case of a request for approval as an approved alternative, the substitute will adequately perform the functions called for by the general design, be similar in substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance.

B6.5 The Contract Administrator, after assessing the request for approval of a substitute, may in his sole discretion grant approval for the use of a substitute as an "approved equal" or as an "approved alternative", or may refuse to grant approval of the substitute.

B6.6 The Contract Administrator will provide a response in writing, at least two (2) Business Days prior to the Submission Deadline, only to the Bidder who requested approval of the substitute.

B6.6.1 The Bidder requesting and obtaining the approval of a substitute shall be entirely responsible for disseminating information regarding the approval to any person or persons he wishes to inform.

B6.7 If the Contract Administrator approves a substitute as an "approved equal", any Bidder may use the approved equal in place of the specified item.

B6.8 If the Contract Administrator approves a substitute as an "approved alternative", any Bidder bidding that approved alternative may base his Total Bid Price upon the specified item but may also indicate an alternative price based upon the approved alternative. Such alternatives will be evaluated in accordance with B15.

B6.9 No later claim by the Contractor for an addition to the Total Bid Price because of any other changes in the Work necessitated by the use of an approved equal or an approved alternative will be considered.

B6.10 Notwithstanding B6.2 to B6.9, in accordance with B7.6, deviations inconsistent with the Bid Opportunity document shall be evaluated in accordance with B15.1(a).

## **B7. BID COMPONENTS**

B7.1 The Bid shall consist of the following components:

- (a) Form A: Bid;
- (b) Form B: Prices, hard copy;
- (c) Bid Security;
  - (i) Form G1: Bid Bond and Agreement to Bond, or  
Form G2: Irrevocable Standby Letter of Credit and Undertaking, or  
a certified cheque or draft;

B7.2 Further to B7.1, the Bidder should include the written correspondence from the Contract Administrator approving a substitute in accordance with B6.

B7.3 All components of the Bid shall be fully completed or provided, and submitted by the Bidder no later than the Submission Deadline, with all required entries made clearly and completely, to constitute a responsive Bid.

B7.4 The Bid shall be submitted enclosed and sealed in an envelope clearly marked with the Bid Opportunity number and the Bidder's name and address.

B7.4.1 Samples or other components of the Bid which cannot reasonably be enclosed in the envelope may be packaged separately, but shall be clearly marked with the Bid Opportunity number, the Bidder's name and address, and an indication that the contents are part of the Bidder's Bid.

B7.4.2 A hard copy of Form B: Prices must be submitted with the Bid. If there is any discrepancy between the Adobe PDF version of Form B: Prices and the Microsoft Excel version of Form B: Prices, the PDF version shall take precedence.

B7.5 Bidders are advised not to include any information/literature except as requested in accordance with B7.1.

B7.6 Bidders are advised that inclusion of terms and conditions inconsistent with the Bid Opportunity document, including the General Conditions, will be evaluated in accordance with B15.1(a).

B7.7 Bids submitted by facsimile transmission (fax) or internet electronic mail (e-mail) will not be accepted.

B7.8 Bids shall be submitted to:

The City of Winnipeg  
Corporate Finance Department  
Materials Management Division  
185 King Street, Main Floor  
Winnipeg MB R3B 1J1

## **B8. BID**

B8.1 The Bidder shall complete Form A: Bid, making all required entries.

B8.2 Paragraph 2 of Form A: Bid shall be completed in accordance with the following requirements:

- (a) if the Bidder is a sole proprietor carrying on business in his own name, his name shall be inserted;
- (b) if the Bidder is a partnership, the full name of the partnership shall be inserted;
- (c) if the Bidder is a corporation, the full name of the corporation shall be inserted;

- (d) if the Bidder is carrying on business under a name other than his own, the business name and the name of every partner or corporation who is the owner of such business name shall be inserted.

B8.2.1 If a Bid is submitted jointly by two or more persons, each and all such persons shall identify themselves in accordance with B8.2.

B8.3 In Paragraph 3 of Form A: Bid, the Bidder shall identify a contact person who is authorized to represent the Bidder for purposes of the Bid.

B8.4 Paragraph 12 of Form A: Bid shall be signed in accordance with the following requirements:

- (a) if the Bidder is a sole proprietor carrying on business in his own name, it shall be signed by the Bidder;
- (b) if the Bidder is a partnership, it shall be signed by the partner or partners who have authority to sign for the partnership;
- (c) if the Bidder is a corporation, it shall be signed by its duly authorized officer or officers and the corporate seal, if the corporation has one, shall be affixed;
- (d) if the Bidder is carrying on business under a name other than his own, it shall be signed by the registered owner of the business name, or by the registered owner's authorized officials if the owner is a partnership or a corporation.

B8.4.1 The name and official capacity of all individuals signing Form A: Bid should be printed below such signatures.

B8.5 If a Bid is submitted jointly by two or more persons, the word "Bidder" shall mean each and all such persons, and the undertakings, covenants and obligations of such joint Bidders in the Bid and the Contract, when awarded, shall be both joint and several.

## **B9. PRICES**

B9.1 The Bidder shall state a price in Canadian funds for each item of the Work identified on Form B: Prices.

B9.1.1 For the convenience of Bidders, and pursuant to B7.4.2 and B15.4.3, an electronic spreadsheet Form B: Prices in Microsoft Excel (.xls) format is available along with the Adobe PDF documents for this Bid Opportunity on the Bid Opportunities page at the Materials Management Division website at <http://www.winnipeg.ca/matmgt>

B9.2 The quantities listed on Form B: Prices are to be considered approximate only. The City will use said quantities for the purpose of comparing Bids.

B9.3 The quantities for which payment will be made to the Contractor are to be determined by the Work actually performed and completed by the Contractor, to be measured as specified in the applicable Specifications.

B9.4 Prices from Non-Resident Bidders are subject to a Non-Resident Withholding Tax pursuant to the Income Tax Act (Canada).

## **B10. QUALIFICATION**

B10.1 The Bidder shall:

- (a) undertake to be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba; and
- (b) be financially capable of carrying out the terms of the Contract; and
- (c) have all the necessary experience, capital, organization, and equipment to perform the Work in strict accordance with the terms and provisions of the Contract.

- B10.2 The Bidder and any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:
- (a) be responsible and not be suspended, debarred or in default of any obligations to the City. A list of suspended or debarred individuals and companies is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt/debar.stm>
- B10.3 The Bidder and/or any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:
- (a) have successfully carried out work similar in nature, scope and value to the Work; and
  - (b) be fully capable of performing the Work required to be in strict accordance with the terms and provisions of the Contract; and
  - (c) have a written workplace safety and health program if required pursuant to The Workplace Safety and Health Act (Manitoba);
- B10.4 Further to B10.3(c), the Bidder shall, within five (5) Business Days of a request by the Contract Administrator, provide proof satisfactory to the Contract Administrator that the Bidder/Subcontractor has a workplace safety and health program meeting the requirements of The Workplace Safety and Health Act (Manitoba), by providing:
- (a) a valid COR certification number under the Certificate of Recognition (COR) Program administered by the Manitoba Construction Safety Association or by the Manitoba Heavy Construction Association's Safety, Health and Environment Program; or
  - (b) a report or letter to that effect from an independent reviewer acceptable to the City. (A list of acceptable reviewers and the review template are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt>)
- B10.5 The Bidder shall submit, within three (3) Business Days of a request by the Contract Administrator, proof satisfactory to the Contract Administrator of the qualifications of the Bidder and of any proposed Subcontractor.
- B10.6 The Bidder shall provide, on the request of the Contract Administrator, full access to any of the Bidder's equipment and facilities to confirm, to the Contract Administrator's satisfaction, that the Bidder's equipment and facilities are adequate to perform the Work.

## **B11. BID SECURITY**

- B11.1 The Bidder shall provide bid security in the form of:
- (a) a bid bond, in the amount of at least ten percent (10%) of the Total Bid Price, and agreement to bond of a company registered to conduct the business of a surety in Manitoba, in the form included in the Bid Submission (Form G1: Bid Bond and Agreement to Bond); or
  - (b) an irrevocable standby letter of credit, in the amount of at least ten percent (10%) of the Total Bid Price, and undertaking issued by a bank or other financial institution registered to conduct business in Manitoba and drawn on a branch located in Winnipeg, in the form included in the Bid Submission (Form G2: Irrevocable Standby Letter of Credit and Undertaking); or
  - (c) a certified cheque or draft payable to "The City of Winnipeg", in the amount of at least fifty percent (50%) of the Total Bid Price, drawn on a bank or other financial institution registered to conduct business in Manitoba.
- B11.1.1 If the Bidder submits alternative bids, the bid security shall be in the amount of the specified percentage of the highest Total Bid Price submitted.
- B11.1.2 All signatures on bid securities shall be original.
- B11.1.3 The Bidder shall sign the Bid Bond.



- B11.1.4 The Surety shall sign and affix its corporate seal on the Bid Bond and the Agreement to Bond.
- B11.2 The bid security of the successful Bidder and the next two lowest evaluated responsive and responsible Bidders will be released by the City when a Contract for the Work has been duly executed by the successful Bidder and the performance security furnished as provided herein. The bid securities of all other Bidders will be released when a Contract is awarded.
- B11.2.1 Where the bid security provided by the successful Bidder is in the form of a certified cheque or draft pursuant to B11.1(c), it will be deposited and retained by the City as the performance security and no further submission is required.
- B11.2.2 The City will not pay any interest on certified cheques or drafts furnished as bid security or subsequently retained as performance security.
- B11.3 The bid securities of all Bidders will be released by the City as soon as practicable following notification by the Contract Administrator to the Bidders that no award of Contract will be made pursuant to the Bid Opportunity.

## **B12. OPENING OF BIDS AND RELEASE OF INFORMATION**

- B12.1 Bids will be opened publicly, after the Submission Deadline has elapsed, in the office of the Corporate Finance Department, Materials Management Division, or in such other office as may be designated by the Manager of Materials.
- B12.1.1 Bidders or their representatives may attend.
- B12.1.2 Bids determined by the Manager of Materials, or his designate, to not include the bid security specified in B11 will not be read out.
- B12.2 Following the submission deadline, the names of the Bidders and their Total Bid Prices (unevaluated, and pending review and verification of conformance with requirements) will be available on the Closed Bid Opportunities (or Public/Posted Opening & Award Results) page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt>
- B12.3 After award of Contract, the name(s) of the successful Bidder(s) and the Contract Amount(s) will be available on the Closed Bid Opportunities (or Public/Posted Opening & Award Results) page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt>
- B12.4 The Bidder is advised that any information contained in any Bid may be released if required by City policy or procedures, by The Freedom of Information and Protection of Privacy Act (Manitoba), by other authorities having jurisdiction, or by law.

## **B13. IRREVOCABLE BID**

- B13.1 The Bid(s) submitted by the Bidder shall be irrevocable for the time period specified in Paragraph 11 of Form A: Bid.
- B13.2 The acceptance by the City of any Bid shall not release the Bids of the next two lowest evaluated responsive Bidders and these Bidders shall be bound by their Bids on such Work until a Contract for the Work has been duly executed and the performance security furnished as herein provided, but any Bid shall be deemed to have lapsed unless accepted within the time period specified in Paragraph 11 of Form A: Bid.

## **B14. WITHDRAWAL OF BIDS**

- B14.1 A Bidder may withdraw his Bid without penalty by giving written notice to the Manager of Materials at any time prior to the Submission Deadline.

- B14.1.1 Notwithstanding C23.3, the time and date of receipt of any notice withdrawing a Bid shall be the time and date of receipt as determined by the Manager of Materials.
- B14.1.2 The City will assume that any one of the contact persons named in Paragraph 3 of Form A: Bid or the Bidder's authorized representatives named in Paragraph 12 of Form A: Bid, and only such person, has authority to give notice of withdrawal.
- B14.1.3 If a Bidder gives notice of withdrawal prior to the Submission Deadline, the Manager of Materials will:
- (a) retain the Bid until after the Submission Deadline has elapsed;
  - (b) open the Bid to identify the contact person named in Paragraph 3 of Form A: Bid and the Bidder's authorized representatives named in Paragraph 12 of Form A: Bid; and
  - (c) if the notice has been given by any one of the persons specified in B14.1.3(b), declare the Bid withdrawn.
- B14.2 A Bidder who withdraws his Bid after the Submission Deadline but before his Bid has been released or has lapsed as provided for in B13.2 shall be liable for such damages as are imposed upon the Bidder by law and subject to such sanctions as the Chief Administrative Officer considers appropriate in the circumstances. The City, in such event, shall be entitled to all rights and remedies available to it at law, including the right to retain the Bidder's bid security.

## **B15. EVALUATION OF BIDS**

- B15.1 Award of the Contract shall be based on the following bid evaluation criteria:
- (a) compliance by the Bidder with the requirements of the Bid Opportunity, or acceptable deviation therefrom (pass/fail);
  - (b) qualifications of the Bidder and the Subcontractors, if any, pursuant to B10 (pass/fail);
  - (c) Total Bid Price;
  - (d) economic analysis of any approved alternative pursuant to B6.
- B15.2 Further to B15.1(a), the Award Authority may reject a Bid as being non-responsive if the Bid is incomplete, obscure or conditional, or contains additions, deletions, alterations or other irregularities. The Award Authority may reject all or any part of any Bid, or waive technical requirements or minor informalities or irregularities, if the interests of the City so require.
- B15.3 Further to B15.1(b), the Award Authority shall reject any Bid submitted by a Bidder who does not demonstrate, in his Bid or in other information required to be submitted, that he is responsible and qualified.
- B15.4 Further to B15.1(c), the Total Bid Price shall be the sum of the quantities multiplied by the unit prices for each item shown on Form B: Prices.
- B15.4.1 If there is any discrepancy between the Total Bid Price written in figures, the Total Bid Price written in words and the sum of the quantities multiplied by the unit prices for each item, the sum of the quantities multiplied by the unit prices for each item shall take precedence.
- B15.4.2 Further to B15.1(a), in the event that a unit price is not provided on Form B: Prices, the City will determine the unit price by dividing the Amount (extended price) by the approximate quantity, for the purposes of evaluation and payment.
- B15.4.3 The electronic Form B: Prices and the formulas imbedded in that spreadsheet are only provided for the convenience of Bidders. The City makes no representations or warranties as to the correctness of the imbedded formulas. It is the Bidder's responsibility to ensure the extensions of the unit prices and the sum of Total Bid Price performed as a function of the formulas within the electronic Form B: Prices are correct.

**B16. AWARD OF CONTRACT**

- B16.1 The City will give notice of the award of the Contract or will give notice that no award will be made.
- B16.2 The City will have no obligation to award a Contract to a Bidder, even though one or all of the Bidders are determined to be responsible and qualified, and the Bids are determined to be responsive.
- B16.2.1 Without limiting the generality of B16.2, the City will have no obligation to award a Contract where:
- (a) the prices exceed the available City funds for the Work;
  - (b) the prices are materially in excess of the prices received for similar work in the past;
  - (c) the prices are materially in excess of the City's cost to perform the Work, or a significant portion thereof, with its own forces;
  - (d) only one Bid is received; or
  - (e) in the judgment of the Award Authority, the interests of the City would best be served by not awarding a Contract.
- B16.3 Where an award of Contract is made by the City, the award shall be made to the responsible and qualified Bidder submitting the lowest evaluated responsive Bid, in accordance with B15.
- B16.3.1 Following the award of contract, a Bidder will be provided with information related to the evaluation of his Bid upon written request to the Contract Administrator.

## **PART C - GENERAL CONDITIONS**

### **C0. GENERAL CONDITIONS**

- C0.1 The *General Conditions for Construction* (Revision 2006 12 15) are applicable to the Work of the Contract.
- C0.1.1 The *General Conditions for Construction* are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at [http://www.winnipeg.ca/matmgt/gen\\_cond.stm](http://www.winnipeg.ca/matmgt/gen_cond.stm)
- C0.2 A reference in the Bid Opportunity to a section, clause or subclause with the prefix “**C**” designates a section, clause or subclause in the *General Conditions for Construction*.

## **PART D - SUPPLEMENTAL CONDITIONS**

### **GENERAL**

#### **D1. GENERAL CONDITIONS**

D1.1 In addition to the General Conditions for Construction, these Supplemental Conditions are applicable to the Work of the Contract.

#### **D2. SCOPE OF WORK**

D2.1 The Work to be done under the Contract shall consist of:

- (a) Pavement Reconstruction
  - (i) De Bourmont Avenue – Autumnwood Road to Elizabeth Road
- (b) Crack and Seating of Existing Concrete Pavement
  - (i) Berrydale Avenue – St. Mary's Road to St. David Road
- (c) Major Rehabilitation
  - (i) Farnham Road – Beaverhill Boulevard to Cherwell Road

D2.2 The major components of the Work are as follows:

- (a) Pavement Reconstruction
  - (i) Remove existing concrete pavement with asphalt overlay
  - (ii) Excavation
  - (iii) Compaction of existing sub-grade
  - (iv) Installation of catch pits and connection pipe
  - (v) Placement of separation fabric
  - (vi) Placement of sub-base and base course materials
  - (vii) Adjustment of existing manholes
  - (viii) Construct 200mm concrete pavement (reinforced)
  - (ix) Construct 180mm barrier curb (separate) utilizing slip-form paving equipment
  - (x) Sidewalk repairs
  - (xi) Boulevard restoration and placement of sod
- (b) Crack and Seating of Existing Concrete Pavement
  - (i) Curb removal
  - (ii) Crack and seat existing pavement
  - (iii) Complete sidewalk renewal
  - (iv) Installation of catch pits and connection pipe
  - (v) Complete pavement patching
  - (vi) Construct curb
  - (vii) Complete curb renewal at intersections
  - (viii) Placement asphalt overlay complete with moisture/stress absorption fabric (average thickness – 100mm)
  - (ix) Boulevard restoration
- (c) Major Rehabilitation
  - (i) Plane existing asphalt pavement as required
  - (ii) Plane lip curb
  - (iii) Full depth repair of existing joints and slabs
  - (iv) Renewal of existing curb utilizing slip-form paving equipment
  - (v) Curb renewal at intersections

- (vi) Renewal of existing sidewalk as required
- (vii) Installation of catch pits and connection pipe
- (viii) Placement asphalt overlay (Average thickness 80mm)

**D3. CONTRACT ADMINISTRATOR**

D3.1 The Contract Administrator is Genivar, represented by:

Scott Minty  
Project Manager  
10 Prairie Way, Winnipeg, Manitoba, R2J 3J8  
Telephone No. (204) 477-6650  
Facsimile No. (204) 474-2864

D3.2 At the pre-construction meeting, Scott Minty will identify additional personnel representing the Contract Administrator and their respective roles and responsibilities for the Work.

**D4. CONTRACTOR'S SUPERVISOR**

D4.1 At the pre-construction meeting, the Contractor shall identify his designated supervisor and any additional personnel representing the Contractor and their respective roles and responsibilities for the Work.

D4.2 At least two (2) business days prior to the commencement of any Work on the site, the Contractor shall provide the Contract Administrator with a phone number where the supervisor identified in D4.1 or an alternate can be contacted twenty-four (24) hours a day to respond to an emergency.

**D5. NOTICES**

D5.1 Except as provided for in C23.2.2, all notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications to the Contractor shall be sent to the address or facsimile number identified by the Contractor in Paragraph 2 of Form A: Bid.

D5.2 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications to the City, except as expressly otherwise required in D5.3, D5.4 or elsewhere in the Contract, shall be sent to the attention of the Contract Administrator at the address or facsimile number identified in D3.1.

D5.3 Notwithstanding C21., all notices of appeal to the Chief Administrative Officer shall be sent to the attention of the Chief Financial Officer at the following address or facsimile number:

The City of Winnipeg  
Chief Financial Officer  
Administration Building, 3rd Floor  
510 Main Street  
Winnipeg MB R3B 1B9  
Facsimile No.: (204) 949-1174

D5.4 All notices, requests, nominations, proposals, consents, approvals, statements, authorizations, documents or other communications required to be submitted or returned to the City Solicitor shall be sent to the following address or facsimile number:

The City of Winnipeg  
Internal Services Department  
Legal Services Division  
Attn: City Solicitor

185 King Street, 3rd Floor  
Winnipeg MB R3B 1J1  
Facsimile No.: (204) 947-9155

## **D6. FURNISHING OF DOCUMENTS**

- D6.1 Upon award of the Contract, the Contractor will be provided with five (5) complete sets of the Bid Opportunity. If the Contractor requires additional sets of the Bid Opportunity, they will be supplied to him at cost.

## **SUBMISSIONS**

### **D7. AUTHORITY TO CARRY ON BUSINESS**

- D7.1 The Contractor shall be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Contractor does not carry on business in Manitoba, in the jurisdiction where the Contractor does carry on business, throughout the term of the Contract, and shall provide the Contract Administrator with evidence thereof upon request.

### **D8. SAFE WORK PLAN**

- D8.1 The Contractor shall provide the Contract Administrator with a Safe Work Plan at least five (5) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract.
- D8.2 The Safe Work Plan shall be prepared and submitted in the format shown in the City's template which is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt/safety/default.stm>

### **D9. INSURANCE**

- D9.1 The Contractor shall provide and maintain the following insurance coverage:
- (a) commercial general liability insurance, in the amount of at least two million dollars (\$2,000,000.00) inclusive, with The City of Winnipeg added as an additional insured, with a cross-liability clause, such liability policy to also contain contractual liability, unlicensed motor vehicle liability, non-owned automobile liability, broad form property damage cover and products and completed operations, to remain in place at all times during the performance of the Work and throughout the warranty period;
  - (b) automobile liability insurance for owned automobiles used for or in connection with the Work in the amount of at least two million dollars (\$2,000,000.00) at all times during the performance of the Work and until the date of Total Performance;
  - (c) an all risks Installation Floater carrying adequate limits to cover all machinery, equipment, supplies and/or materials intended to enter into and form part of any installation.
- D9.2 Deductibles shall be borne by the Contractor.
- D9.3 The Contractor shall provide the City Solicitor with a certificate(s) of insurance, in a form satisfactory to the City Solicitor, at least two (2) Business Days prior to the commencement of any Work but in no event later than the date specified in the C4.1 for the return of the executed Contract.
- D9.4 The Contractor shall not cancel, materially alter, or cause each policy to lapse without providing at least thirty (30) Calendar Days prior written notice to the Contract Administrator.

## **D10. PERFORMANCE SECURITY**

- D10.1 The Contractor shall provide and maintain performance security until the expiration of the warranty period in the form of:
- (a) a performance bond of a company registered to conduct the business of a surety in Manitoba, in the form attached to these Supplemental Conditions (Form H1: Performance Bond), in the amount of fifty percent (50%) of the Contract Price; or
  - (b) an irrevocable standby letter of credit issued by a bank or other financial institution registered to conduct business in Manitoba and drawn on a branch located in Winnipeg, in the form attached to these Supplemental Conditions (Form H2: Irrevocable Standby Letter of Credit), in the amount of fifty percent (50%) of the Contract Price; or
  - (c) a certified cheque or draft payable to "The City of Winnipeg", drawn on a bank or other financial institution registered to conduct business in Manitoba, in the amount of fifty percent (50%) of the Contract Price.
- D10.1.1 Where the performance security is in the form of a certified cheque or draft, it will be deposited by the City. The City will not pay any interest on certified cheques or drafts furnished as performance security.
- D10.2 If the bid security provided in his Bid was not a certified cheque or draft pursuant to B11.1(c), the Contractor shall provide the City Solicitor with the required performance security within seven (7) Calendar Days of notification of the award of the Contract by way of letter of intent and prior to the commencement of any Work on the Site and in no event later than the date specified in the C4.1 for the return of the executed Contract.

## **D11. SUBCONTRACTOR LIST**

- D11.1 The Contractor shall provide the Contract Administrator with a complete list of the Subcontractors whom the Contractor proposes to engage (Form J: Subcontractor List) at or prior to a pre-construction meeting, or at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in the C4.1 for the return of the executed Contract.

## **D12. EQUIPMENT LIST**

- D12.1 The Contractor shall provide the Contract Administrator with a complete list of the equipment which the Contractor proposes to utilize (Form K: Equipment List) at or prior to a pre-construction meeting, or at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in the C4.1 for the return of the executed Contract.

## **D13. DETAILED WORK SCHEDULE**

- D13.1 The Contractor shall provide the Contract Administrator with a detailed work schedule at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in the General Conditions for the return of the executed Contract.

## **SCHEDULE OF WORK**

### **D14. COMMENCEMENT**

- D14.1 The Contractor shall not commence any Work until he is in receipt of a letter of intent from the Award Authority authorizing the commencement of the Work.
- D14.2 The Contractor shall not commence any Work on the Site until:
- (a) the Contract Administrator has confirmed receipt and approval of:
    - (i) evidence of authority to carry on business specified in D7;



- (ii) evidence of the workers compensation coverage specified in C6.15;
  - (iii) the twenty-four (24) hour emergency response phone number specified in D4.2.
  - (iv) the Safe Work Plan specified in D8;
  - (v) evidence of the insurance specified in D9;
  - (vi) the performance security specified in D10;
  - (vii) the subcontractor list specified in D11;
  - (viii) the equipment list specified in D12;
  - (ix) the detailed work schedule specified in D13.
- (b) the Contractor has attended a pre-construction meeting with the Contract Administrator, or the Contract Administrator has waived the requirement for a pre-construction meeting.
- D14.3 The Contractor shall commence the Work on the Site within seven (7) Working Days of receipt of the letter of intent.
- D14.3.1 If the actual date of award is later than the intended date, the dates specified for Substantial Performance, and Total Performance will be adjusted by the difference between the aforementioned intended and actual dates

#### **D15. WORKING DAYS**

- D15.1 Further to C1.1(gg);
- D15.1.1 The Contract Administrator will determine daily if a Working Day has elapsed and will record his assessment. On a weekly basis the Contract Administrator will provide the Contractor with a record of the Working Days assessed for the preceding week. The Contractor shall sign each report signifying that he agrees with the Contract Administrator's determination of the Working Days assessed for the report period.
- D15.1.2 Work done to restore the Site to a condition suitable for Work, shall not be considered "work" as defined in the definition of a Working Day.

#### **D16. RESTRICTED WORK HOURS**

- D16.1 Further to clause 3.10 of CW 1130, the Contractor shall require written permission forty-eight (48) hours in advance from the Contract Administrator for any work to be performed between 2000 hours and 0700 hours, or on Saturdays, Sundays, Statutory Holidays and or Civic Holidays.

#### **D17. WORK BY OTHERS**

- D17.1 Work by others on or near the Site will include but not necessarily be limited to:
- (a) Manitoba Hydro – Gas Division;
  - (b) Traffic Services Sign Replacement.

#### **D18. SEQUENCE OF WORK**

- D18.1 Further to C6.1, the sequence of work shall comply with the following:
- D18.1.1 Providing that the Work on each street is completed in a similar order to the order that the Work was commenced in, the Contractor will be permitted to have a maximum of three (3) streets under construction at any one time. Completion of a street means that all of the necessary concrete, asphalt including approaches and landscaping Work is completed to the satisfaction of the Contract Administrator.
- D18.1.2 Where the Contractor utilizes two (2) or more crews that work independently on the same major component of the Work as identified in D2, the Contract Administrator may approve an increase to the maximum number of streets under construction at any time.

- D18.1.3 Placing the topsoil and finished grading of all boulevard and median areas shall be completed prior to commencing construction of asphaltic concrete overlays, including scratch courses.
- D18.1.4 The Pavement Reconstruction on De Bourmont Avenue shall not commence until completion of the associated watermain renewal. The watermain renewal is estimated for completion by July 15, 2010.
- D18.1.5 Each Site requiring subdividing shall be subdivided into Phases. Each phase will include items of work shown in D2.2(a).
- (a) Pavement Reconstruction – De Bourmont Avenue
    - (i) Construction activity is to be restricted to the limits described for each phase. No construction shall commence on the subsequent phase of De Bourmont Avenue until all work on the preceding phase has been completed.
    - (ii) Phase 1 – Autumnwood Road to Station 3+05
    - (iii) Phase 2 – Station 3+05 to Elizabeth Road

## **D19. SUBSTANTIAL PERFORMANCE**

- D19.1 The Contractor shall achieve Substantial Performance within Fifty Five (55) consecutive Working Days of the commencement of the Work as specified in D14.
- D19.2 When the Contractor considers the Work to be substantially performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Substantial Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be re-inspected.
- D19.3 The date on which the Work has been certified by the Contract Administrator as being substantially performed to the requirements of the Contract through the issue of a certificate of Substantial Performance is the date on which Substantial Performance has been achieved.

## **D20. TOTAL PERFORMANCE**

- D20.1 The Contractor shall achieve Total Performance within Sixty (60) consecutive Working Days of the commencement of the Work as specified in D14.
- D20.2 When the Contractor or the Contract Administrator considers the Work to be totally performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Total Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be re-inspected.
- D20.3 The date on which the Work has been certified by the Contract Administrator as being totally performed to the requirements of the Contract through the issue of a certificate of Total Performance is the date on which Total Performance has been achieved.

## **D21. LIQUIDATED DAMAGES**

- D21.1 If the Contractor fails to achieve Substantial Performance in accordance with the Contract by the day fixed herein for Substantial Performance, the Contractor shall pay the City one thousand five hundred dollars (\$1500) per working day for each and every working day following the day fixed herein for Substantial Performance during which such failure continues.
- D21.2 The amount specified for liquidated damages in D21.1 is based on a genuine pre-estimate of the City's damages in the event that the Contractor does not achieve Substantial Performance by the day fixed herein for same.

D21.3 The City may reduce any payment to the Contractor by the amount of any liquidated damages assessed.

## **D22. SCHEDULED MAINTENANCE**

D22.1 The Contractor shall perform the following scheduled maintenance in the manner and within the time periods required by the Specifications:

- (a) Sodding as specified in CW-3510-R9;
- (b) Reflective Crack Sealing as specified in CW-3250-R7;

D22.2 Determination of Substantial Performance and Total Performance shall be exclusive of scheduled maintenance identified herein. All scheduled maintenance shall be completed prior to the expiration of the warranty period. Where the scheduled maintenance cannot be completed during the warranty period, the warranty period shall be extended for such period of time as it takes the Contractor to complete the scheduled maintenance.

## **CONTROL OF WORK**

### **D23. JOB MEETINGS**

D23.1 Regular weekly job meetings will be held at the site. These meetings shall be attended by a minimum of one representative of the Contract Administrator, one representative of the City and one representative of the Contractor. Each representative shall be a responsible person capable of expressing the position of the Contract Administrator, the City and the Contractor respectively on any matter discussed at the meeting including the Work schedule and the need to make any revisions to the Work schedule. The progress of the Work will be reviewed at each of these meetings.

D23.2 The Contract Administrator reserves the right to cancel any job meeting or call additional job meetings whenever he deems it necessary.

### **D24. PRIME CONTRACTOR – THE WORKPLACE SAFETY AND HEALTH ACT (MANITOBA)**

D24.1 Further to C6.24, the Contractor shall be the Prime Contractor and shall serve as, and have the duties of the Prime Contractor in accordance with The Workplace Safety and Health Act (Manitoba).

## **WARRANTY**

### **D25. WARRANTY**

D25.1 Notwithstanding C13.2, the warranty period shall begin on the date of Total Performance and shall expire one (1) years thereafter for crack and seating and rehabilitation works ; and two (2) years thereafter for pavement reconstruction works, unless extended pursuant to C13.2.1 or C13.2.2, in which case it shall expire when provided for thereunder.

D25.2 Notwithstanding C13.2 or D25.1, the Contract Administrator may permit the warranty period for a portion or portions of the Work to begin prior to the date of substantial Performance if:

- (a) a portion of the Work cannot be completed because of unseasonable weather or other conditions reasonably beyond the control of the Contractor but that portion does not prevent the balance of the Work from being put to its intended use; or

D25.2.1 In such case the date specified by the Contract Administrator for the warranty period to begin shall be substituted for the date specified in C13.2 for the warranty period to begin.

**H1: PERFORMANCE BOND**  
(See D10)

KNOW ALL MEN BY THESE PRESENTS THAT

\_\_\_\_\_ ,  
(hereinafter called the "Principal"), and

\_\_\_\_\_ ,  
(hereinafter called the "Surety"), are held and firmly bound unto **THE CITY OF WINNIPEG** (hereinafter called the "Obligee"), in the sum of

\_\_\_\_\_ dollars (\$\_\_\_\_\_)

of lawful money of Canada to be paid to the Obligee, or its successors or assigns, for the payment of which sum the Principal and the Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS the Principal has entered into a written contract with the Obligee for

BID OPPORTUNITY NO. 271-2010

2010 RESIDENTAL STREET RENEWALS – DE BOURMONT AVENUE, BERRYDALE AVENUE AND FARNHAM ROAD

which is by reference made part hereof and is hereinafter referred to as the "Contract".

NOW THEREFORE the condition of the above obligation is such that if the Principal shall:

- (a) carry out and perform the Contract and every part thereof in the manner and within the times set forth in the Contract and in accordance with the terms and conditions specified in the Contract;
- (b) perform the Work in a good, proper, workmanlike manner;
- (c) make all the payments whether to the Obligee or to others as therein provided;
- (d) in every other respect comply with the conditions and perform the covenants contained in the Contract; and
- (e) indemnify and save harmless the Obligee against and from all loss, costs, damages, claims, and demands of every description as set forth in the Contract, and from all penalties, assessments, claims, actions for loss, damages or compensation whether arising under "The Workers Compensation Act", or any other Act or otherwise arising out of or in any way connected with the performance or non-performance of the Contract or any part thereof during the term of the Contract and the warranty period provided for therein;

THEN THIS OBLIGATION SHALL BE VOID, but otherwise shall remain in full force and effect. The Surety shall not, however, be liable for a greater sum than the sum specified above.

AND IT IS HEREBY DECLARED AND AGREED that the Surety shall be liable as Principal, and that nothing of any kind or matter whatsoever that will not discharge the Principal shall operate as a discharge or release of liability of the Surety, any law or usage relating to the liability of Sureties to the contrary notwithstanding.

IN WITNESS WHEREOF the Principal and Surety have signed and sealed this bond the

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_ .

SIGNED AND SEALED  
in the presence of:

\_\_\_\_\_  
(Witness as to Principal if no seal)

\_\_\_\_\_  
(Name of Principal)

Per: \_\_\_\_\_ (Seal)

Per: \_\_\_\_\_

\_\_\_\_\_  
(Name of Surety)

By: \_\_\_\_\_ (Seal)  
(Attorney-in-Fact)

**FORM H2: IRREVOCABLE STANDBY LETTER OF CREDIT  
(PERFORMANCE SECURITY)**  
(See D10)

\_\_\_\_\_  
(Date)

The City of Winnipeg  
Internal Services Department  
Legal Services Division  
185 King Street, 3rd Floor  
Winnipeg MB R3B 1J1

RE: PERFORMANCE SECURITY – BID OPPORTUNITY NO. 271-2010

2010 RESIDENTIAL STREET RENEWALS – DE BOURMONT AVENUE, BERRYDALE AVENUE AND  
FARNHAM ROAD

Pursuant to the request of and for the account of our customer,

\_\_\_\_\_  
(Name of Contractor)

\_\_\_\_\_  
(Address of Contractor)

WE HEREBY ESTABLISH in your favour our irrevocable Standby Letter of Credit for a sum not exceeding  
in the aggregate

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_ Canadian dollars.

This Standby Letter of Credit may be drawn on by you at any time and from time to time upon written demand for payment made upon us by you. It is understood that we are obligated under this Standby Letter of Credit for the payment of monies only and we hereby agree that we shall honour your demand for payment without inquiring whether you have a right as between yourself and our customer to make such demand and without recognizing any claim of our customer or objection by the customer to payment by us.

The amount of this Standby Letter of Credit may be reduced from time to time only by amounts drawn upon it by you or by formal notice in writing given to us by you if you desire such reduction or are willing that it be made.

Partial drawings are permitted.

We engage with you that all demands for payment made within the terms and currency of this Standby Letter of Credit will be duly honoured if presented to us at:

\_\_\_\_\_  
(Address)

and we confirm and hereby undertake to ensure that all demands for payment will be duly honoured by us.

All demands for payment shall specifically state that they are drawn under this Standby Letter of Credit.

Subject to the condition hereinafter set forth, this Standby Letter of Credit will expire on

\_\_\_\_\_  
(Date)

It is a condition of this Standby Letter of Credit that it shall be deemed to be automatically extended from year to year without amendment from the present or any future expiry date, unless at least 30 days prior to the present or any future expiry date, we notify you in writing that we elect not to consider this Standby Letter of Credit to be renewable for any additional period.

This Standby Letter of Credit may not be revoked or amended without your prior written approval.

This credit is subject to the Uniform Customs and Practice for Documentary Credit (1993 Revision), International Chamber of Commerce Publication Number 500.

\_\_\_\_\_  
(Name of bank or financial institution)

Per: \_\_\_\_\_  
(Authorized Signing Officer)

Per: \_\_\_\_\_  
(Authorized Signing Officer)

**FORM J: SUBCONTRACTOR LIST**  
(See D11)

2010 RESIDENTIAL STREET RENEWALS – DE BOURMONT AVENUE, BERRYDALE AVENUE AND  
FARNHAM ROAD

<u>Portion of the Work</u>	<u>Name</u>	<u>Address</u>
<b>SURFACE WORKS:</b>		
<i>Supply of Materials:</i>		
<i>Concrete</i>		
<i>Asphalt</i>		
<i>Base Course &amp; Sub-Base</i>		
<i>Planing</i>		
<i>Crack and Seating</i>		
<i>Installation/Placement:</i>		
<i>Excavation/Pavement Removal</i>		
<i>Asphalt</i>		
<i>Sod</i>		
<b>UNDERGROUND WORKS:</b>		
<i>Supply of Materials:</i>		
<i>Catch pits</i>		
<i>Catch basins</i>		
<i>Installation/Placement:</i>		
<i>Catch pits</i>		
<i>Catch basins</i>		
<b>OTHERS:</b>		
<i>Reflective Crack Maintenance</i>		



**FORM K: EQUIPMENT**  
(See D12)

2010 RESIDENTIAL STREET RENEWALS – DE BOURMONT AVENUE, BERRYDALE AVENUE AND  
FARNHAM ROAD

<p><b>1. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>
<p><b>2. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>
<p><b>3. Category/type:</b></p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p> <p>Make/Model/Year: _____ Serial No.: _____</p> <p>Registered owner: _____</p>

**FORM K: EQUIPMENT**  
(See D12)

2010 RESIDENTIAL STREET RENEWALS – DE BOURMONT AVENUE, BERRYDALE AVENUE AND  
FARNHAM ROAD

**4. Category/type:**

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

**5. Category/type:**

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

**6. Category/type:**

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

Make/Model/Year: \_\_\_\_\_ Serial No.: \_\_\_\_\_

Registered owner: \_\_\_\_\_

## PART E - SPECIFICATIONS

### GENERAL

#### E1. APPLICABLE SPECIFICATIONS AND DRAWINGS

- E1.1 These Specifications shall apply to the Work.
- E1.2 *The City of Winnipeg Standard Construction Specifications* in its entirety, whether or not specifically listed on Form B: Prices, shall apply to the Work.
- E1.2.1 *The City of Winnipeg Standard Construction Specifications* is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Materials Management Division website at <http://www.winnipeg.ca/matmgt/Spec/Default.stm>
- E1.2.2 The version in effect three (3) Business Days before the Submission Deadline shall apply.
- E1.2.3 Further to C2.4(d), Specifications included in the Bid Opportunity shall govern over *The City of Winnipeg Standard Construction Specifications*.
- E1.3 The following are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing Name/Title</u>	<u>Drawing (Original) Sheet Size</u>
271-2010_09169-00	Cover Sheet	36x24
271-2010_09169-01	De Bourmont Avenue Autumnwood Road to Station 1+90	36x24
271-2010_09169-02	De Bourmont Avenue Station 1+90 to Station 2+75	36x24
271-2010_09169-03	De Bourmont Avenue Station 2+75 to Station 3+95	36x24
271-2010_09169-04	De Bourmont Avenue Station 3+95 to Elizabeth Road	36x24
271-2010_09169-05	Berrydale Avenue St. Mary's Road to St. David Road	Letter
271-2010_09169-06	Farnham Road Beaverhill Boulevard to Cherwell Road	Letter

#### E2. GEOTECHNICAL REPORT

- E2.1 Further to C3.1, the geotechnical report is provided to aid the Contractor's evaluation of the existing soil conditions. The geotechnical report is contained in Appendix 'A'.

#### E3. OFFICE FACILITIES

- E3.1 The Contractor shall supply office facilities meeting the following requirements:
- The field office shall be for the exclusive use of the Contract Administrator.
  - The building shall be conveniently located near the site of the Work.
  - The building shall have a minimum floor area of 20 square metres, with two windows and a door entrance with a suitable lock.
  - The building shall be suitable for all weather use. It shall be equipped with an electric heater and air conditioner so that the room temperature can be maintained between either 16-18°C or 24-25°C.
  - The building shall be adequately lighted with fluorescent fixtures and have a minimum of three wall outlets.
  - The building shall be furnished with one desk, one table, and six chairs.

- (g) A portable toilet shall be located near the field office building. The toilet shall have a locking door and be for the exclusive use of the Contract Administrator and other personnel from the City.
- (h) The field office building and the portable toilet shall be cleaned on a weekly basis immediately prior to each site meeting. The Contract Administrator may request additional cleaning when he deems it necessary.

- E3.2 The Contractor shall be responsible for all installation and removal costs, all operating costs, and the general maintenance of the office facilities.
- E3.3 The office facilities will be provided from the date of the commencement of the Work to the date of Substantial Performance.
- E3.4 On a one time basis, where directed by the Contract Administrator, the Contractor shall relocate the office facilities to a location more convenient for the remaining Work.

#### **E4. PROTECTION OF EXISTING TREES**

- E4.1 The Contractor shall take the following precautionary steps to prevent damage from construction activities to existing boulevard trees within the limits of the construction area:
  - (a) The Contractor shall not stockpile materials and soil or park vehicles and equipment on boulevards within 2 metres of trees.
  - (b) Trees identified to be at risk by the Contract Administrator are to be strapped with 25 x 100 x 2400mm wood planks, or suitably protected as approved by the Contract Administrator.
  - (c) Excavation shall be performed in a manner that minimizes damage to the existing root systems. Where possible, excavation shall be carried out such that the edge of the excavation shall be a minimum of 1.5 times the diameter (measured in inches), with the outcome read in feet, from the closest edge of the trunk. Where roots must be cut to facilitate excavation, they shall be pruned neatly at the face of excavation.
  - (d) Operation of equipment within the dripline of the trees shall be kept to the minimum required to perform the work required. Equipment shall not be parked, repaired, refuelled; construction materials shall not be stored, and earth materials shall not be stockpiled within the driplines of trees. The dripline of a tree shall be considered to be the ground surface directly beneath the tips of its outermost branches. The Contractor shall ensure that the operations do not cause flooding or sediment deposition on areas where trees are located.
  - (e) Work on-site shall be carried out in such a manner so as to minimize damage to existing tree branches. Where damage to branches does occur, they shall be neatly pruned.
- E4.2 All damage to existing trees caused by the Contractor's activities shall be repaired to the requirements and satisfaction of the Contract Administrator and the City Forester or his designate.
- E4.3 No separate measurement or payment will be made for the protection of trees.
- E4.4 Except as required in clause E4.1(c) and E4.1(e), Elm trees shall not be pruned at any time between April 1 and July 31.

#### **E5. TRAFFIC CONTROL**

- E5.1 Further to clauses 3.6 and 3.7 of CW 1130:
  - (a) Where directed, the Contractor shall construct and maintain temporary asphalt ramps to alleviate vertical pavement obstructions such as manholes and planing drop-offs to the satisfaction of the Contract Administrator. Payment shall be in accordance with CW3410.
  - (b) In accordance with the Manual of Temporary Traffic Control in Work Areas on City Streets, the Contractor ("Agency" in the manual) shall make arrangements with the Traffic Services Branch of the City of Winnipeg to place all temporary regulatory signs. The Contractor

shall bear all costs associated with the placement of temporary traffic control devices by the Traffic Services Branch of the City of Winnipeg in connection with the works undertaken by the Contractor.

## **E6. TRAFFIC MANAGEMENT**

E6.1 Further to clause 3.7 of CW 1130:

E6.1.1 The Contractor shall schedule construction activities to meet the following:

- (a) De Bourmont Avenue at least one lane for local access traffic shall be maintained northbound (Phase I) and one lane of traffic southbound (Phase II) during their respective construction times. At least one intersection on adjacent bays shall be open at a time.
- (b) Berrydale Avenue will be closed to all traffic. The Contractor shall sign the street "Road Closed" in accordance with the Manual of Temporary Traffic Control.
- (c) Farnham Road will be closed to through traffic. Local access and/or bus traffic shall be maintained. The Contractor shall sign the street "Road Closed Local Access Only" in accordance with the Manual of Temporary Traffic Control.

E6.1.2 Should the Contractor be unable to maintain an existing access to a residence or business, he shall review the planned disruption with the business or residence and the Contract Administrator, and take reasonable measures to minimize the impact. The Contractor shall provide a minimum of 24 hours notification to the affected residence or business and the Contract Administrator, prior to disruption of access.

E6.1.3 Pedestrian and ambulance/emergency vehicle access must be maintained at all times.

## **E7. REFUSE AND RECYCLING COLLECTION**

E7.1 While access to refuse and/or recycling collection vehicles is restricted, on collection day(s) the Contractor shall move all of the affected property owners refuse and/or recycling materials to a nearby common area, prior to an established time, in accordance with E7.2 to permit the normal collection vehicles to collect the materials. Immediately following recycling collection the Contractor shall return recycling receptacles to the addresses marked on the receptacles.

E7.2 Collection Schedule:

### **De Bourmont Avenue.**

*Collection Day(s):*           **4**

### **Berrydale Avenue.**

*Collection Day(s):*           **5**

### **Farnham Road.**

*Collection Day(s):*           **5**

E7.3 No measurement or payment will be made for the work associated with this specification.

## **E8. WATER OBTAINED FROM THE CITY**

E8.1 Further to clause 3.7 of CW 1120, the Contractor shall pay for all costs associated with obtaining water in accordance with the Waterworks By-law, including sewer charges.

## **E9. SURFACE RESTORATIONS**

- E9.1 Further to clause 3.3 of CW 1130, when Total Performance is not achieved in the year the Contract is commenced, the Contractor shall temporarily repair any Work commenced and not completed to the satisfaction of the Contract Administrator. The Contractor shall maintain the temporary repairs in a safe condition as determined by the Contract Administrator until permanent repairs are completed. The Contractor shall bear all costs associated with temporary repairs and their maintenance.

## **E10. INFRASTRUCTURE SIGNS**

- E10.1 The Contractor shall obtain infrastructure signs from the Traffic Services Sign Shop at 421 Osborne Street. The Contractor shall mount each sign securely to a rigid backing material approved by the Contract Administrator. The Contractor shall fasten each sign to a suitable support and erect and maintain one sign at each street as directed by the Contract Administrator. When the Contract Administrator considers the Work on the street complete, the Contractor shall remove and dispose of the signs and supports. No measurement for payment will be made for performing all operations herein described and all other items incidental to the work described

## **E11. CRACK AND SEATING OF EXISTING CONCRETE PAVEMENT**

### DESCRIPTION

- E11.1 General
- E11.1.1 This specification covers the crack and seating of existing concrete pavements.
- E11.2 Definitions
- E11.2.1 Proof Rolling – applying of a dynamic load to a concrete pavement with the intent of cracking and embedding the cracked concrete into the existing base.
- E11.3 Referenced Standard Construction Specifications
- (a) CW 3110 – R12 – Sub-Grade, Sub-Base and Base Course Construction.
  - (b) CW 3240 – R8 – Renewal of Existing Curbs
  - (c) CW 3310 – R14 – Portland Cement Concrete Pavement Works

### CONSTRUCTION METHODS

- E11.4 Curb Removal and Saw-Cutting
- E11.4.1 Remove curb flush with existing pavement.
- E11.4.2 Saw cut full depth at approaches and intersections to isolate approaches and intersections from pavement to be cracked and seated. Saw cut full depth along longitudinal joint.
- E11.5 Crack and Seating
- E11.5.1 The equipment for the crack and seating will be a roller having a single axle, unless approved otherwise by the Contract Administrator. The single axle roller will have a maximum of four (4) pneumatic tire wheels and the wheels will be evenly spaced in one line across the width of the roller and be arranged so that each wheel will carry an approximate equal load when operated over an uneven surface. The centre-to-centre spacing between adjacent wheels will not exceed 800 millimetres. The roller equipment will have a suitable body for ballast loading with a minimum capacity of 40 tonnes and the ability to add additional ballast to a max capacity of 60 tonnes.
- E11.5.2 Complete initial proof rolling of the concrete pavement with the equipment specified in accordance with Clause E11.5.1 of this specification.

- E11.5.3 Complete passes as necessary to ensure that the equipment has contacted the entire pavement surface.
- E11.5.4 Undertake second proof rolling as directed by the Contract Administrator.
- E11.5.5 Loading requirements for each proof rolling will be identified by the Contract Administrator.
- E11.5.6 Avoid proof rolling in areas of instability. Remove existing concrete pavement in areas of instability in accordance with the drawings and with Section 3.1 of CW 3110.
- E11.5.7 One rolling cycle will consist of two complete proof rolling applications to the pavement surface.
- E11.5.8 Complete partial depth saw-cuts at 2/3 the depth of the existing concrete pavement at locations as directed by the Contract Administrator.
- E11.5.9 Complete additional rolling cycles and partial depth saw-cuts until the existing concrete pavement has been cracked to a minimum of 300 millimetres to a maximum of 600 millimetres pieces and the pavement has been seated into the sub-base, as directed by the Contract Administrator.
- E11.5.10 Install curb in accordance with CW 3240.

#### MEASUREMENT AND PAYMENT

#### E11.6 Crack and Seating Pavement

- E11.6.1 Crack and seating of existing concrete pavement will be measured on an area basis and paid for at the Contract Unit Price per square metre for "Crack and Seating Pavement". The area to be paid for will be the total number of square metres of existing concrete pavement cracked and seated in one rolling cycle, in accordance with this specification, accepted and measured by the Contract Administrator.
- E11.6.2 Additional rolling cycles will be measured and paid for as "Crack and Seating Pavement" in accordance with Section E11.6.1 of this specification.
- E11.6.3 Saw-cutting of the existing concrete pavement along the longitudinal joint and at approaches and intersections will be included in the payment for "Crack and Seating Pavement".

#### E11.7 Partial Depth Saw-Cutting

- E11.7.1 Partial depth saw-cutting will be measured on a length basis and paid for at the Contract Unit Price per metre for "Partial Depth Saw-Cutting". The length to be paid for will be the total number of metres of existing concrete pavement saw-cut in accordance with this specification, accepted and measured by the Contract Administrator.

#### E11.8 Curb Renewal

- E11.8.1 Curb renewal will be paid in accordance with CW 3240.

### **E12. SUPPLY AND INSTALLATION OF MOISTURE BARRIER/STRESS ABSORPTION GEOTEXTILE FABRIC**

#### DESCRIPTION

#### E12.1 General

- E12.1.1 This specification covers the supply and installation of Moisture Barrier/Stress Absorption Geotextile.
- E12.1.2 Referenced Standard Construction Specifications
  - (a) CW 3130 – R2 – Supply and Installation of Geotextile Fabrics.
  - (b) CW 3410 – R8 – Asphaltic Concrete Pavement Works.

## MATERIALS

### E12.2 Mill Certificate and Bill of Lading

E12.2.1 Provide mill certificate and bill of lading in accordance with Section 2 of CW 3130.

### E12.3 Storage and Handling

E12.3.1 Store and handle material in accordance with Section 2 of CW 3130.

### E12.4 Moisture Barrier/Stress Absorption Geotextile Fabric

E12.4.1 Geotextile fabric will be non-woven.

E12.4.2 All physical property requirements are minimum average roll values determined in accordance with ASTM 4759. The moisture barrier/stress absorption geotextile fabric will meet or exceed the standards as follows:

PROPERTY	STANDARD	TEST METHOD
Grab Tensile Strength	0.40 kN	ASTM D4632
Grab Elongation	50%	ASTM D4632
Mullen Burst	1240 kPa	ASTM D3786

E12.4.3 Acceptable products will be Amoco-Petromat 4599, MIRAFI MIRAPAVE 400, NILEX-9W99 or an approved equal.

### E12.5 Tack Coat

E12.5.1 Tack coat will be 150 – 200 asphalt cement supplied in accordance with Clause 5.4.2 of CW 3410.

## CONSTRUCTION METHODS

### E12.6 General

E12.6.1 Install moisture barrier/stress absorption geotextile fabric at the locations as shown on the Drawings or as directed by the Contract Administrator.

E12.6.2 Proceed with installation upon completion and acceptance of the asphalt levelling course.

E12.6.3 Ensure pavement surface is clean and free of all dirt, water, oil or foreign materials.

E12.6.4 Apply tack coat with a distribution truck in accordance with manufacturer's specifications and recommendations. Ensure uniform coverage of entire pavement surface.

E12.6.5 Install geotextile fabric in accordance with the manufacturer's specifications and recommendations.

E12.6.6 Only construction equipment required to place the final asphalt surface course will be allowed to travel on the exposed geotextile fabric.

E12.6.7 Replace damaged or improperly placed geotextile fabric.

E12.6.8 All fabric installed must be covered with asphalt the same day.

E12.6.9 Commence placement of asphalt material after the fabric has been placed over the full width of the pavement surface and accepted by the Contract Administrator.

E12.6.10 Ensure temperature of asphalt material does not exceed the melting point of the fabric.



## MEASUREMENT AND PAYMENT

### E12.7 Moisture Barrier/Stress Absorption Geotextile Fabric

- E12.7.1 Supply and installation of Moisture Barrier/Stress Absorption Geotextile Fabric will be measured on an area basis and paid for at the Contract Unit Price per square metre for "Moisture Barrier/Stress Absorption Geotextile Fabric". The area to be paid for will be the total number of square metres of geotextile fabric supplied and installed in accordance with this specification, accepted and measured by the Contract Administrator.
- E12.7.2 The supply and application of the tack coat will be included in the payment for "Moisture Barrier/Stress Absorption Geotextile Fabric".

## E13. PATCHING OF EXISTING PAVEMENT

### DESCRIPTION

#### E13.1 General

- E13.1.1 This specification covers patching of existing concrete pavement in preparation for an asphalt overlay.
- E13.1.2 Referenced Standard Construction Specifications
- (a) CW 3110 – R12 – Sub-Grade, Sub-Base and Base Course Construction.
  - (b) CW 3130 – R2 – Supply and Installation of Geotextile Fabrics.
  - (c) CW 3410 – R8 – Asphaltic Concrete Pavement Works.

### MATERIALS

#### E13.2 Crushed Sub-Base Material

- E13.2.1 Crushed Sub-base material will have a maximum aggregate size of 50 millimetre and be supplied in accordance with Section 2.1 of CW 3110.

#### E13.3 Geotextile Fabric

- E13.3.1 Geotextile fabric will be supplied in accordance with Section 2 of CW 3130.

#### E13.4 Asphalt Material

- E13.4.1 Asphalt material will be Type 1A and will be supplied in accordance with Sections 5 and 6 of CW 3410.

### CONSTRUCTION METHODS

#### E13.5 General

- E13.5.1 Remove existing concrete pavement to a minimum width of 1.5 metres at locations as shown on the Drawings or as directed by the Contract Administrator in accordance with Section 3.1 of Specification CW 3110.
- E13.5.2 Excavate to a depth of 350 millimetres below the top of the existing pavement.
- E13.5.3 Compact existing sub-grade to a minimum of 95% Standard Proctor Density.
- E13.5.4 Place separation/reinforcement geotextile fabric in accordance with Specification CW 3130.
- E13.5.5 Place and compact crushed sub-base material in accordance with CW 3110 to a 300 millimetres compacted depth. Compact to a minimum of 100% Standard Proctor Density.
- E13.5.6 Place and compact asphalt material to a 50 millimetres compacted depth matching the top of the existing concrete pavement. Compact to an average of 95% percent of the 75 Blow Marshall Density of the paving mixture with no individual test being less than 90% percent.

- E13.5.7 Each layer must be levelled and accepted by the Contract Administrator before the succeeding layer may be placed.
- E13.5.8 Additional excavation and placement of sub-base material beyond the identified pavement structure will be completed in accordance with CW 3110 as directed by the Contract Administrator.

#### MEASUREMENT AND PAYMENT

- E13.6 Pavement Patching
- E13.6.1 Pavement patching will be measured on an area basis and paid for at the Contract Unit Price per square metre for "Pavement Patching". The area to be paid for will be the total number of square metres of pavement patched in accordance with this specification, accepted and measured by the Contract Administrator.

### **E14. RECYCLED CONCRETE BASE COURSE MATERIAL**

#### DESCRIPTION

- E14.1 General
- E14.1.1 Further to CW 3110, this specification covers supply and placement of recycled concrete base course material for Full-Depth Partial Slab Patches (Class A, B, C, & D), miscellaneous concrete slabs and sidewalks.
- E14.2 Definitions
- E14.2.1 Deleterious material – are materials such as vegetation, organic material, wood, glass, plastic, metal, reinforcing steel, building rubble, brick, salvaged asphalt materials, clay, shale, and friable particles.
- E14.3 Referenced Standard Construction Specifications
- (a) CW 3110 – R12 – Sub-Grade. Sub-Base and Base Course Construction.
  - (b) CW 3230 – R6 – Full-Depth Patching of Existing Pavement Slabs and Joints.
  - (c) CW 3235 – R7 – Renewal of Existing Miscellaneous Concrete Slabs.
  - (d) CW 3325 – R3 – Portland Cement Concrete Sidewalk.

#### MATERIALS

- E14.4 Recycled Concrete Base Course Material
- E14.4.1 Recycled concrete base course material when used for Full-Depth Partial Slab Patches (Class A, B, C, & D), miscellaneous concrete slabs and sidewalks will be considered equal to granular or limestone base course material specified in Section 2.2 of CW 3110.
- E14.4.2 Recycled concrete base course material will be approved by the Contract Administrator.
- E14.4.3 Recycled concrete base course material will consist of sound durable particles produced by crushing, screening, and grading of recovered concrete materials, free from soft material that would disintegrate through decay or weathering.
- E14.4.4 The recycled concrete base course material will be well graded and conform to the following grading requirements:
- Recycled Concrete Base Course Material Grading Requirements

CANADIAN METRIC SIEVE SIZE	PERCENT OF TOTAL DRY WEIGHT PASSING EACH SIEVE
20 000	100%
5 000	40% - 70%
2 500	25% - 60%
315	8% - 25%
80	6% - 17%

E14.4.5 Recycled concrete base course material when subjected to the abrasion test will have a loss of not more than 35% when tested in accordance with grading B of ASTM C131, Test for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.

E14.4.6 The amount of deleterious material will be limited to a maximum of two percent of the total dry weight.

#### CONSTRUCTION METHODS

E14.5 Placement of Recycled Concrete Base Course Material

E14.5.1 Place and compact recycled concrete base course material as a levelling course to a maximum thickness of 50 millimetres.

E14.5.2 Spread materials uniformly to avoid segregation free of pockets of fine and coarse material.

E14.5.3 Level and compact to the finished elevation. Compact to 100% Standard Proctor Density for Full-Depth Partial Slab Patches (Class A, B, C, & D) and 90% Standard Proctor Density for miscellaneous concrete slabs and sidewalks.

E14.5.4 Maintain the finished material until the pavement or sidewalk is placed.

#### MEASUREMENT AND PAYMENT

E14.6 Recycled Concrete Base Course Material

E14.6.1 The supplying, placing and compaction of recycled concrete base course material will be measured on a volume basis and paid for at the Contract Unit Price per cubic metre for the "Supplying and Placing Base Course Material" as specified in accordance with CW 3110.

E14.6.2 No measurement or payment will be made for material placed as a levelling course under miscellaneous concrete slabs and sidewalks where the costs are included in accordance with CW 3235 and CW 3325.

E14.6.3 No measurement or payment will be made for materials rejected by the Contract Administrator.

### **E15. 100MM CRUSHED SUB-BASE MATERIAL WITH GEOTEXTILE FABRIC AND GEOGRID FOR UNSTABLE SUB-GRADES**

#### DESCRIPTION

E15.1 Further to CW 3110, this specification covers the supply and placement of 100mm crushed sub-base material for unstable sub-grades.

E15.2 Referenced Standard Construction Specifications

- (a) CW 3110 – Sub-grade, Sub-base and Base Course Construction
- (b) CW 3120 – Installation of Subdrains
- (c) CW 3130 – Supply and Installation of Geotextile Fabrics
- (d) CW 3135 – Supply and Installation of Geogrid

## MATERIALS

- E15.3 100mm crushed sub-base material will be supplied in accordance with CW 3110.
- E15.4 Separation geotextile fabric will be non-woven fabric supplied in accordance with CW 3120.
- E15.5 Geogrid will be supplied in accordance with CW 3135.

## CONSTRUCTION METHODS

- E15.6 Prepare the subgrade in accordance with CW 3110.
- E15.7 Place separation geotextile fabric (non-woven) over the accepted subgrade in accordance with CW 3130.
- E15.8 Place geogrid over the separation fabric (non-woven) in accordance with CW 3135.
- E15.9 Place sub-base material by end dumping down the centre of the excavation. The sub-base shall be pushed forward and levelled using a track type dozer where possible, to build a thickened section to support the hauling operations and avoid damage to the subgrade, geotextile fabric or geogrid. This procedure shall continue until all sub-base material has been placed down the centre of the excavation.
- E15.10 Spread the sub-base material to final grades utilizing a track type dozer.
- E15.11 Initial compaction of the sub-base material shall consist of two complete passes utilizing vibratory type equipment capable of compacting the material. Each pass shall be over lapped by half the width of the roller. All additional compaction shall be completed utilizing static type equipment. No trucks, rubber tire loaders or graders will be allowed to travel on the sub-base material until the Contract Administrator has approved the compaction of the sub-base.
- E15.12 The final compacted thickness of the sub-base material shall be a minimum of 300 mm thickness or as shown on the drawings.

## MEASUREMENT AND PAYMENT

- E15.13 Supply and installation of separation geotextile fabric (non-woven) will be measured on an area basis and paid for at the Contract Unit Price per square metre for "Separation Geotextile Fabric". The area to be paid for will be the total number of square metres of separation geotextile fabric, supplied and installed in accordance with this specification, accepted and measured by the Contract Administrator.
- E15.14 Supply and installation of geogrid will be measured and paid in accordance with CW 3135.
- E15.15 Supply, placement and compaction of crushed sub-base material will be measured and paid in accordance with CW 3110.
- E15.16 No measurement or payment will be made for materials rejected by the Contract Administrator.

## **E16. SUPPLY AND INSTALL DETECTABLE WARNING SURFACE TILES**

### DESCRIPTION

- E16.1 This specification covers the supply and installation of detectable warning surface tiles in sidewalk ramps and multi-use path ramps.

### SPECIFICATIONS AND DRAWINGS

- E16.2 Referenced Standard Construction Specifications and Standard Details
  - (a) CW 3235 - Renewal of Existing Miscellaneous Concrete Slabs

- (b) CW 3240 - Renewal of Existing Curbs
- (c) CW 3310 - Portland Cement Concrete Pavement Works
- (d) CW 3325 - Portland Cement Concrete Sidewalk
- (e) SD-229C - Curb Ramp for Concrete Pavement
- (f) SD-229D - Curb Ramp for Asphalt Overlay

E16.3 Attached; SDE Drawings and Installation Manual

- (a) SDE-229A - Curb Ramp Layout for Intersections
- (b) SDE-229AA - Detectable Warning Surface in Curb Ramps for Intersections
- (c) SDE-229AB - Curb Ramp Layout for Offset Intersections
- (d) SDE-229BB - Detectable Warning Surface in Curb Ramps for Medians
- (e) SDE-229E - Curb Ramp Depressed Curb
- (f) Manufacturer's Installation Manual – Armor-Tile Cast in Place Inline Dome Detectable/Tactile Warning Surface Tile.

MATERIALS

E16.4 Acceptable products for:

Sidewalks: 2'x 4' (610 x 1220mm) Armor-Tile Cast in Place (yellow)

Available from:

Engineered Plastics Inc.  
1400 Cornwall Road Unit 6  
Oakville, Ontario L6J 7W5

Attention: Manny Burgio  
Ph: 800-682-2525  
Fax: 800-769-4463

or

Alsip's Building Products  
1 Cole Avenue  
Winnipeg, Manitoba

Attention: Jason Alsip  
Ph. 204-667-3330

- E16.4.1 Detectable warning surface tiles shall be Highway Yellow (USA) or Safety Yellow (Canada).
- E16.4.2 Detectable warning surface tiles shall be cast in place type.
- E16.4.3 Truncated domes on detectable warning surface tiles shall be in accordance with ADA Accessibility Guidelines (ADAAG).

CONSTRUCTION METHODS

E16.5 General


- E16.5.1 Construct curb ramps, sidewalk ramps and multi-use path in accordance with referenced Standard Construction Specifications, Standard Details, and SDE drawings (attached).
- E16.5.2 Construct the lip of the depressed curb in accordance with SDE – 229E.

- E16.5.3 Construct sidewalk ramp grades in accordance with SD-229C and SD-229D.
- E16.5.4 Install the detectable warning surface tile in accordance with the amended Manufacturer's Installation Manual (attached). Drill additional 6mm air vent holes in ribs under the tile as required and use vibration to help seat the tile, to facilitate the installation process.
- E16.5.5 Trim the corner of the tile at radii in accordance with SDE-229A, SDE-229AA and SDE-228AB
- E16.5.6 Install and orient the detectable warning surface tiles as shown on the referenced drawings or as directed by the Contract Administrator.
- E16.6 Medians and Refuge Islands:
- E16.6.1 Where the distance from back of curb to back of curb is 1.32m or greater, install one detectable warning surface tile 50mm from each curb.
- E16.6.2 Where the distance from back of curb to back of curb is less than 1.32m, fill the area between the curbs with detectable warning surface tile(s).
- E16.7 Multi-use Paths
- E16.7.1 Construct a curb ramp with a depressed curb to the full width of the multi-use path in accordance with SDE-229E.
- E16.7.2 Construct a concrete ramp the width of the multi-use path and a minimum of 1.50m deep from back of curb in accordance with SD-229C and SD-229D.
- E16.7.3 Install two (2) tiles in each concrete ramp, one (1) on each side for each direction. Place the short edge of each tile 150mm from the edge of the concrete ramp, with both tiles in line with each other transversely across the concrete ramp. The tile(s) nearest the curb must be 50mm from back of curb similar to tile placement in SDE-229A.
- E16.7.4 Saw cut the middle of the concrete slab, perpendicular to the curb and to a depth of D/4. Cut additional sawcuts as directed by the Contract Administrator.

#### MEASUREMENT AND PAYMENT


- E16.8 Supply and installation of detectable warning surface tiles will be measured on a unit basis and paid for at the Contract Unit Price for "Detectable Warning Surface Tiles". The number of units to be paid for will be the total number of full or trimmed tiles supplied and installed in accordance with this specification, accepted and measured by the Contract Administrator.
- E16.8.1 The area under the detectable warning surface tile is part of the concrete sidewalk ramp and will be paid in accordance with CW 3235 and CW 3325.
- E16.8.2 The concrete sidewalk ramp and the concrete ramp for multi-use paths will be paid as 100mm sidewalk in accordance with CW 3235 or CW 3325.
- E16.8.3 Curb ramp will be paid in accordance with CW 3240 or CW 3310.

DRAWINGS AND INSTALLATION MANUAL



 **THE CITY OF WINNIPEG**  
 PUBLIC WORKS DEPARTMENT

Reference Spec. No.  
 CW 3235, CW 3310, CW 3325  
 E-SUPPLY & INSTALL DETECTABLE WARNING SURFACE



**STANDARD LAYOUT**

(REF. SD-229A)

**ALTERNATE LAYOUT**

(REF. SD-229A)

**NOTE:**


1. DEPRESSED CURB RAMP TO LINE UP WITH BACK OF SIDEWALK.
2. FOR A 1.83m WIDE SIDEWALK USE A DETECTABLE WARNING SURFACE MEASURING 610 X 1520

DIMENSIONS ARE IN MILLIMETRES

<b>THE CITY OF WINNIPEG</b> PUBLIC WORKS DEPARTMENT
Reference Spec. No. CW 3235, CW 3310, CW 3325 E-SUPPLY & INSTALL DETECTABLE WARNING SURFACE
<b>DETECTABLE WARNING SURFACE                  IN CURB RAMPS FOR                  INTERSECTIONS</b>


Designed By: B.P.	Drawn By: T.G.A.	Scale : N.T.S.
Checked By: F.W.C.	Date: 10-02-18	Drawing No.
Approved:		SDE-229AA






**NOTES:**

1. LOCATE GRATINGS, ACCESS COVERS AND OTHER APPURTENANCES OUTSIDE OF CURB RAMPS, DEPRESSED CURBS, CLEAR SPACE LANDINGS AND GUTTERS AS DIRECTED BY THE CONTRACT ADMINISTRATOR.
2. LOCATE END OF DEPRESSED CURB IN LINE WITH PROJECTED BACK OF SIDEWALK.


 <b>THE CITY OF WINNIPEG</b> PUBLIC WORKS DEPARTMENT	Reference Spec. No. CW 3235, CW 3310, CW 3325 E—SUPPLY & INSTALL DETECTABLE WARNING SURFACE		
	DIMENSIONS ARE IN MILLIMETRES		
<b>CURB RAMP LAYOUT          FOR OFFSET INTERSECTIONS</b>	Designed By: B.P.	Drawn By: T.G.A.	Scale : N.T.S.
	Checked By: F.W.C.	Date: 10-02-18	Drawing No.
	Approved:		SDE-229AB




MEDIAN SIDEWALK CROSSING  
 (REF. SD-229B)

NOTE:

1. FOR NARROW MEDIANS AND REFUGE ISLANDS < 1.32m IN WIDTH, PLACE DETECTABLE WARNING SURFACE FULL WIDTH BETWEEN CURBS.
2. DETECTABLE WARNING SURFACE SHALL NOT BE PLACED AT PRIVATE APPROACHES OR ALLEYS.
3. FOR A 1.83m WIDE SIDEWALK, USE A DETECTABLE WARNING SURFACE TILE MEASURING 610 X 1520.


 <b>THE CITY OF WINNIPEG</b> PUBLIC WORKS DEPARTMENT	DIMENSIONS ARE IN MILLIMETRES		
	Reference Spec. No. CW 3235, CW 3310, CW 3325 E-SUPPLY & INSTALL DETECTABLE WARNING SURFACE	Designed By: B.P.	Drawn By: T.G.A.
DETECTABLE WARNING SURFACE IN CURB RAMPS FOR MEDIANS	Checked By: F.W.C.	Date: 10-12-18	Drawing No. SDE-229BB
	Approved:		



DEPRESSED CURB

NOTES:

- 1) SIDEWALK RAMP SURFACE SHALL BE GIVEN A PARALLEL TEXTURED BROOM FINISH.
- 2) INSTALL DETECTABLE WARNING SURFACE SO THAT THE TOP OF THE TRUNCATED DOMES ARE FLUSH WITH THE SURFACE OF THE ADJACENT SIDEWALK.

 <b>THE CITY OF WINNIPEG</b> PUBLIC WORKS DEPARTMENT	DIMENSIONS ARE IN MILLIMETRES		
	Reference Spec. No. CW 3235, CW 3310, CW 3325 E-SUPPLY & INSTALL DETECTABLE WARNING SURFACE	Designed By: B.P.	Drawn By: T.G.A.
<b>CURB RAMP</b> <b>DEPRESSED CURB</b>	Checked By: F.W.C.	Date: 10-02-18	Drawing No. SDE-229E
	Approved:		

## Manufacturer's Installation Manual Armor-Tile Cast In Place

### Inline Dome Detectable/Tactile Warning Surface Tile

- A. During Cast In Place Detectable/Tactile Warning Surface Tile installation procedures, ensure adequate safety guidelines are in place and that they are in accordance with the applicable industry and government standards.
- B. The specifications of the structural embedment flange system and related materials shall be in strict accordance with the contract documents and the guidelines set by their respective manufacturers. Not recommended for asphalt applications.
- C. The physical characteristics of the concrete shall be consistent with the contract specifications while maintaining a slump range of 4 – 7 to permit solid placement of the Cast In Place Detectable/Tactile Warning Surface Tile system. An overly wet mix will cause the tile to float. Under these conditions, suitable weights such as 2 concrete blocks or sandbags (25 lb) shall be placed on each tile.
- D. Prior to placement of the Cast In Place Detectable/Tactile Warning Surface Tile system, the contract drawings shall be reviewed.
- E. The concrete pouring and finishing operations require typical mason's tools, however, a 4' long level with electronic slope readout, 25 lb. weights, and a large non-marring rubber mallet are specific to the installation of the Cast In Place Detectable/Tactile Warning Surface Tile system. A vibrating mechanism such as that manufactured by Vibco can be employed, if desired. The vibrating unit should be fixed to a soft base such as wood, at least 1 foot square.
- F. The factory-installed plastic sheeting must remain in place during the entire installation process to prevent the splashing of concrete onto the finished surface of the tile.
- G. When preparing to set the tile, it is important that NO concrete be removed in the area to accept the tile. It is imperative that the installation technique eliminates any air voids under the tile. Holes in the tile perimeter allow air to escape during the installation process. Concrete will flow through the large holes in each embedment flange on the underside of the tile. This will lock the tile solidly into the cured concrete.
- H. The concrete shall be poured and finished true and smooth to the required dimensions and slope prior to the tile placement. Immediately after finishing concrete, the electronic level should be used to check that the required slope is achieved. The tile shall be placed in accordance with the contract drawings. The Cast In Place Detectable/Tactile Warning Surface Tiles shall be tamped (or vibrated) into the fresh concrete to ensure that the field level of the tile is flush to the adjacent concrete surface. The embedment process should not be accomplished by stepping on the tile as this may cause uneven setting which can result in air voids under the tile surface. The contract drawings indicate that the tile field level (base of truncated dome) is flush to adjacent surfaces to permit proper water drainage and eliminate tripping hazards between adjacent finishes.
- I. In cold weather climates it is recommended that the Cast In Place Detectable/Tactile Warning Surface Tiles be set deeper such that the top of domes are level to the adjacent concrete on the top and sides of ramp and that the base of domes to allow water drainage. This installation will reduce the possibility of damage due to snow clearing operations.
- J. Immediately after placement, the tile elevation is to be checked to adjacent concrete. The elevation and slope should be set consistent with contract drawings to permit water drainage to curb as the design dictates.
- K. While concrete is workable, a 3/8" radius edging tool shall be used to create a finished edge of concrete, then a steel trowel shall be used to finish the concrete around the tile's perimeter, flush to the field level of the tile.
- L. During and after the tile installation and the concrete curing stage, it is imperative that there is no walking, leaning or external force placed on the tile that may rock the tile causing a void between the underside of tile and concrete.
- M. Following tile placement, review installation tolerances to contract drawings and adjust tile before the concrete sets. Two suitable weights of 25 lb each shall be placed on each tile as necessary to ensure solid contact of the underside of tile to concrete.
- N. Following the concrete curing stage, protective plastic wrap is to be removed from the tile surface by cutting the plastic with a sharp knife, tight to the concrete/tile interface. If concrete bled under the plastic, a soft brass wire brush will clean the residue without damage to the tile surface.
- O. If desired, individual tiles can be bolted together using ¼ inch or equivalent hardware. This can help to ensure that adjacent tiles are flush to each other during the installation process. Tape or caulking can be placed on the underside of the bolted butt joint to ensure that concrete does not rise up between the tiles during installation. Any protective plastic wrap which was peeled back to facilitate bolting or cutting, should be replaced and taped to ensure that the tile surface remains free of concrete during the installation process.
- P. Tiles can be cut to custom sizes, or to make a radius, using a continuous rim diamond blade in a circular saw or mini-grinder. Use of a straightedge to guide the cut is advisable where appropriate.
- Q. Any sound-amplifying plates on the underside of the tile, which are dislodged during handling or cutting, should be replaced and secured with construction adhesive. The air gap created between these plates and the bottom of the tile is important in preserving the detectability properties of the Armor-Tile system as required in various jurisdictions.