




FINISH NOTES

- 
 CARPET TILE AS SPECIFIED
 INSTALLED AS PER MANUFACTURE'S INSTRUCTIONS
- 
 RUBBER FLOORING AS SPECIFIED
 INSTALLED AS PER MANUFACTURE'S INSTRUCTIONS
- 
 CERAMIC TILE AS SPECIFIED
 INSTALLED AS PER MANUFACTURE'S INSTRUCTIONS
 4" MATCHING CERAMIC TILE TO BE INSTALLED NEXT TO CERAMIC
 TILE FLOORING ONLY. TOP CAP TO BE
 SCHLUTER AE100

ALL EXISTING FLOORING TO BE REMOVED IN AREAS THAT ARE TO RECEIVE NEW FLOORING. ALL SURFACES TO BE CLEANED AND PREPARED AS PER MANUFACTURES RECOMMENDATIONS FOR NEW FLOORING

THE TRANSITION BETWEEN THE CARPET TILE AND CERAMIC TILE TO HAVE A TRANSITION STRIP AS SPECIFIED

CEILING, BEAMS, BULKHEADS AND COLUMNS (EXCEPT AS NOTED) TO BE PAINTED TYPE 1 FLAT, CEILING TO BE PRICED SEPARATELY
 ALL DOORS TO BE PAINT TYPE 4

ALL EXISTING SIGNS TO BE REMOVED AND WALLS TO BE PATCHED IF REQUIRED
 PATCH AND REPAIR ALL DAMAGED GWB.
 ALL WINDOW TRIM TO BE PAINTED TO MATCH ADJACENT WALL

THE CONTRACTOR TO TAKE DOWN ALL THE BLINDS AND STORE AS PER THE MANAGERS INSTRUCTIONS
 A SMALL AMOUNT OF THE HORIZONTAL BLINDS WILL BE REINSTALLED BASED ON THE MANAGERS INSTRUCTIONS. THE MANAGER MAY INSTRUCT THE CONTRACTOR TO REINSTALL PART OR ALL THE OF THE VERTICAL BLINDS.

MAIN FLOOR PLAN

FLOOR PLAN NOT SITE CHECKED



**THE CITY OF WINNIPEG
 CIVIC BUILDINGS DEPARTMENT**

NO.	DATE	DESCRIPTION	BY

DRAWN BY
 PRINTING DATE

Drawings and specifications, as instruments of service are the property of the designer, the copyright in the same being reserved to them. No reproduction may be made without the permission of the designer, and All prints to be returned.
 The contractor is to verify dimensions and data noted herein with conditions on the site and is held responsible for reporting any discrepancy to the designer for adjustment.



13 Rosewarne. Avenue WINNIPEG, MB Canada R2M 0V8
 204 233 9159 P 204 237 4769 F
 malvine@synergyinteriors.com

DATE NOV. 2009 SCALE REVISIONS
 DRAWN BY M.G. CHECKED BY M.G.

**1168 DAKOTA STREET
 LOUIS RIEL LIBRARY
 FINISH PLAN**