

Appendix C

Contents: Finish Schedule

4 pages attached

ROOM FINISH SCHEDULE		FLOOR				BASE			WALLS				CEILING					REMARKS							
NO.	NAME	RESILIENT SHEET VINYL (NIC)	RUBBER SPORT FLOOR	CONCRETE W/SEALER	EPOXY - TYPE 1 NIC	EPOXY - TYPE 2 (NIC)	PVC TILE SKATE FLOOR (NIC)	RUBBER	PVC TILE SKATE FLOOR (NIC)	RUBBER	EXISTING	GWB	GWB W / PLYWOOD BACKING	PLYWOOD	CONCRETE BLOCK	FINISH CODE	ACOUSTIC CEILING TILE	GWB	OPEN CEILING	AXIOM EDGE	FINISH CODE	HEIGHT			
WINAKWA COMMUNITY CENTRE WINNIPEG MANITOBA																									
PROJECT NUMBER: 09-012 DATE: JUNE 2010 PAGE: SHEET 1 OF 4																									
MAIN FLOOR																									
100	NEW VESTIBULE															1		●					3000	NOTE 1 -INSTALL STEEL FLOOR GRATE AS PER "2006 CITY OF WINNIPEG ACCESSIBILITY DESIGN STANDARDS"	
101	GRAND HALL			●			●			●						1			●				-	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
102	GYMNASIUM		●													1			●				-	FLOORING TO INCORPORATE GYMNASIUM GAME LINES & CLIENT LOGO. SEE SPEC. SECTION 09 62 40.	
103	CORRIDOR			●			●									1			●				-	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
104	VESTIBULE			●			●									1			●				-	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
105	CHANGE ROOM			●			●									1			●				-	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
106	CHANGE ROOM			●			●									1			●				-	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
107	CHANGE ROOM			●			●									1			●				-	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
108	CHANGE ROOM						●									1			●				-	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
109	SPARE																								
110	REFEREE'S ROOM			●			●									1			●				2700	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
111	CORRIDOR						●									1			●				-	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
112	MALE WR						●									2			●				2700	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
113	CORRIDOR						●									1			●				2700	NOTE 4	
114	BAR						●									2			●				2700	NOTE 4	
115	STORAGE						●									1			●				-	NOTE 4	
116	NEW MEETING ROOM						●									1			●				2700	NOTE 4 -NON-PERFORATED HUMIDITY RESISTANT, SOIL-RESISTANT & WASHABLE VINYL ACT	
117	FEMALE WR						●									2			●				2700	NOTE 4 -SKATE FLOOR WILL HAVE FLOATED INSTALLATION ABOVE SEALED CONCRETE (NIC)	
118	FACILITY MANAGER						●									1			●				2700	NOTE 4	
119	CANTEEN						●									2			●				2700	NOTE 4	

ROOM FINISH SCHEDULE		FLOOR										BASE			WALLS				CEILING					REMARKS			
NO.	NAME	RESILIENT SHEET VINYL (NIC)	RUBBER SPORT FLOOR	CONCRETE W/SEALER	EPOXY - TYPE 1 NIC	EPOXY - TYPE 2 (NIC)	PVC TILE SKATE FLOOR (NIC)	RUBBER	PVC TILE SKATE FLOOR (NIC)	EXISTING	SELF COVERED	RUBBER	EXISTING	GWB	GWB W / PLYWOOD BACKING	PLYWOOD	CONCRETE BLOCK	EXISTING	FINISH CODE	ACOUSTIC CEILING TILE	GWB	OPEN CEILING	AXIOM EDGE	FINISH CODE	HEIGHT		
WINAKWA COMMUNITY CENTRE WINNIPEG MANITOBA PROJECT NUMBER: 09-012 DATE: JUNE 2010 PAGE: SHEET 2 OF 4																											
MAIN FLOOR																											
120	RENOV. STORAGE	●									●								2		●					EX	NOTE 4
121	STORAGE										●															EX	EXISTING CLG
122	STORAGE										●															EX	EXISTING CLG
123	STORAGE										●															EX	EXISTING CLG
124	STORAGE										●															EX	EXISTING CLG
125	EXISTING CORRIDOR										●															EX	EXISTING CLG
126	EX. SPORT EQUIP. STORAGE										●															EX	EXISTING CLG
127	EXISTING WR										●															EX	EXISTING CLG
128	EXISTING WR										●															EX	EXISTING CLG
129	EXISTING CORRIDOR										●															EX	EXISTING CLG
130	EXISTING M & E ROOM										●															EX	EXISTING CLG
131	EXISTING KITCHEN										●															EX	EXISTING CLG
131A	EXISTING KITCHEN										●															EX	EXISTING CLG
132	EXISTING CANTEEN										●															EX	EXISTING CLG
133	RENOV. OPEN HALL										●														2700	NOTE 2/ NOTE 4	
134	RENOV. JANITOR ROOM										●														EX	NOTE 4	
135	EXISTING GARAGE										●															EX	EXISTING CLG
136	RENOV. MECH / ELECTRICAL											●														EX	EXISTING CLG
137	RENOV. EXIST. LOBBY											●														EX	NOTE 4 EXISTING CLG
138	EXISTING OFFICE										●															EX	EXISTING CLG

ROOM FINISH SCHEDULE

**WINAKWA
COMMUNITY CENTRE
WINNIPEG MANITOBA**

PROJECT NUMBER: 09-012
DATE: JUNE 2010
PAGE: SHEET 4 OF 4

NO.	NAME	FLOOR										BASE					WALLS					CEILING					REMARKS		
		RESILIENT SHEET VINYL (NIC)	RUBBER SPORT FLOOR	CONCRETE W/SEALER	EPOXY - TYPE 1 NIC	EPOXY - TYPE 2 (NIC)	PVC TILE SKATE FLOOR (NIC)	RUBBER	PVC TILE SKATE FLOOR (NIC)	RUBBER	PVC TILE SKATE FLOOR (NIC)	EXISTING	SELF COVERED	RUBBER	EXISTING	GWB	GWB W / PLYWOOD BACKING	PLYWOOD	CONCRETE BLOCK	EXISTING	FINISH CODE	ACUSTIC CEILING TILE	GWB	OPEN CEILING	AXIOM EDGE	FINISH CODE		HEIGHT	
MEZZANINE FLOOR																													
201	CORRIDOR	●																											NOTE 4
202	MECHANICAL ROOM		●																										NOTE 4
203	AUDIO / VIDEO ROOM	●																					●				2700	NOTE 4	
204	SPARE																												
205	EXISTING OPEN HALL																												EXISTING CLG
206	EXISTING M & E																												EXISTING CLG
207	EXISTING WR																												EXISTING CLG
208	EXISTING WR																												EXISTING CLG
209	EXISTING OPEN SPACE																												EXISTING CLG

FINISH CODES:
1. PAINT
2. EPOXY PAINT

NOTES:
4. PREPARE CONCRETE SLAB &/OR SUB FLOOR AS NECESSARY FOR FUTURE INSTALLATION OF FLOORING.