Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 01 33 00 Submittal Procedures
- .2 Section 01 74 11 Cleaning
- .3 Section 01 78 00 Closeout Submittals
- .4 Section 23 05 05 Installation of Pipework
- .5 Section 23 05 93 Testing, Adjusting and Balancing for HVAC

1.2 REFERENCES

- .1 American National Standards Institute (ANSI)/American Society of Mechanical Engineers International (ASME)
 - .1 ANSI/ASME B16.15, Cast Bronze Threaded Fittings, Classes 125 and 250.
 - .2 ANSI/ASME B16.18, Cast Copper Alloy Solder Joint Pressure Fittings.
 - .3 ANSI/ASME B16.22, Wrought Copper and Copper Alloy Solder Joint Pressure Fittings.
 - .4 ANSI/ASME B16.24, Cast Copper Alloy Pipe Flanges and Flanged Fittings, Class 150, 300, 400, 600, 900, 1500 and 2500.
- .2 ASTM International Inc.
 - .1 ASTM A307, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .2 ASTM A536, Standard Specification for Ductile Iron Castings.
 - .3 ASTM B88M, Standard Specification for Seamless Copper Water Tube (Metric).
- .3 American National Standards Institute/American Water Works Association (ANSI)/(AWWA)
 - .1 ANSI/AWWA C111/A21.11, Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings.
- .4 Canadian Standards Association (CSA International)
 - .1 CSA B242, Groove and Shoulder Type Mechanical Pipe Couplings.
- .5 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Protection Act, 1999, c. 33 (CEPA).
- .6 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .7 Manufacturer's Standardization Society of the Valve and Fittings Industry (MSS).
 - .1 MSS-SP-67, Butterfly Valves.

- .2 MSS-SP-70, Gray Iron Gate Valves, Flanged and Threaded Ends.
- .3 MSS-SP-71, Gray Iron Swing Check Valves, Flanged and Threaded Ends.
- .4 MSS-SP-80, Bronze Gate, Globe, Angle and Check Valves.
- .8 National Research Council (NRC)/Institute for Research in Construction
 - .1 NRCC 38728, National Plumbing Code of Canada (NPC).
- .9 Transport Canada (TC)
 - .1 Transportation of Dangerous Goods Act, 1992, c. 34 (TDGA).

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for insulation and adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Closeout Submittals:
 - .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 Closeout Submittals.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Packaging Waste Management: remove for reuse and return by manufacturer of pallets crates paddling and packaging materials in accordance with Section 01 74 21 Construction/Demolition Waste Management and Disposal.
- .2 Place materials defined as hazardous or toxic in designated containers.
- .3 Handle and dispose of hazardous materials in accordance with Regional and Municipal regulations.
- .4 Materials and Resources Credit MRc2.1 Construction Waste Management: Divert 50% From Landfill and MRc2.2 Construction Waste Management: Divert 75% From Landfill: prepare Construction Waste Management plan in accordance with General Condition.

Part 2 Products

2.1 PIPING

- .1 Domestic hot, cold water systems, within building.
 - .1 Above ground: copper tube, hard drawn, type L: to ASTM B88M.
 - .2 Buried or embedded: copper tube, soft annealed, type K: to ASTM B88M, in long lengths and with no buried joints.

2.2 FITTINGS

.1 Cast copper, solder type: to ANSI/ASME B16.18.

- .2 Wrought copper and copper alloy, solder type: to ANSI/ASME B16.22.
- .3 NPS 2 and larger: ANSI/ASME B16.18 or ANSI/ASME B16.22 roll grooved to CSA B242.
- .4 NPS 1 1/2 and smaller: cast copper to ANSI/ASME B16.18; with 301stainless steel internal components and EPDM seals. Suitable for operating pressure to 1380 kPa.

2.3 JOINTS

- .1 Rubber gaskets, latex-free 1.6 mm thick: to AWWA C111.
- .2 Bolts, nuts, hex head and washers: to ASTM A307, heavy series.
- .3 Solder: 95/5 tin copper alloy.
- .4 Teflon tape: for threaded joints.
- .5 Grooved couplings: designed with angle bolt pads to provide rigid joint, complete with EPDM gasket.
- .6 Dielectric connections between dissimilar metals: dielectric fitting, complete with thermoplastic liner.

2.4 BALL VALVES

- .1 NPS 2 and under, screwed:
 - .1 Class 150.
 - .2 Bronze body, stainless steel ball, PTFE adjustable packing, brass gland and PTFE seat, steel lever handle as specified Section 23 05 23.01 Valves Bronze.
- .2 NPS 2 and under, soldered:
 - .1 To ANSI/ASME B16.18, Class 150.
 - .2 Bronze body, stainless steel ball, PTFE adjustable packing, brass gland and PTFE seat, steel lever handle, with NPT to copper adaptors as specified Section 23 05 23.01 Valves Bronze.

Part 3 Execution

3.1 APPLICATION

.1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 Install in accordance with Plumbing Code and local authority having jurisdiction.
- .2 Install pipe work in accordance with Section 23 05 05 Installation of Pipework, supplemented as specified herein.

- .3 Assemble piping using fittings manufactured to ANSI standards.
- .4 Install CWS piping below and away from HWS and HWC and other hot piping so as to maintain temperature of cold water as low as possible.
- .5 Connect to fixtures and equipment in accordance with manufacturer's written instructions unless otherwise indicated.
- .6 Buried tubing:
 - .1 Lay in well compacted washed sand in accordance with AWWA Class B bedding.
 - .2 Bend tubing without crimping or constriction. Minimize use of fittings.

3.3 VALVES

- .1 Isolate equipment, fixtures and branches with ball valves.
- .2 Balance recirculation system using lockshield globe valves. Mark settings and record on as-built drawings on completion.

3.4 PRESSURE TESTS

.1 Test pressure: greater of 1 times maximum system operating pressure or 860 kPa.

3.5 FLUSHING AND CLEANING

.1 Flush entire system for 8 h. Ensure outlets flushed for 2 hours. Let stand for 24 hours, then draw one sample off longest run. Submit to testing laboratory to verify that system is clean copper to Provincial potable water guidelines. Let system flush for additional 2 hours, then draw off another sample for testing.

3.6 PRE-START-UP INSPECTIONS

- .1 Systems to be complete, prior to flushing, testing and start-up.
- .2 Verify that system can be completely drained.
- .3 Ensure that pressure booster systems are operating properly.
- .4 Ensure that air chambers, expansion compensators are installed properly.

3.7 START-UP

- .1 Timing: start up after:
 - .1 Pressure tests have been completed.
 - .2 Disinfection procedures have been completed.
 - .3 Certificate of static completion has been issued.
 - .4 Water treatment systems operational.
- .2 Provide continuous supervision during start-up.
- .3 Start-up procedures:

- .1 Establish circulation and ensure that air is eliminated.
- .2 Check pressurization to ensure proper operation and to prevent water hammer, flashing and/or cavitation.
- .3 Bring HWS storage tank up to design temperature slowly.
- .4 Monitor piping HWS and HWC piping systems for freedom of movement, pipe expansion as designed.
- .5 Check control, limit, safety devices for normal and safe operation.
- .4 Rectify start-up deficiencies.

3.8 **PERFORMANCE VERIFICATION**

- .1 Scheduling:
 - .1 Verify system performance after pressure and leakage tests and disinfection are completed, and Certificate of Completion has been issued by authority having jurisdiction.
- .2 Procedures:
 - .1 Verify that flow rate and pressure meet Design Criteria.
 - .2 TAB HWC in accordance with Section 23 05 93 Testing, Adjusting and Balancing for HVAC.
 - .3 Adjust pressure regulating valves while withdrawal is maximum and inlet pressure is minimum.
 - .4 Sterilize HWS and HWC systems for Legionella control.
 - .5 Verify performance of temperature controls.
 - .6 Verify compliance with City's Safety & Health Requirements.
 - .7 Check for proper operation of water hammer arrestors. Run one outlet for 10 seconds, then shut of water immediately. If water hammer occurs, replace water hammer arrestor or re-charge air chambers. Repeat for outlets and flush valves.
 - .8 Confirm water quality consistent with supply standards, and ensure no residuals remain as result of flushing or cleaning.
- .3 Reports:
 - .1 Include certificate of water flow and pressure tests conducted on incoming water service, demonstrating adequacy of flow and pressure.

3.9 OPERATION REQUIREMENTS

.1 Co-ordinate operation and maintenance requirements including, cleaning and maintenance of specified materials and products with Section 23 05 05 - Installation of Pipework.

3.10 CLEANING

.1 Clean in accordance with Section 01 74 11 - Cleaning.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 01 33 00 Submittal Procedures
- .2 Section 01 61 00 Common Product Requirements
- .3 Section 01 74 11 Cleaning
- .4 Section 23 05 05 Installation of Pipework

1.2 **REFERENCES**

- .1 ASTM International Inc.
 - .1 ASTM D2235, Standard Specification for Solvent Cement for Acrylonitrile-Butadiene-Styrene (ABS) Plastic Pipe and Fittings.
 - .2 ASTM D2564, Standard Specification for Solvent Cements for Poly(Vinyl-Chloride) (PVC) Plastic Piping Systems.
- .2 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-Series B1800, Thermoplastic Nonpressure Pipe Compendium B1800 Series.
- .3 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-36, Commercial Adhesives.
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .5 South Coast Air Quality Management District (SCAQMD), California State
 - .1 SCAQMD Rule 1168-A2005, Adhesive and Sealant Applications.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for piping and adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Provide two copies WHMIS MSDS Material Safety Data Sheets in accordance with City's Safety & Health Requirements.

1.4 DELIVERY, STORAGE AND HANDLING

.1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.

- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Store at temperatures and conditions recommended by manufacturer.
- .4 Packaging Waste Management: remove for reuse and return by manufacturer of pallets crates paddling and packaging materials in accordance with Section 01 74 21 Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 MATERIAL

.1 Adhesives and Sealants: in accordance with Section 07 92 00 - Joint Sealants.

2.2 PIPING AND FITTINGS

- .1 For buried and above ground DWV piping to:
 - .1 CAN/CSA B1800.

2.3 JOINTS

- .1 Solvent weld for PVC: to ASTM D2564.
- .2 Solvent weld for ABS: to ASTM D2235.

Part 3 Execution

3.1 APPLICATION

.1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 In accordance with Section 23 05 05 Installation of Pipework.
- .2 Install in accordance with National Plumbing Code and local authority having jurisdiction.

3.3 TESTING

- .1 Pressure test buried systems before backfilling.
- .2 Hydraulically test to verify grades and freedom from obstructions.

3.4 **PERFORMANCE VERIFICATION**

.1 Cleanouts:

- .1 Ensure accessible and that access doors are correctly located.
- .2 Open, cover with linseed oil and re-seal.
- .3 Verify cleanout rods can probe as far as the next cleanout, at least.
- .2 Test to ensure traps are fully and permanently primed.
- .3 Storm water drainage:
 - .1 Verify domes are secure.
 - .2 Ensure weirs are correctly sized and installed correctly.
 - .3 Verify provisions for movement of roof system.
- .4 Ensure fixtures are properly anchored, connected to system and effectively vented.
- .5 Affix applicable label (storm, sanitary, vent, pump discharge) c/w directional arrows every floor or 4.5 m (whichever is less).

3.5 CLEANING

- .1 Clean in accordance with Section 01 74 11 Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for reuse and recycling in accordance with General Condition.

END OF SECTION