

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures
- .2 Section 01 45 00 - Quality Control
- .3 Section 01 78 00 - Closeout Submittals
- .4 Section 09 90 00 - Painting
- .5 Section 23 05 93 - Testing, Adjusting and Balancing for HVAC

1.2 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Shop drawings; submit drawings stamped and signed by professional engineer.
- .3 Shop drawings to show:
 - .1 Mounting arrangements
 - .2 Operating and maintenance clearances
- .4 Shop drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts
 - .2 Acoustical sound power data, where applicable
 - .3 Points of operation on performance curves
 - .4 Manufacturer to certify current model production
 - .5 Certification of compliance to applicable codes
- .5 In addition to transmittal letter referred to in Section 01 33 00 - Submittal Procedures: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.
- .6 Closeout Submittals:
 - .1 Provide operation and maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.
 - .2 Operation and maintenance manual approved by, and final copies deposited with, [the Engineer before final inspection.
 - .3 Operation data to include:
 - .1 Control schematics for systems including environmental controls
 - .2 Description of systems and their controls
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances
 - .4 Operation instruction for systems and component
 - .5 Description of actions to be taken in event of equipment failure

- .6 Valves schedule and flow diagram
- .7 Colour coding chart
- .4 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
- .5 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
- .6 Approvals:
 - .1 Submit [1] [one] copies of draft Operation and Maintenance Manual to the Engineer for approval. Submission of individual data will not be accepted unless directed by the Engineer.
 - .2 Make changes as required and re-submit as directed by the Engineer.
- .7 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .8 Site records:
 - .1 The Architect will provide one set of reproducible mechanical drawings. Provide sets of prints as required for each phase of work. Mark changes immediately as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
 - .2 Transfer information daily to master reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .9 **Record Drawings:**
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of record drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "RECORD DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Drawings that do not reflect the installation with reasonable accuracy (at the discretion of the engineer) will be subject to a **hold-back** of \$800 per drawing.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.

.5 Submit completed reproducible record drawings with Operating and Maintenance Manuals.

.10 Submit copies of record drawings for inclusion in final TAB report.

1.3 QUALITY ASSURANCE

.1 Quality Assurance: in accordance with Section 01 45 00 - Quality Control.

.2 Health and Safety Requirements: do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.4 MAINTENANCE

.1 Furnish spare parts in accordance with Section 01 78 00 - Closeout Submittals as follows:

.1 One filter cartridge or set of filter media for each filter or filter bank in addition to final operating set.

.2 Provide one set of special tools required to service equipment as recommended by manufacturers and in accordance with Section 01 78 00 - Closeout Submittals.

.3 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

1.5 DELIVERY, STORAGE, AND HANDLING

.1 Waste Management and Disposal:

.1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

Part 2 Products

2.1 MATERIALS

.1 All materials used on this project shall be new and CSA approved unless noted otherwise.

Part 3 Execution

3.1 PAINTING REPAIRS AND RESTORATION

.1 Do painting in accordance with Section 09 90 00 - Painting.

.2 Prime and touch up marred finished paintwork to match original.

.3 Restore to new condition, finishes which have been damaged.

3.2 CLEANING

.1 Clean interior and exterior of all systems including strainers. Vacuum interior of ductwork and air handling units.

3.3 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 - SUBMITTALS.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.4 DEMONSTRATION

- .1 The contractor will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Trial usage to apply to following equipment and systems:
 - .1 All furnaces
 - .2 All energy recovery ventilators
- .3 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .4 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .5 Instruction duration time requirements as specified in appropriate sections.

3.5 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

Part 1 General

1.1 SUMMARY

.1 Section Includes:

.1 Use of mechanical systems during construction.

.2 Related Sections:

1.2 USE OF SYSTEMS

.1 Use of new and existing permanent heating and ventilating systems for supplying temporary heat or ventilation is not permitted.

Part 2 END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 01 33 00 - Submittal Procedures
- .2 Section 01 61 00 - Common Product Requirements
- .3 Section 01 74 11 - Cleaning
- .4 Section 07 84 00 - Fire Stopping
- .5 Section 07 92 00 - Joint Sealants

1.2 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.181-99, Ready-Mixed Organic Zinc-Rich Coating.
- .2 Canada Green Building Council (CaGBC)
 - .1 LEED Canada-NC Version 1.0-2004, LEED (Leadership in Energy and Environmental Design): Green Building Rating System Reference Package For New Construction and Major Renovations.
 - .2 Rating System Addenda for New Construction and Major Renovations LEED Canada-NC Version 1.0-Addendum 2007.
 - .3 LEED Canada-CI Version 1.0-2007, LEED (Leadership in Energy and Environmental Design): Green Building Rating System Reference Guide For Commercial Interiors.
- .3 Canadian Standards Association (CSA International)
 - .1 CSA B139-04, Installation Code for Oil Burning Equipment.
- .4 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-11-2008, 2nd Edition, Environmental Standard for Paints and Coatings.
- .5 National Fire Code of Canada (NFCC 2005)

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature, specifications and datasheets for piping and equipment and include product characteristics, performance criteria, physical size, finish and limitations.

1.4 QUALITY ASSURANCE

- .1 Sustainability Standards Certification:
 - .1 Low-Emitting Materials: provide listing of sealants coatings used in building, comply with VOC and chemical component limits or restriction requirements.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding and packaging materials in accordance with General Condition.

Part 2 Products

2.1 MATERIAL

- .1 Paint: zinc-rich to CAN/CGSB-1.181.
 - .1 Primers Paints Coating: in accordance with manufacturer's recommendations for surface conditions.
 - .2 Primer: maximum VOC limit 250 g/L to Standard GS-11 to SCAQMD Rule 1113.
 - .3 Paints: maximum VOC limit 150 g/L to Standard GS-11 to SCAQMD Rule 1113.
- .2 Sealants: in accordance with Section 07 92 00 - Joint Sealants.
 - .1 Sealants: maximum VOC limit to SCAQMD Rule 1168 to GSES GS-36.
- .3 Sealants: maximum VOC limit to SCAQMD Rule 1168 to GSES GS-36.
- .4 Adhesives: maximum VOC limit to SCAQMD Rule 1168 to GSES GS-36.
- .5 Fire Stopping: in accordance with Section 07 84 00 - Fire Stopping.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 CONNECTIONS TO EQUIPMENT

- .1 In accordance with manufacturer's instructions unless otherwise indicated.
- .2 Use valves and either unions or flanges for isolation and ease of maintenance and assembly.
- .3 Use double swing joints when equipment mounted on vibration isolation and when piping subject to movement.

3.3 CLEARANCES

- .1 Provide clearance around systems, equipment and components for observation of operation, inspection, servicing, maintenance and as recommended by manufacturer and National Fire Code of Canada.
- .2 Provide space for disassembly, removal of equipment and components without interrupting operation of other system, equipment and components. Confirm with the general contractor coordination with other trades' installations.

3.4 DRAINS

- .1 Install piping with grade in direction of flow except as indicated.
- .2 Install drain valve at low points in piping systems, at equipment and at section isolating valves.
- .3 Pipe each drain valve discharge separately to above floor drain.
 - .1 Discharge to be visible.
- .4 Drain valves: NPS 3/4 gate or globe valves unless indicated otherwise, with hose end male thread, cap and chain.

3.5 DIELECTRIC COUPLINGS

- .1 General: compatible with system, to suit pressure rating of system.
- .2 Locations: where dissimilar metals are joined.
- .3 NPS 2 and under: isolating unions or bronze valves.
- .4 Over NPS 2: isolating flanges.

3.6 PIPEWORK INSTALLATION

- .1 Install pipework to CSA B139
- .2 Screwed fittings jointed with Teflon tape.
- .3 Protect openings against entry of foreign material.

- .4 Install to isolate equipment and allow removal without interrupting operation of other equipment or systems.
- .5 Assemble piping using fittings manufactured to ANSI standards.
- .6 Saddle type branch fittings may be used on mains if branch line is no larger than half size of main.
 - .1 Hole saw (or drill) and ream main to maintain full inside diameter of branch line prior to welding saddle.
- .7 Install exposed piping, equipment, rectangular cleanouts and similar items parallel or perpendicular to building lines.
- .8 Install concealed pipework to minimize furring space, maximize headroom, and conserve space.
- .9 Slope piping, except where indicated, in direction of flow for positive drainage and venting.
- .10 Install, except where indicated, to permit separate thermal insulation of each pipe.
- .11 Group piping wherever possible and as indicated.
- .12 Ream pipes; remove scale and other foreign material before assembly.
- .13 Use eccentric reducers at pipe size changes to ensure positive drainage and venting.
- .14 Provide for thermal expansion as indicated.
- .15 Valves:
 - .1 Install in accessible locations.
 - .2 Remove interior parts before soldering.
 - .3 Install with stems above horizontal position unless indicated.
 - .4 Valves accessible for maintenance without removing adjacent piping.
 - .5 Install globe valves in bypass around control valves.
 - .6 Use bronze ball valve with stainless steel ball at branch take-offs for isolating purposes except where specified.
 - .7 Use chain operators on valves NPS 2 1/2 and larger where installed more than 2400mm above floor in Mechanical Rooms.

3.7 SLEEVES

- .1 General: install where pipes pass through masonry, concrete structures, fire rated assemblies, and as indicated.
- .2 Material: schedule 40 black steel pipe.
- .3 Construction: use annular fins continuously welded at mid-point at foundation walls and where sleeves extend above finished floors.

- .4 Sizes: 6mm minimum clearance between sleeve and uninsulated pipe or between sleeve and insulation.
- .5 Installation:
 - .1 Concrete, masonry walls, concrete floors on grade: terminate flush with finished surface.
 - .2 Other floors: terminate 25 mm above finished floor.
 - .3 Before installation, paint exposed exterior surfaces with heavy application of zinc-rich paint to CAN/CGSB-1.181.
- .6 Sealing:
 - .1 Foundation walls and below grade floors: fire retardant, waterproof non-hardening mastic.
 - .2 Elsewhere:
 - .1 Provide space for firestopping.
 - .2 Maintain fire rating integrity.
 - .3 Sleeves installed for future use: fill with lime plaster or other easily removable filler.
 - .4 Ensure no contact between copper pipe or tube and sleeve.

3.8 ESCUTCHEONS

- .1 Install on pipes passing through walls, partitions, floors, and ceilings in finished areas.
- .2 Construction: one piece type with set screws.
 - .1 Chrome or nickel plated brass or type 302 stainless steel.
- .3 Sizes: outside diameter to cover opening or sleeve.
 - .1 Inside diameter to fit around pipe or outside of insulation if so provided.

3.9 PREPARATION FOR FIRE STOPPING

- .1 Install firestopping within annular space between pipes, ducts, insulation and adjacent fire separation in accordance with Section 07 84 00 - Fire Stopping.
- .2 Insulated pipes and ducts: ensure integrity of insulation and vapour barriers.

3.10 FLUSHING OUT OF PIPING SYSTEMS

- .1 Before start-up, clean interior of piping systems in accordance with requirements of Section 01 74 11 - Cleaning. Preparatory to acceptance, clean and refurbish equipment and leave in operating condition, including replacement of filters in piping systems.

3.11 PRESSURE TESTING OF EQUIPMENT AND PIPEWORK

- .1 Advise the Engineer 72 hours minimum prior to performance of pressure tests.
- .2 Pipework: test as specified in relevant sections of heating, ventilating and air conditioning work.

- .3 Maintain specified test pressure without loss for 4hours minimum unless specified for longer period of time in relevant mechanical sections.
- .4 Prior to tests, isolate equipment and other parts which are not designed to withstand test pressure or media.
- .5 Conduct tests in presence of the Engineer.
- .6 Pay costs for repairs or replacement, retesting, and making good. The Engineer to determine whether repair or replacement is appropriate.
- .7 Insulate or conceal work only after approval and certification of tests by the Engineer.

3.12 EXISTING SYSTEMS

- .1 Connect into existing piping systems at times approved by City of Winnipeg Inspector.
- .2 Request written approval by City of Winnipeg Inspector 10days minimum prior to commencement of work.
- .3 Be responsible for damage to existing plant by this work.

3.13 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for reuse and recycling in accordance with General Condition.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Electrical motors, drives and guards for mechanical equipment and systems.
 - .2 Supplier and installer responsibility indicated in Motor, Control and Equipment Schedule on electrical drawings and related mechanical responsibility is indicated on Mechanical Equipment Schedule on mechanical drawings.
 - .3 Control wiring and conduit is specified in Division 26 except for conduit, wiring and connections below 50 V which are related to control systems specified in Division 22 and 23. Refer to Division 26 for quality of materials and workmanship.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 45 00 - Quality Control
 - .3 Section 01 61 00 - Common Product Requirements
 - .4 Section 01 74 11 - Cleaning
 - .5 Section 01 78 00 - Closeout Submittals

1.2 REFERENCES

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers (ASHRAE)
 - .1 ASHRAE 90.1-01, Energy Standard for Buildings Except Low-Rise Residential Buildings (IESNA cosponsored; ANSI approved; Continuous Maintenance Standard).
- .2 Electrical Equipment Manufacturers' Association Council (EEMAC)
- .3 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Shop Drawings: submit drawings stamped and signed by professional engineer.

- .3 Quality Control: in accordance with Section 01 45 00 - Quality Control.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 The Engineer will make available 1 copy of systems supplier's installation instructions.
- .4 Closeout Submittals
 - .1 Provide maintenance data for motors, drives and guards for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 QUALITY ASSURANCE

- .1 Regulatory Requirements: work to be performed in compliance with CEPA CEEA, TDGA, and applicable Provincial /Territorial regulations.
- .2 Health and Safety Requirements: do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

Part 2 Products

2.1 GENERAL

- .1 Motors: high efficiency, in accordance with local Hydro company standards and to ASHRAE 90.1.

2.2 MOTORS

- .1 Provide motors for mechanical equipment as specified.
- .2 Motors under 3730 W 5 HP: speed as indicated, continuous duty, built-in overload protection, resilient mount, single phase, 120/240 V, unless otherwise specified or indicated.

2.3 TEMPORARY MOTORS

- .1 If delivery of specified motor will delay completion or commissioning work, install motor approved by the Engineer for temporary use. Work will only be accepted when specified motor is installed.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Fasten securely in place.
- .2 Make removable for servicing, easily returned into, and positively in position.

3.3 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in Section 01 45 00 - Quality Control and submit report as described in PART 1 - SUBMITTALS.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

PART 1 **GENERAL**

1.1 SECTION INCLUDES

- .1 Materials and installation for thermometers and pressure gauges in piping systems.

1.2 RELATED SECTIONS

- .1 Section 01 33 00 – Submittal Procedures
- .2 Section 23 05 23.01 – Valves - Bronze
- .3 Section 23 05 53.01 – Mechanical Identification

1.3 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B40.100, Pressure Gauges and Gauge Attachments.
 - .2 ASME B40.200, Thermometers, Direct Reading and Remote Reading.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-14.4, Thermometers, Liquid-in-Glass, Self Indicating, Commercial/Industrial Type.
 - .2 CAN/CGSB-14.5, Thermometers, Bimetallic, Self-Indicating, Commercial/Industrial Type.

1.4 SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 – Submittal Procedures.
- .2 Submit shop drawings and product data.
- .3 Submit manufacturer's product data for following items:
 - .1 Thermometers
 - .2 Pressure Gauges
 - .3 Ball Valves
 - .4 Syphons
 - .5 Wells

1.5 HEALTH AND SAFETY

- .1 Do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.6 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with General Condition.
- .2 Collect, separate and place in designated containers for reuse and recycling, paper, plastic, polystyrene, corrugated cardboard packaging, steel, metal, in accordance with Waste Management Plan.
- .3 Fold up metal banding, flatten and place in designated area for recycling.
- .4 Place materials defined as hazardous or toxic waste in designated containers.
- .5 Ensure emptied containers are sealed, labelled and stored safely for disposal away from children.

PART 2 **PRODUCTS**

2.1 GENERAL

- .1 Design point to be at mid point of scale or range.
- .2 Ranges: dual imperial and metric.

2.2 DIRECT READING THERMOMETERS

- .1 Industrial, variable angle type, liquid filled, accuracy ± 1 scale division, 175 mm scale length: to CAN/CGSB14.4.
 - .1 Acceptable Product: Trerice, Ashcroft, Wika, Winters, Marsh.

2.3 REMOTE READING THERMOMETERS

- .1 100 mm diameter liquid filled or vapor activated dial type: to CAN/CGSB-14.5, accuracy within one scale division, brass movement, stainless steel capillary, stainless steel spiral armour, stainless steel bulb and polished brass or stainless steel case for wall mounting.
 - .1 Acceptable Product: Trerice, Ashcroft, Wika, Winters, Marsh.

2.4 THERMOMETER WELLS

- .1 Copper pipe: copper or bronze.
- .2 Steel pipe: brass or stainless steel.

2.5 PRESSURE GAUGES

- .1 112 mm, dial type: to ASME B40.1, Grade 2A, stainless steel or phosphor bronze bourdon tube having 0.5% accuracy full scale, 1% accuracy for liquid filled.
 - .1 Acceptable Product: Trerice, Ashcroft, Wika, Winters, Marsh.

- .2 Provide:
 - .1 Siphon for steam service.
 - .2 Snubber for pulsating operation.
 - .3 Diaphragm assembly for corrosive service.
 - .4 Gasketed pressure relief back with solid front.
 - .5 Bronze ball valve to Section 23 05 23.01 – Valves – Bronze.
 - .6 Oil filled for high vibration applications.

PART 3 **EXECUTION**

3.1 GENERAL

- .1 Install so they can be easily read from floor or platform. If this cannot be accomplished, install remote reading units.
- .2 Install between equipment and first fitting or valve.

3.2 THERMOMETERS

- .1 Install in wells on piping. Provide heat conductive material inside well.
- .2 Install in locations as indicated and on inlet and outlet of:
 - .1 Heat exchangers.
 - .2 Heating and cooling coils.
 - .3 Boilers.
 - .4 Chillers.
 - .5 Cooling towers.
 - .6 DHW tanks.
- .3 Install wells.
- .4 Use extensions where thermometers are installed through insulation.

3.3 PRESSURE GAUGES

- .1 Install in following locations:
 - .1 Suction and discharge of pumps. (Liquid filled.)
 - .2 Upstream and downstream of PRV's.
 - .3 Upstream and downstream of control valves.
 - .4 Inlet and outlet of coils.
 - .5 Inlet and outlet of heat exchangers.
 - .6 Outlet of boilers.
 - .7 In other locations as indicated.

- .2 Install ball valves.
 - .3 Use extensions where pressure gauges are installed through insulation.
- 3.4 NAMEPLATES
- .1 Install engraved lamicoïd nameplates as specified in Section 23 05 53.01 - Mechanical Identification, identifying medium.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Bronze - valves.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures.
 - .2 Section 01 78 00 - Closeout Submittals.
 - .3 Section 23 05 05 - Installation of Pipework.

1.2 REFERENCES

- .1 American National Standards Institute (ANSI)/ American Society of Mechanical Engineers (ASME).
 - .1 ANSI/ASME B1.20.1-1983 (R2001), Pipe Threads, General Purpose (Inch).
 - .2 ANSI/ASME B16.18-2001, Cast Copper Alloy Solder Joint Pressure Fittings.
- .2 American Society for Testing and Materials International, (ASTM).
 - .1 ASTM A276-04, Specification for Stainless Steel Bars and Shapes.
 - .2 ASTM B62-02, Specification for Composition Bronze or Ounce Metal Castings.
 - .3 ASTM B283-99a, Specification for Copper and Copper Alloy Die Forgings (Hot-Pressed).
 - .4 ASTM B505/B505M-02, Specification for Copper-Base Alloy Continuous Castings.
- .3 Manufacturers Standardization Society of the Valve and Fittings Industry, Inc. (MSS).
 - .1 MSS-SP-25-1998, Standard Marking System for Valves, Fittings, Flanges and Unions.
 - .2 MSS-SP-80-2003, Bronze Gate Globe, Angle and Check Valves.
 - .3 MSS-SP-110-1996, Ball Valves, Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends.

1.3 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data: submit WHMIS MSDS - Material Safety Data Sheets in accordance with Section 02 81 01 - Hazardous Materials.
 - .1 Submit shop drawings and product data in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Submit data for valves specified in this section.
- .3 Closeout Submittals:

- .1 Submit maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 QUALITY ASSURANCE

- .1 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY STORAGE AND DISPOSAL

- .1 Waste Management and Disposal:
 - .2 Separate and recycle waste materials in accordance with General Condition.
 - .3 Collect and separate for disposal paper, plastic, polystyrene and corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.

1.6 MAINTENANCE

- .1 Extra Materials:
 - .2 Furnish following spare parts:
 - .1 Valve seats: one for every 10 valves each size, minimum 1.
 - .2 Discs: one for every 10 valves, each size. Minimum 1.
 - .3 Stem packing: one for every 10 valves, each size. Minimum 1.
 - .4 Valve handles: 2 of each size.

Part 2 Products

2.1 MATERIALS

- .1 Valves:
 - .1 To be single manufacturer.
 - .2 All products to have CRN registration numbers.
- .2 End Connections:
 - .1 Connection into adjacent piping/tubing:
 - .1 Steel pipe systems: Screwed ends to ANSI/ASME B1.20.1.
 - .2 Copper tube systems: Solder ends to ANSI/ASME B16.18.
- .3 Gate Valves:
 - .1 Requirements common to gate valves, unless specified otherwise:
 - .1 Standard specification: MSS SP-80.
 - .2 Bonnet: union with hexagonal shoulders.
 - .3 Connections: screwed with hexagonal shoulders.

- .4 Inspection and pressure testing: to MSS SP-80. Tests to be hydrostatic.
- .5 Packing: non-asbestos.
- .6 Handwheel: non-ferrous.
- .7 Handwheel Nut: bronze to ASTM B62.
- .2 NPS 2 and under, non-rising stem, solid wedge disc, Class 125
 - .1 Body: with long disc guides, screwed bonnet with stem retaining nut.
 - .2 Operator: Handwheel.
- .3 NPS 2 and under, non-rising stem, solid wedge disc, Class 150:
 - .1 Body: with long disc guides, screwed bonnet with stem retaining nut.
 - .2 Operator: Handwheel.
- .4 NPS 2 and under, rising stem, split wedge disc, Class 125:
 - .1 Body: with long disc guides, screwed bonnet.
 - .2 Disc: split wedge, bronze to ASTM B283, loosely secured to stem.
 - .3 Operator: Handwheel.
- .5 NPS 2 and under, rising stem, solid wedge disc, Class 125:
 - .1 Body: with long disc guides, screwed bonnet.
 - .2 Operator: Handwheel.
- .6 NPS 2 and under, rising stem, solid wedge disc, Class 150:
 - .1 Body: with long disc guides, [screwed] [union] bonnet.
 - .2 Operator: Handwheel.
- .4 Check Valves:
 - .1 Requirements common to check valves, unless specified otherwise:
 - .1 Standard specification: MSS SP-80.
 - .2 Connections: screwed with hexagonal shoulders.
 - .2 NPS 2 and under, swing type, bronze disc, Class 125:
 - .1 Body: Y-pattern with integral seat at 45 degrees, screw-in cap with hex head.
 - .2 Disc and seat: renewable rotating disc, two-piece hinge disc construction; seat: regrindable.
 - .3 NPS 2 and under, swing type, bronze disc:
 - .1 Body: Y-pattern with integral seat at 45 degrees, screw-in cap with hex head.
 - .2 Disc and seat: renewable rotating disc, two-piece hinge disc construction; seat: regrindable.
 - .4 NPS 2 and under, swing type, composition disc, Class 200:
 - .1 Body: Y-pattern with integral seat at 45 degrees, screw-in cap with hex head.
 - .2 Disc: renewable rotating disc of number 6 composition to suit service conditions, bronze two-piece hinge disc construction.
 - .5 NPS 2 and under, horizontal lift type, composition disc, Class 150:
 - .1 Body: with integral seat, union bonnet ring with hex shoulders, cap.

- .2 Disc: renewable PTFE no. 6 composition rotating disc in disc holder having guides top and bottom, of bronze to ASTM B62.
- .6 NPS 2 and under, vertical lift type, bronze disc, Class 125:
 - .1 Disc: rotating disc having guides top and bottom, disc guides, retaining rings.
- .5 Ball Valves:
 - .1 NPS 2 and under:
 - .1 Body and cap: cast high tensile bronze to ASTM B62.
 - .2 Pressure rating: Class125.
 - .3 Connections: Screwed ends to ANSI B1.20.1 and with hexagonal shoulders.
 - .4 Stem: tamperproof ball drive.
 - .5 Stem packing nut: external to body.
 - .6 Ball and seat: replaceable stainless steel solid ball and teflon seats.
 - .7 Stem seal: TFE with external packing nut.
 - .8 Operator: removable lever handle, screwdriver slot for all $\frac{3}{4}$ and smaller.

Part 3 Execution

3.1 INSTALLATION

- .1 Install rising stem valves in upright position with stem above horizontal.
- .2 Remove internal parts before soldering.
- .3 Install valves with unions at each piece of equipment arranged to allow servicing, maintenance, and equipment removal.

3.2 VERIFICATION

- .1 Develop schedule of valves and record thereon identifier, location, service, purchase order number and date, manufacturer, identification data specified above.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and requirements for the identification of piping systems, duct work, valves and controllers, including the installation and location of identification systems.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 61 00 - Common Product Requirements
 - .3 Section 01 74 11 - Cleaning
 - .4 Section 09 91 23 - Interior Painting

1.2 REFERENCES

- .1 Canadian Gas Association (CGA)
 - .1 CSA/CGA B149.1-05, Natural Gas and Propane Installation Code.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.60-97, Interior Alkyd Gloss Enamel.
 - .2 CAN/CGSB-24.3-92, Identification of Piping Systems.
- .3 National Fire Protection Association (NFPA)
 - .1 NFPA 13-2002, Standard for the Installation of Sprinkler Systems.
 - .2 NFPA 14-2003, Standard for the Installation of Standpipe and Hose Systems.

1.3 SUBMITTALS

- .1 Product Data:
- .2 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Product data to include paint colour chips, other products specified in this section.

1.4 QUALITY ASSURANCE

- .1 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.
 - .2 Dispose of unused paint and coating material at official hazardous material collections site approved by the Contract Administrator.
 - .3 Do not dispose of unused paint and coating material into sewer system, into streams, lakes, onto ground or in locations where it will pose health or environmental hazard.

Part 2 Products

2.1 MANUFACTURER'S EQUIPMENT NAMEPLATES

- .1 Metal or plastic laminate nameplate mechanically fastened to each piece of equipment by manufacturer.
- .2 Lettering and numbers raised or recessed.
- .3 Information to include, as appropriate:
 - .1 Equipment: manufacturer's name, model, size, serial number, capacity.
 - .2 Motor: voltage, Hz, phase, power factor, duty, frame size.

2.2 SYSTEM NAMEPLATES

- .1 Colours:
 - .1 Hazardous: red letters, white background.
 - .2 Elsewhere: black letters, white background (except where required otherwise by applicable codes).
- .2 Construction:
 - .1 3 mm thick laminated plastic, matte finish, with square corners, letters accurately aligned and machine engraved into core.
- .3 Sizes:
 - .1 Conform to following table:

Size # mm	Sizes (mm)	No. of Lines	Height of Letters (mm)
1	10 x 50	1	3
2	13 x 75	1	5
3	13 x 75	2	3
4	20 x 100	1	8
5	20 x 100	2	5
6	20 x 200	1	8
7	25 x 125	1	12
8	25 x 125	2	8

Size # mm	Sizes (mm)	No. of Lines	Height of Letters (mm)
9	35 x 200	1	20

.2 Use maximum of 25 letters/numbers per line.

.4 Locations:

.1 Terminal cabinets, control panels: use size # 5.

.2 Equipment in Mechanical Rooms: use size # 9.

.5 Identification for PWGSC Preventive Maintenance Support System (PMSS):

.1 Use arrangement of Main identifier, Source identifier, Destination identifier.

.2 Equipment in Mechanical Room:

.1 Main identifier: size #9.

.2 Source and Destination identifiers: size #6.

.3 Terminal cabinets, control panels: size #5.

.3 Equipment elsewhere: sizes as appropriate.

2.3 EXISTING IDENTIFICATION SYSTEMS

.1 Apply existing identification system to new work.

.2 Where existing identification system does not cover for new work, use identification system specified this section.

.3 Before starting work, obtain written approval of identification system from the Contract Administrator.

2.4 PIPING SYSTEMS GOVERNED BY CODES

.1 Identification:

.1 Natural gas: to CSA/CGA B149.1.

.2 Sprinklers: to NFPA 13.

2.5 IDENTIFICATION OF PIPING SYSTEMS

.1 Identify contents by background colour marking, pictogram (as necessary), legend; direction of flow by arrows. To CAN/CGSB 24.3 except where specified otherwise.

.2 Pictograms:

.1 Where required: Workplace Hazardous Materials Information System (WHMIS) regulations.

.3 Legend:

.1 Block capitals to sizes and colours listed in CAN/CGSB 24.3.

.4 Arrows showing direction of flow:

.1 Outside diameter of pipe or insulation less than 75 mm: 100 mm long x 50 mm high.

.2 Outside diameter of pipe or insulation 75 mm and greater: 150 mm long x 50 mm high.

- .3 Use double-headed arrows where flow is reversible.
- .5 Extent of background colour marking:
 - .1 To full circumference of pipe or insulation.
 - .2 Length to accommodate pictogram, full length of legend and arrows.
- .6 Materials for background colour marking, legend, arrows:
 - .1 Pipes and tubing 20 mm and smaller: waterproof and heat-resistant pressure sensitive plastic marker tags.
 - .2 Other pipes: pressure sensitive plastic-coated cloth or vinyl with protective overcoating, waterproof contact adhesive undercoating, suitable for ambient of 100% RH and continuous operating temperature of 150 degrees C and intermittent temperature of 200 degrees C.
- .7 Colours and Legends:
 - .1 Where not listed, obtain direction from the Contract Administrator.
 - .2 Colours for legends, arrows: to following table:

Background colour:	Legend, arrows:
Yellow	BLACK
Green	WHITE
Red	WHITE

- .3 Background colour marking and legends for piping systems:

Contents	Background colour marking	Legend
** Add design temperature		
++ Add design temperature and pressure		

City water	Green	CITY WATER
Treated water	Green	TREATED WATER

Contents	Background colour marking	Legend
** Add design temperature		
++ Add design temperature and pressure		
Domestic hot water supply	Green	DOM. HW SUPPLY
Dom. HWS recirculation	Green	DOM. HW CIRC
Domestic cold water supply	Green	DOM. CWS
Waste water	Green	WASTE WATER
Storm water	Green	STORM
Sanitary	Green	SAN
Plumbing vent	Green	SAN. VENT
Refrigeration suction	Yellow	REF. SUCTION
Refrigeration liquid	Yellow	REF. LIQUID
Refrigeration hot gas	Yellow	REF. HOT GAS
Natural gas	to Codes	
Gas regulator vents	to Codes	
Fire protection water	Red	FIRE PROT. WTR
Sprinklers	Red	SPRINKLERS
Carbon dioxide	Red	CO2
Instrument air	Green	INSTRUMENT AIR

2.6 IDENTIFICATION DUCTWORK SYSTEMS

- .1 50 mm high stencilled letters and directional arrows 150 mm long x 50 mm high.
- .2 Colours: back, or co-ordinated with base colour to ensure strong contrast.

2.7 VALVES, CONTROLLERS

- .1 Brass tags with 12 mm stamped identification data filled with black paint.
- .2 Include flow diagrams for each system, of approved size, showing charts and schedules with identification of each tagged item, valve type, service, function, normal position, location of tagged item.

2.8 CONTROLS COMPONENTS IDENTIFICATION

- .1 Identify all systems, equipment, components, controls, sensors with system nameplates specified in this section.
- .2 Inscriptions to include function and (where appropriate) fail-safe position.

2.9 LANGUAGE

- .1 Identification in English.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 TIMING

- .1 Provide identification only after painting specified Section 09 91 23 - Interior Painting has been completed.

3.3 INSTALLATION

- .1 Perform work in accordance with CAN/CGSB-24.3 except as specified otherwise.
- .2 Provide ULC and/or CSA registration plates as required by respective agency.
- .3 Identify systems, equipment to conform to PWGSC PMSS.

3.4 NAMEPLATES

- .1 Locations:
 - .1 In conspicuous location to facilitate easy reading and identification from operating floor.
- .2 Standoffs:
 - .1 Provide for nameplates on hot and/or insulated surfaces.
- .3 Protection:
 - .1 Do not paint, insulate or cover.

3.5 LOCATION OF IDENTIFICATION ON PIPING AND DUCTWORK SYSTEMS

- .1 On long straight runs in open areas in boiler rooms, equipment rooms, galleries, tunnels: at not more than 17 m intervals and more frequently if required to ensure that at least one is visible from any one viewpoint in operating areas and walking aisles.
- .2 Adjacent to each change in direction.
- .3 At least once in each small room through which piping or ductwork passes.
- .4 On both sides of visual obstruction or where run is difficult to follow.
- .5 On both sides of separations such as walls, floors, partitions.
- .6 Where system is installed in pipe chases, ceiling spaces, galleries, confined spaces, at entry and exit points, and at access openings.
- .7 At beginning and end points of each run and at each piece of equipment in run.
- .8 At point immediately upstream of major manually operated or automatically controlled valves, and dampers. Where this is not possible, place identification as close as possible, preferably on upstream side.
- .9 Identification easily and accurately readable from usual operating areas and from access points.
 - .1 Position of identification approximately at right angles to most convenient line of sight, considering operating positions, lighting conditions, risk of physical damage or injury and reduced visibility over time due to dust and dirt.

3.6 VALVES, CONTROLLERS

- .1 Valves and operating controllers, except at plumbing fixtures, radiation, or where in plain sight of equipment they serve: Secure tags with non-ferrous chains or closed "S" hooks.
- .2 Install one copy of flow diagrams, valve schedules mounted in frame behind non-glare glass where directed by the Contract Administrator. Provide one copy (reduced in size if required) in each operating and maintenance manual.
- .3 Number valves in each system consecutively.

3.7 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.

1.2 QUALIFICATIONS OF TAB PERSONNEL

- .1 Submit names of personnel to perform TAB to the Engineer within 90days of award of contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-2002.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-1998.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
 - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.

1.3 PURPOSE OF TAB

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads.
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.4 EXCEPTIONS

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

1.5 CO-ORDINATION

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.6 PRE-TAB REVIEW

- .1 Review contract documents before project construction is started and confirm in writing to the Engineer adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to the Engineer in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.7 START-UP

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.

1.8 OPERATION OF SYSTEMS DURING TAB

- .1 Operate systems for length of time required for TAB and as required by the Engineer for verification of TAB reports.

1.9 START OF TAB

- .1 Notify the Engineer 7 days prior to start of TAB.
- .2 Start TAB when building is essentially completed, including:

- .1 Installation of ceilings, doors, windows, other construction affecting TAB.
 - .2 Application of weatherstripping, sealing, and caulking.
 - .3 Pressure, leakage, other tests specified elsewhere Division 23.
 - .4 Provisions for TAB installed and operational.
- .3 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
- .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Air systems:
 - .1 Filters in place, clean.
 - .2 Duct systems clean.
 - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
 - .4 Correct fan rotation.
 - .5 Fire, volume control dampers installed and open.
 - .6 Access doors, installed, closed.
 - .7 Outlets installed, volume control dampers open.

1.10 APPLICATION TOLERANCES

- .1 Do TAB to following tolerances of design values:
 - .1 HVAC systems: plus 10%, minus 10%.

1.11 ACCURACY TOLERANCES

- .1 Measured values accurate to within plus or minus 2% of actual values.

1.12 INSTRUMENTS

- .1 Prior to TAB, submit to the Engineer list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to the Engineer.

1.13 SUBMITTALS

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.14 PRELIMINARY TAB REPORT

- .1 Submit for checking and approval of the Engineer, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
 - .1 Details of instruments used.
 - .2 Details of TAB procedures employed.

- .3 Calculations procedures.
- .4 Summaries.

1.15 TAB REPORT

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in Metric units and to include:
 - .1 Project record drawings.
 - .2 System schematics.
- .3 Submit 6 copies of TAB Report to the Engineer for verification and approval, in English in D-ring binders, complete with index tabs.

1.16 VERIFICATION

- .1 Reported results subject to verification by the Engineer.
- .2 Provide personnel and instrumentation to verify up to 30 % of reported results.
- .3 Number and location of verified results as directed by the Engineer.
- .4 Pay costs to repeat TAB as required to satisfaction of the Engineer.

1.17 SETTINGS

- .1 After TAB is completed to satisfaction of the Engineer, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

1.18 COMPLETION OF TAB

- .1 TAB considered complete when final TAB Report received and approved by the Engineer.

1.19 AIR SYSTEMS

- .1 Standard: TAB standards of AABC, NEBB, SMACNA & ASHRAE.
- .2 Do TAB of systems, equipment, components, controls specified Division 23 following systems, equipment, components, controls:
 - .1 Furnace F-1.
 - .2 Furnace F-2.
 - .3 Furnace F-3.
 - .4 Furnace F-4.
 - .5 Furnace F-5.
 - .6 Furnace F-6.
 - .7 Furnace F-7.

- .8 Furnace F-8
- .9 Energy Recovery Ventilator ERV-1
- .10 Energy Recovery Ventilator ERV-2
- .3 Qualifications: personnel performing TAB current member in good standing of AABC or NEBB qualified to standards of AABC or NEBB.
- .4 Quality assurance: perform TAB under direction of supervisor qualified by standards of AABC or NEBB.
- .5 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
- .6 Locations of equipment measurements: to include as appropriate:
 - .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
 - .2 At controllers, controlled device.
- .7 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

1.20 OTHER TAB REQUIREMENTS

- .1 General requirements applicable to work specified this paragraph:
 - .1 Qualifications of TAB personnel: as for air systems specified this section.
 - .2 Quality assurance: as for air systems specified this section.

Part 2 Products

2.1 NOT USED

Part 3 Execution

3.1 NOT USED

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and methods for pressure testing ducts over 5 m in length, forming part of a supply, return or exhaust ductwork system directly or indirectly connected to air handling equipment.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures.
 - .2 Section 01 45 00 - Quality Control.
 - .3 Section 01 78 00 - Closeout Submittals.

1.2 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .2 Sheet Metal and Air Conditioning Contractor's National Association (SMACNA)
 - .1 SMACNA HVAC Air Duct Leakage Test Manual, 1985.

1.3 SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties. Include pressure test information and results as follows:
 - .1 Submit proposed report form and test report format to the Engineer for approval at least three months before proposed date of first series of tests. Do not start tests until approval received in writing from the Engineer.
 - .2 Prepare report of results and submit to the Engineer within 24hours of completion of tests. Include:
 - .1 Schematic of entire system.
 - .2 Schematic of section under test showing test site.
 - .3 Required and achieved static pressures.
 - .4 Orifice differential pressure at test sites.
 - .5 Permissible and actual leakage flow rate (L/s) for test sites.
 - .6 Witnessed certification of results.
 - .3 Include test reports in final TAB report.
 - .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .5 Instructions: submit manufacturer's installation instructions.

- .6 Manufacturer's field reports specified.

1.4 QUALITY ASSURANCE

- .1 Pre-Installation Meetings:
 - .1 Convene pre-installation meeting one week prior to beginning work of this Section and on-site installations in accordance with a Construction Progress Schedules - Bar (GANTT) Chart.
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.
 - .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with City's Safety & Health Requirements.

Part 2 Products

2.1 TEST INSTRUMENTS

- .1 Test apparatus to include:
 - .1 Fan capable of producing required static pressure.
 - .2 Duct section with calibrated orifice plate mounted and accurately located pressure taps.
 - .3 Flow measuring instrument compatible with the orifice plate.
 - .4 Calibration curves for orifice plates used.
 - .5 Flexible duct for connecting to ductwork under test.
 - .6 Smoke bombs for visual inspections.
- .2 Test apparatus: accurate to within +/- 3% of flow rate and pressure.
- .3 Submit details of test instruments to be used to the Engineer at least three months before anticipated start date.
- .4 Test instruments: calibrated and certificate of calibration deposited with the Engineer no more than 28 days before start of tests.
- .5 Re-calibrated every six months thereafter.

2.2 EQUIPMENT LEAKAGE TOLERANCES

- .1 Equipment and system components such as duct heating leakage: 5 %.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 TEST PROCEDURES

- .1 Maximum lengths of ducts to be tested consistent with capacity of test equipment.
- .2 Section of duct to be tested to include:
 - .1 Fittings, branch ducts, tap-ins.
- .3 Repeat tests until specified pressures are attained. Bear costs for repairs and repetition to tests.
- .4 Base partial system leakage calculations on SMACNA HVAC Air Duct Leakage Test Manual.
- .5 Seal leaks that can be heard or felt, regardless of their contribution to total leakage.

3.3 SITE TOLERANCES

- .1 System leakage tolerances specified are stated as percentage of total flow rate handled by system. Pro-rate specified system leakage tolerances. Leakage for sections of duct systems: not to exceed total allowable leakage.
- .2 Leakage tests on following systems not to exceed specified leakage rates.
 - .1 Small duct systems up to 250 Pa: leakage 2%.
 - .2 Large low pressure duct systems up to 500 Pa: leakage 2%.
- .3 Evaluation of test results to use surface area of duct and pressure in duct as basic parameters.

3.4 TESTING

- .1 Test ducts before installation of insulation or other forms of concealment.
- .2 Test after seals have cured.
- .3 Test when ambient temperature will not affect effectiveness of seals, and gaskets.

3.5 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services.
 - .1 Have manufacturer of products, supplied under this Section, review Work involved in the handling, installation/application, protection and cleaning, of its

- product[s] and submit written reports, in acceptable format, to verify compliance of Work with Contract.
- .2 Manufacturer's Field Services: provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, at stages listed:
 - .1 After delivery and storage of products, and when preparatory Work, or other Work, on which the Work of this Section depends, is complete but before installation begins.
 - .2 Twice during progress of Work at 25% and 60% complete.
 - .3 Upon completion of the Work, after cleaning is carried out.
 - .4 Obtain reports, within 3 days of review, and submit, immediately, to the Engineer.
- .2 Performance Verification:
- .1 The Engineer to witness tests and to verify reported results.
 - .2 To be certified by same TAB agency approved by the Engineer to undertake TAB on this project.

3.6 CLEANING

- .1 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 01 33 00 - Submittal Procedures
- .2 Section 01 61 00 - Common Product Requirements
- .3 Section 01 74 11 – Cleaning

1.2 REFERENCES

- .1 Definitions:
 - .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services and equipment in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - means "not concealed" as previously defined.
 - .3 Insulation systems - insulation material, fasteners, jackets, and other accessories.
 - .2 TIAC Codes:
 - .1 CRD: Code Round Ductwork,
 - .2 CRF: Code Rectangular Finish.
- .2 Reference Standards:
 - .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ANSI/ASHRAE/IESNA 90.1-04, SI; Energy Standard for Buildings Except Low-Rise Residential Buildings.
 - .2 ASTM International Inc.
 - .1 ASTM B209M-07, Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric).
 - .2 ASTM C335-05ae1, Standard Test Method for Steady State Heat Transfer Properties of Pipe Insulation.
 - .3 ASTM C411-05, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
 - .4 ASTM C449/C449M-00, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
 - .5 ASTM C547-07e1, Standard Specification for Mineral Fiber Pipe Insulation.
 - .6 ASTM C553-02e1, Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications.
 - .7 ASTM C612-04e1, Standard Specification for Mineral Fiber Block and Board Thermal Insulation.
 - .8 ASTM C795-03, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.

- .9 ASTM C921-03a, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.
- .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma-89, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
- .4 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-36-00, Commercial Adhesives.
- .5 South Coast Air Quality Management District (SCAQMD), California State
 - .1 SCAQMD Rule 1168-A2005, Adhesive and Sealant Applications.
- .6 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (2005).
- .7 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-03, Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
 - .2 CAN/ULC-S701-05, Standard for Thermal Insulation, Polystyrene, Boards and Pipe Covering.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for duct insulation, and include product characteristics, performance criteria, physical size, finish and limitations.
 - .1 Description of equipment giving manufacturer's name, type, model, year and capacity.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list.
- .3 Shop Drawings:
 - .1 Provide drawings stamped and signed by professional engineer registered in Canada.
- .4 Manufacturers' Instructions:
 - .1 Provide manufacturer's written duct insulation jointing recommendations. and special handling criteria, installation sequence, cleaning procedures .

1.4 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Installer: specialist in performing work of this section, and have at least 3 years successful experience in this size and type of project, qualified to standards member of TIAC.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.

- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address and ULC markings.
- .3 Packaging Waste Management: remove for reuse and return by manufacturer of pallets crates padding and packaging materials in accordance with General Condition.

Part 2 Products

2.1 FIRE AND SMOKE RATING

- .1 To CAN/ULC-S102:
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 INSULATION

- .1 Mineral fibre: as specified includes glass fibre, rock wool, slag wool.
 - .1 Recycled content: minimum of 15 % (Post-Consumer + 1/2 Post-Industrial).
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code C-1: Rigid mineral fibre board to ASTM C612, with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this Section).
- .4 TIAC Code C-2: Mineral fibre blanket to ASTM C553 faced with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this section).
 - .1 Mineral fibre: to ASTM C553.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to ASTM C553.

2.3 JACKETS

- .1 Canvas:
 - .1 220 gm/m² cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .2 Lagging adhesive: compatible with insulation.
 - .1 Maximum VOC limit 50 200 250 g/L to SCAQMD Rule 1168 GSES GS-36.

2.4 ACCESSORIES

- .1 Vapour retarder lap adhesive:
 - .1 Water based, fire retardant type, compatible with insulation.
 - .1 Maximum VOC limit 170 g/L to SCAQMD Rule 1168.
- .2 Indoor Vapour Retarder Finish:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.

- .3 Insulating Cement: hydraulic setting on mineral wool, to ASTM C449.
- .4 ULC Listed Canvas Jacket:
 - .1 220 gm/m² cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .5 Outdoor Vapour Retarder Mastic:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.
 - .2 Reinforcing fabric: Fibrous glass, untreated 305 g/m².
- .6 Tape: self-adhesive, aluminum, reinforced, 75 mm wide minimum.
- .7 Contact adhesive: quick-setting
 - .1 Maximum VOC limit 50 g/L [to SCAQMD Rule 1168] [GSES GS-36].
- .8 Canvas adhesive: washable.
 - .1 Maximum VOC limit 50 g/L [to SCAQMD Rule 1168] [GSES GS-36].
- .9 Tie wire: 1.5 mm stainless steel.
- .10 Banding: 12mm wide, 0.5 mm thick stainless steel.
- .11 Facing: 25 mm stainless steel hexagonal wire mesh stitched on one face of insulation.
- .12 Fasteners: [2] mm diameter pins with 35mm diameter clips, length to suit thickness of insulation.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 PRE-INSTALLATION REQUIREMENTS

- .1 Pressure test ductwork systems complete, witness and certify.
- .2 Ensure surfaces are clean, dry, free from foreign material.

3.3 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturer's instructions and as indicated.
- .3 Use 2 layers with staggered joints when required nominal thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.

- .1 Ensure hangers, and supports are outside vapour retarder jacket.
- .5 Apply high compressive strength insulation where insulation may be compressed by weight of ductwork.
- .6 Fasteners: install at 300 mm on centre in horizontal and vertical directions, minimum 2 rows each side.

3.4 DUCTWORK INSULATION SCHEDULE

- .1 Insulation types and thicknesses: conform to following table:

	TIAC Code	Vapour Retarder	Thickness (mm)
Rectangular cold and dual temperature supply air ducts	C-1	yes	50
Round cold and dual temperature supply air ducts	C-2	yes	50
Rectangular warm air ducts	C-1	no	25
Round warm air ducts	C-1	no	25
Supply, return and exhaust ducts exposed in space being served			
Outside air ducts to mixing plenum	C-1	yes	25
Mixing plenums	C-1	yes	25
Exhaust duct between dampers and louvres	C-1	no	25
Rectangular ducts outside	C-1	special	50
Round ducts outside	C-1	special	50
Acoustically lined ducts	See Section 23 33 53- Duct Liners		

- .2 Exposed round ducts 600 mm and larger, smaller sizes where subject to abuse:

- .1 Use TIAC code C-1 insulation, scored to suit diameter of duct.

- .1 Finishes: conform to following table:

	TIAC Code	TIAC Code
	Rectangular	Round
Indoor, concealed	none	none
Indoor, exposed within mechanical room	CRF/1	CRD/2
Indoor, exposed elsewhere	CRF/2	CRD/3
Outdoor, exposed to precipitation	CRF/3	CRD/4
Outdoor, elsewhere	CRF/4	CRD/5

3.5 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.

- .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for reuse and recycling in accordance with General Condition.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and installation procedures for electric heating and cooling controls.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 61 00 - Common Product Requirements
 - .3 Section 01 74 11 - Cleaning

1.2 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 The Contract Administrator will make available 1 copy of systems supplier's installation instructions.

1.4 QUALITY ASSURANCE

- .1 Health and Safety Requirements: do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.

- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

Part 2 Products

2.1 THERMOSTAT (LINE VOLTAGE-HEATING AND COOLING)

- .1 Line voltage, wall-mounted thermostat, for heating or cooling or heating-cooling as indicated with:
 - .1 Full load rating: 6 A at 120 V.
 - .2 Temperature setting range: 5 EC to 30 EC.
 - .3 Thermometer range: 5 EC to 30 EC.
 - .4 Markings in 5 degree increments.
 - .5 Differential temperature fixed at 1.1 EC.

2.2 THERMOSTAT (HEAVY-DUTY, LINE VOLTAGE, HEATING AND COOLING)

- .1 Heavy-duty line voltage thermostat for heating, cooling, heating/cooling with manual changeover two- stage heating or cooling, heating/cooling automatic changeover as indicated with:
 - .1 Full load rating: 16 A at 120 V.
 - .2 Temperature setting range: 5 EC to 30 EC.
 - .3 Thermometer range: 5 EC to 30 EC.
 - .4 Markings in 5 ° degree increments.
 - .5 Differential temperature fixed at 1.1EC.

2.3 THERMOSTAT (LINE VOLTAGE, HEATING)

- .1 Line voltage wall mounted integral electric heating thermostat with:
 - .1 Full load rating: 22 A at 120 V.
 - .2 Temperature setting range: 5 EC to 30 EC.
 - .3 Single pole.
 - .4 Thermometer range: 5 EC to 30 EC.
 - .5 Scale markings: Off-5-10-15-20-25EC.

2.4 THERMOSTAT (LOW VOLTAGE)

- .1 Low voltage wall thermostat:
 - .1 For use on 24 V circuit at 1.5 A capacity.
 - .2 With heat anticipator adjustable 0.1 to 1.2 A.
 - .3 Temperature setting range: 10EC to 25EC.
 - .4 Without sub-base.

2.5 THERMOSTAT (REMOTE BULB)

- .1 Line voltage remote bulb type thermostat with:
 - .1 30 A rating on 120 V.
 - .2 3 m copper capillary tube.
 - .3 Moisture and dust-resistant enclosure.

2.6 THERMOSTAT (FAN COIL)

- .1 Line voltage fan coil heating-cooling thermostat with:
 - .1 Full load rating: 6 A at 120 V.
 - .2 Two rocker switches for "Heat-Off-Cool" and "Low-Medium-High" fan switching. Isolate heating and cooling circuits. "Off" switch to break power to fan and thermostat.

2.7 THERMOSTAT/REMOTE SENSOR GUARDS

- .1 Thermostat guards: lockable, clear opaque plastic cast metal. Slots for air circulation to thermostat.

2.8 SAIL SWITCH

- .1 Sail switch, mercury bulb type with stainless steel sail 79 mm width, adjustable range set for 3.8 m/s air velocity with upward flow. Full load: 16 A at 120 V. Maximum ambient temperature: 82 EC.

2.9 PRESSURE SWITCH

- .1 Pressure switch for air at range to suit application with auto manual reset, contacts open on rise. Maximum allowable gauge pressure of 1.2 MPa. Full load 16 A at 120 V, ULC rated.

2.10 TEMPERATURE SENSORS

- .1 Temperature sensors supplied, installed and wired by Division 25. Component of EMCS System. Electrical Division to provide box and conduit to ceiling space only.

2.11 Electric Heating Relays

- .1 Low voltage solid state electric heating relays installed in ventilated enclosure, recess mounted, complete with power supply. Complete assembly to be CSA approved.
- .2 Heating relays, c/w integral heat sink, over voltage protection and status LED.
- .3 Relay to have veiled conductor connections. No exposed terminals permitted.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install control devices.
- .2 On outside wall, mount thermostats on bracket or insulated pad 25 mm from exterior wall.
- .3 Install remote sensing device and capillary tube in metallic conduit. Conduit enclosing capillary tube must not touch heater or heating cable.

3.3 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and installation for piping, valves and fittings for gas fired equipment.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures.
 - .2 Section 01 45 00 - Quality Control.
 - .3 Section 01 78 00 - Closeout Submittals.
 - .4 Section 23 05 05 - Installation of Pipework.

1.2 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B16.5-03, Pipe Flanges and Flanged Fittings.
 - .2 ASME B16.18-01, Cast Copper Alloy Solder Joint Pressure Fittings.
 - .3 ASME B16.22-01, Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings.
 - .4 ASME B18.2.1-96, Square and Hex Bolts and Screws Inch Series.
- .2 American Society for Testing and Materials International (ASTM)
 - .1 ASTM A47/A47M-99(2004), Standard Specification for Ferritic Malleable Iron Castings.
 - .2 ASTM A53/A53M-04, Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc Coated, Welded and Seamless.
 - .3 ASTM B75M-99, Standard Specification for Seamless Copper Tube Metric.
 - .4 ASTM B837-01, Standard Specification for Seamless Copper Tube for Natural Gas and Liquefied Petroleum (LP) Gas Fuel Distribution Systems.
- .3 Canadian Standards Association (CSA International)
 - .1 CSA W47.1-03, Certification of Companies for Fusion Welding of Steel.
- .4 Canadian Standards Association (CSA)/Canadian Gas Association (CGA)
 - .1 CAN/CSA B149.1HB-00, Natural Gas and Propane Installation Code Handbook.
 - .2 CAN/CSA B149.2-00, Propane Storage and Handling Code.
- .5 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:

- .1 Submit manufacturer's printed product literature, specifications and datasheet for piping, fittings and equipment.
- .2 Indicate on manufacturer's catalogue literature.
- .3 Submit WHMIS MSDS. Indicate VOC's for adhesive and solvents during application and curing.
- .3 Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Instructions: submit manufacturer's installation instructions.
- .6 Closeout Submittals: submit maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 QUALITY ASSURANCE

- .1 Pre-Installation Meeting:
 - .1 Convene pre-installation meeting one week prior to beginning work of this Section and on-site installations in accordance with a Construction Progress Schedules - Bar (GANNT) Chart.
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.
 - .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal:
 - .1 Separate waste materials for reuse and recycling in accordance with General Condition.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan (WMP).
 - .4 Separate for reuse and recycling and place in designated containers Steel, Metal and Plastic waste in accordance with Waste Management Plan (WMP).
 - .5 Divert unused metal materials from landfill to metal recycling facility as approved by the Contract Administrator.

Part 2 Products

2.1 PIPE

- .1 Steel pipe: to ASTM A53/A53M, Schedule 40, seamless as follows:
 - .1 NPS 1/2 to 2, screwed.
 - .2 NPS2 1/2 and over, plain end.
- .2 Copper tube: to ASTM B837.

2.2 JOINTING MATERIAL

- .1 Screwed fittings: pulverized lead paste.
- .2 Welded fittings: to CSA W47.1.
- .3 Flange gaskets: nonmetallic flat.
- .4 Brazing: to ASTM B837.

2.3 FITTINGS

- .1 Steel pipe fittings, screwed, flanged or welded:
 - .1 Malleable iron: screwed, banded, Class 150.
 - .2 Steel pipe flanges and flanged fittings: to ASME B16.5.
 - .3 Welding: butt-welding fittings.
 - .4 Unions: malleable iron, brass to iron, ground seat, to ASTM A47/A47M.
 - .5 Bolts and nuts: to ASME B18.2.1.
 - .6 Nipples: schedule 40, to ASTM A53/A53M.
- .2 Copper pipe fittings, screwed, flanged or soldered:
 - .1 Cast copper fittings: to ASME B16.18.
 - .2 Wrought copper fittings: to ASME B16.22.

2.4 VALVES

- .1 Provincial Code approved, lubricated ball type.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 PIPING

- .1 Install in accordance with Section 23 05 05 - Installation of Pipework, applicable Provincial/Territorial Codes, CAN/CSA B149.1, CAN/CSA B149.2, supplemented as specified.
- .2 Install drip points:
 - .1 At low points in piping system.
 - .2 At connections to equipment.

3.3 VALVES

- .1 Install valves with stems upright or horizontal unless otherwise approved by the Engineer.
- .2 Install valves at branch take-offs to isolate pieces of equipment, and as indicated.

3.4 FIELD QUALITY CONTROL

- .1 Site Tests/Inspection:
 - .1 Test system in accordance with CAN/CSA B149.1 and CAN/CSA B149.2 and requirements of authorities having jurisdiction.
- .2 Manufacturer's Field Services:
 - .1 Have manufacturer of products supplied under this Section review work involved in handling, installation/application, protection and cleaning of its products, and submit written reports, in acceptable format, to verify compliance of work with Contract.
 - .2 Provide manufacturer's field services, consisting of product use recommendations and periodic site visits for inspection of product installation, in accordance with manufacturer's instructions.
 - .3 Schedule site visits to review work at stages listed:
 - .1 After delivery and storage of products, and when preparatory work on which work of this Section depends is complete, but before installation begins.
 - .2 Twice during progress of work at 25% and 60% complete.
 - .3 Upon completion of work, after cleaning is carried out.
- .3 Obtain reports within 3 days of review and submit immediately to the Engineer.
- .4 Performance Verification:
 - .1 Refer to Section 23 08 01 - Performance Verification of Mechanical Piping Systems.
- .5 PV procedures:
 - .1 Test performance of components.

3.5 ADJUSTING

- .1 Purging: purge after pressure test in accordance with CAN/CSA B149.1 and CAN/CSA B149.2.

- .2 Pre-Start-Up Inspections:
 - .1 Check vents from regulators, control valves, terminate outside building in approved location, protected against blockage, damage.
 - .2 Check gas trains, entire installation is approved by authority having jurisdiction.

3.6 CLEANING

- .1 Cleaning: in accordance with Section 23 08 02 - Cleaning and Start-Up of Mechanical Piping Systems, CAN/CSA B149.1, CAN/CSA B149.2, supplemented as specified.
- .2 Perform cleaning operations as specified in Section and in accordance with manufacturer's recommendations.
- .3 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and installation for duct accessories including flexible connections, access doors, vanes and collars.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures.
 - .2 Section 01 45 00 - Quality Control.
 - .3 Section 01 78 00 - Closeout Submittals.

1.2 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .2 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA).
 - .1 SMACNA - HVAC Duct Construction Standards - Metal and Flexible, 95.

1.3 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and data sheet. Indicate the following:
 - .1 Flexible connections.
 - .2 Duct access doors.
 - .3 Turning vanes.
 - .4 Instrument test ports.
 - .2 Submit WHMIS MSDS. Indicate VOC's for adhesive and solvents during application and curing.
- .3 Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties.
 - .1 Certification of ratings: catalogue or published ratings to be those obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Instructions: submit manufacturer's installation instructions.
- .6 Manufacturer's Field Reports: manufacturer's field reports specified.

- .7 Closeout submittals: submit maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 QUALITY ASSURANCE

- .1 Pre-Installation Meetings:
- .1 Convene pre-installation meeting one week prior to beginning work of this Section and on-site installations. Provide a construction progress schedule.
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.
 - .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal:
- .1 Separate waste materials for reuse and recycling in accordance with General Condition.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan (WMP).
 - .4 Separate for reuse and recycling and place in designated containers Steel, Metal and Plastic waste in accordance with Waste Management Plan (WMP).
 - .5 Divert unused metal materials from landfill to metal recycling facility as approved by the Contract Administrator.

Part 2 Products

2.1 GENERAL

- .1 Manufacture in accordance with SMACNA - HVAC Duct Construction Standards.

2.2 FLEXIBLE CONNECTIONS

- .1 Frame: galvanized sheet metal frame 1.5 mm thick with fabric clenched by means of double locked seams.
- .2 Material:
- .1 Fire resistant, self extinguishing, neoprene coated glass fabric, temperature rated at minus 40 degrees C to plus 90 degrees C, density of 1.3kg/m².

2.3 ACCESS DOORS IN DUCTS

- .1 Non-Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame.
- .2 Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame and 25 mm thick rigid glass fibre insulation.
- .3 Gaskets: neoprene or foam rubber.
- .4 Hardware:
 - .1 Up to 300 x 300mm: two sash locks [complete with safety chain.
 - .2 301 to 450mm: four sash locks complete with safety chain.
 - .3 451 to 1000 mm: piano hinge and minimum two sash locks.
 - .4 Doors over 1000 mm: piano hinge and two handles operable from both sides.
 - .5 Hold open devices.
 - .6 300 x 300 mm glass viewing panels.

2.4 TURNING VANES

- .1 Factory or shop fabricated to recommendations of SMACNA and as indicated.

2.5 INSTRUMENT TEST

- .1 1.6 mm thick steel zinc plated after manufacture.
- .2 Cam lock handles with neoprene expansion plug and handle chain.
- .3 28 mm minimum inside diameter. Length to suit insulation thickness.
- .4 Neoprene mounting gasket.

2.6 SPIN-IN COLLARS

- .1 Conical galvanized sheet metal spin-in collars with lockable butterfly damper.
- .2 Sheet metal thickness to co-responding round duct standards.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.2 INSTALLATION

- .1 Flexible Connections:

- .1 Install in following locations:
 - .1 Inlets and outlets to supply air units and fans.
 - .2 Inlets and outlets of exhaust and return air fans.
 - .3 As indicated.
- .2 Length of connection: 100mm.
- .3 Minimum distance between metal parts when system in operation: 75 mm.
- .4 Install in accordance with recommendations of SMACNA.
- .5 When fan is running:
 - .1 Ducting on sides of flexible connection to be in alignment.
 - .2 Ensure slack material in flexible connection.
- .2 Access Doors and Viewing Panels:
 - .1 Size:
 - .1 600 x 600 mm for person size entry.
 - .2 450 x 450 mm for servicing entry.
 - .3 300 x 300 mm for viewing.
 - .4 As indicated.
 - .2 Locations:
 - .1 Fire and smoke dampers.
 - .2 Control dampers.
 - .3 Devices requiring maintenance.
 - .4 Required by code.
 - .5 Reheat coils.
 - .6 Elsewhere as indicated.
- .3 Instrument Test Ports:
 - .1 General:
 - .1 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
 - .2 Locate to permit easy manipulation of instruments.
 - .3 Install insulation port extensions as required.
 - .4 Locations:
 - .1 For traverse readings:
 - .1 Ducted inlets to roof and wall exhausters.
 - .2 Inlets and outlets of other fan systems.
 - .3 Main and sub-main ducts.
 - .4 And as indicated.
 - .2 For temperature readings:
 - .1 At outside air intakes.
 - .2 In mixed air applications in locations as approved by the Engineer.
 - .3 At inlet and outlet of coils.

- .4 Downstream of junctions of two converging air streams of different temperatures.
 - .5 And as indicated.
- .4 Turning vanes:
- .1 Install in accordance with recommendations of SMACNA and as indicated.

3.3 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
- .1 Have manufacturer of products, supplied under this Section, review Work involved in the handling, installation/application, protection and cleaning, of its product[s] and submit written reports, in acceptable format, to verify compliance of Work with Contract.
 - .2 Manufacturer's Field Services: provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, at stages listed:
 - .1 After delivery and storage of products, and when preparatory Work, or other Work, on which the Work of this Section depends, is complete but before installation begins.
 - .2 Twice during progress of Work at 25% and 60% complete.
 - .3 Upon completion of the Work, after cleaning is carried out.
 - .4 Obtain reports, within 3 days of review, and submit, immediately, to the Engineer.

3.4 CLEANING

- .1 Perform cleaning operations as specified in Section 01 74 11 – Cleaning and in accordance with manufacturer's recommendations.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Balancing dampers for mechanical forced air ventilation and air conditioning systems.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 61 00 - Common Product Requirements
 - .3 Section 01 74 11 - Cleaning

1.2 REFERENCES

- .1 Sheet Metal and Air Conditioning National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards, Metal and Flexible-1985.
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 The Contract Administrator will make available 1 copy of systems supplier's installation instructions.

1.4 QUALITY ASSURANCE

- .1 Health and Safety Requirements:
 - .1 Do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

Part 2 Products

2.1 GENERAL

- .1 Manufacture to SMACNA standards.

2.2 SPLITTER DAMPERS

- .1 Fabricate from same material as duct but one sheet metal thickness heavier, with appropriate stiffening.
- .2 Double thickness construction.
- .3 Control rod with locking device and position indicator.
- .4 Rod configuration to prevent end from entering duct.
- .5 Pivot: piano hinge.
- .6 Folded leading edge.

2.3 SINGLE BLADE DAMPERS

- .1 Fabricate from same material as duct, but one sheet metal thickness heavier. V-groove stiffened.
- .2 Size and configuration to recommendations of SMACNA.
- .3 Locking quadrant with shaft extension to accommodate insulation thickness.
- .4 Inside and outside nylon or bronze end bearings.
- .5 Channel frame of same material as adjacent duct, complete with angle stop.

2.4 MULTI-BLADED DAMPERS

- .1 Factory manufactured of material compatible with duct.
- .2 Opposed blade: configuration, metal thickness and construction to recommendations of SMACNA.
- .3 Maximum blade height: 100mm.
- .4 Bearings: pin in bronze bushings or self-lubricating nylon.

- .5 Linkage: shaft extension with locking quadrant.
- .6 Channel frame of same material as adjacent duct, complete with angle stop.
- .7 Maximum leakage: 2% at 500Pa.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install where indicated.
- .2 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
- .3 Locate balancing dampers in each branch duct, for supply, return and exhaust systems.
- .4 Runouts to registers and diffusers: install single blade damper located as close as possible to main ducts.
- .5 Dampers: vibration free.
- .6 Ensure damper operators are observable and accessible.
- .7 Corrections and adjustments conducted by Engineer.

3.3 FIELD QUALITY CONTROL

- .1 Tests:
 - .1 Tests to cover period of not less than 7 days and demonstrate that system is functioning as specified.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Firedampers and fire stop flaps.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 61 00 - Common Product Requirements
 - .3 Section 01 74 11 - Cleaning
 - .4 Section 01 78 00 - Closeout Submittals

1.2 REFERENCES

- .1 American National Standards Institute/National Fire Protection Association (ANSI/NFPA)
 - .1 ANSI/NFPA 90A-2002, Standard for the Installation of Air Conditioning and Ventilating Systems.
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .3 Underwriters Laboratories of Canada (ULC)
 - .1 CAN4-S112-M1990, Fire Test of Fire Damper Assemblies.
 - .2 CAN4-S112.2-M84, Standard Method of Fire Test of Ceiling Firestop Flap Assemblies.
 - .3 ULC-S505-1974, Fusible Links for Fire Protection Service.

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Indicate the following:
 - .1 Fire dampers.
 - .2 Fire stop flaps.
 - .3 Fusible links.
 - .4 Design details of break-away joints.
- .2 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.

- .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .2 Instructions: submit manufacturer's installation instructions.
 - .1 The Project Engineer will make available 1 copy of systems supplier's installation instructions.
- .3 Closeout Submittals:
 - .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 QUALITY ASSURANCE

- .1 Health and Safety Requirements: do construction occupational health and safety in accordance with City's Safety & Health Requirements.
- .2 Certificates:
 - .1 Catalogue or published ratings those obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

1.5 MAINTENANCE

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Provide following:
 - .1 6 fusible links of each type.

1.6 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

Part 2 Products

2.1 FIRE DAMPERS

- .1 Fire dampers: arrangement Type B, blades out of air stream, listed and bear label of ULC, meet requirements of provincial fire authority and ANSI/NFPA 90A. Fire damper assemblies fire tested in accordance with CAN4-S112.
- .2 Mild steel, factory fabricated for fire rating requirement to maintain integrity of fire wall and/or fire separation.

- .1 Fire dampers: 1-1/2 hour fire rated unless otherwise indicated.
- .2 Fire dampers: automatic operating type and have dynamic rating suitable for maximum air velocity and pressure differential to which it will be subjected.
- .3 Top hinged: offset round or square; multi-blade hinged or interlocking type; roll door type; or guillotine type; sized to maintain full duct cross section.
- .4 Fusible link actuated, weighted to close and lock in closed position when released or having negator-spring-closing operator for multi-leaf type or roll door type in horizontal position with vertical air flow.
- .5 40 x 40 x 3 mm retaining angle iron frame, on full perimeter of fire damper, on both sides of fire separation being pierced.
- .6 Equip fire dampers with steel sleeve or frame installed disruption ductwork or impair damper operation.
- .7 Equip sleeves or frames with perimeter mounting angles attached on both sides of wall or floor opening. Construct ductwork in fire-rated floor-ceiling or roof-ceiling assembly systems with air ducts that pierce ceiling to conform with ULC.
- .8 Design and construct dampers to not reduce duct or air transfer opening cross-sectional area.
- .9 Dampers shall be installed so that the centerline of the damper depth or thickness is located in the centerline of the wall, partition or floor slab depth or thickness.
- .10 Unless otherwise indicated, the installation details given in SMACNA Install Fire Damp HVAC and in manufacturer's instructions for fire dampers shall be followed.

2.2 FIRE STOP FLAPS

- .1 Fire smoke flaps: ULC listed and labelled and fire tested in accordance with CAN4-S112.2.
- .2 Construct of minimum 1.5 mm thick sheet steel with 1.6 mm thick non-asbestos ULC listed insulation and corrosion-resistant pins and hinges.
- .3 Flaps held open with fusible link conforming to ULC-S505 and close at 74 degrees C.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install in accordance with ANSI/NFPA 90A and in accordance with conditions of ULC listing.

- .2 Maintain integrity of fire separation.
- .3 After completion and prior to concealment obtain approvals of complete installation from authority having jurisdiction.
- .4 Install access door adjacent to each damper. See Section 23 33 00 - Air Duct Accessories.
- .5 Co-ordinate with installer of firestopping.
- .6 Ensure access doors/panels, fusible links, damper operators are easily observed and accessible.
- .7 Install break-away joints of approved design on each side of fire separation.

3.3 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

.1 Section Includes:

.1 Materials and installation of flexible ductwork, joints and accessories.

.2 Related Sections:

.1 Section 01 33 00 - Submittal Procedures.

1.2 REFERENCES

.1 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).

.2 Department of Justice Canada (Jus).

.1 Canadian Environmental Protection Act (CEPA), 1999, c. 33.

.2 Transportation of Dangerous Goods Act, 1992 (TDGA), c. 34.

.3 Health Canada/Workplace Hazardous Materials Information System (WHMIS).

.1 Material Safety Data Sheets (MSDS).

.4 National Fire Protection Association (NFPA).

.1 NFPA 90A-02, Standard for the Installation of Air-Conditioning and Ventilating Systems.

.2 NFPA 90B-02, Standard for Installation of Warm Air Heating and Air-Conditioning Systems.

.5 Sheet Metal and Air-Conditioning Contractors' National Association (SMACNA).

.1 SMACNA HVAC Duct Construction Standards - Metal and Flexible, 95 (Addendum No.1, November 1997).

.2 SMACNA IAQ Guideline for Occupied Buildings under Construction, 1st Edition 1995.

.6 Underwriters' Laboratories Inc. (UL).

.1 UL 181-96, Standard for Factory-Made Air Ducts and Air Connectors.

.7 Underwriters' Laboratories of Canada (ULC).

.1 CAN/ULC-S110-1986(R2001), Fire Tests for Air Ducts.

1.3 SUBMITTALS

.1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.

.2 Product Data: submit WHMIS MSDS for the following:

.1 Thermal properties.

.2 Friction loss.

- .3 Acoustical loss.
- .4 Leakage.
- .5 Fire rating.
- .3 Samples: submit samples with product data of different types of flexible duct being used in accordance with Section 01 33 00 - Submittal Procedures.

1.4 QUALITY ASSURANCE

- .1 Certification of Ratings:
 - .1 Catalogue or published ratings to be those obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.
- .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Protect on site stored or installed absorptive material from moisture damage.
- .2 Waste Management and Disposal:
 - .1 Separate waste materials for reuse and recycling in accordance with General Condition.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Collect and separate for disposal paper, plastic, polystyrene and corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
 - .4 Place materials defined as hazardous or toxic in designated containers.
 - .5 Handle and dispose of hazardous materials in accordance with CEPA, TDGA, Regional and Municipal regulations.
 - .6 Ensure emptied containers are sealed and stored safely.
 - .7 Fold up metal and plastic banding, flatten and place in designated area for recycling.

1.6 INDOOR AIR QUALITY (IAQ) MANAGEMENT PLAN

- .1 During construction meet or exceed the requirements of SMACNA IAQ Guideline for Occupied Buildings under Construction.

Part 2 Products

2.1 GENERAL

- .1 Factory fabricated to CAN/ULC-S110.

- .2 Pressure drop coefficients listed below are based on relative sheet metal duct pressure drop coefficient of 1.00.
- .3 Flame spread rating not to exceed 25. Smoke developed rating not to exceed 50.

2.2 METALLIC - UNINSULATED

- .1 Type 1: spiral wound flexible aluminum.
- .2 Performance:
 - .1 Factory tested to 1 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.

2.3 METALLIC - INSULATED

- .1 Type 2: spiral wound flexible aluminum with factory applied, 37mm thick flexible glass fibre thermal insulation with vapour barrier and vinyl or reinforced mylar/neoprene laminate jacket.
- .2 Performance:
 - .1 Factory tested to 1 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.
 - .3 Thermal loss/gain: 1.3 W/m². degrees C mean.

2.4 NON-METALLIC - UNINSULATED

- .1 Type 3: non-collapsible, coated mineral base fabric or aluminum foil mylar type, mechanically bonded to, and helically supported by, external steel wire.
- .2 Performance:
 - .1 Factory tested to 1 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.

2.5 NON-METALLIC - INSULATED

- .1 Type 4: non-collapsible, coated mineral base fabric or aluminum foil/mylar type mechanically bonded to, and helically supported by, external steel wire with factory applied, 37 mm thick flexible mineral fibre thermal insulation with vapour barrier and vinyl or reinforced mylar/neoprene laminate jacket.
- .2 Performance:
 - .1 Factory tested to 1 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.
 - .3 Thermal loss/gain: 1.3 W/m². degrees C mean.

2.6 METALLIC ACOUSTIC INSULATED - MEDIUM PRESSURE

- .1 Type 5: Spiral wound, flexible perforated aluminum with factory applied 37 mm thick flexible mineral fibre thermal insulation and sleeved by aluminum foil and mylar laminate vapour barrier.

.2 Performance:

- .1 Factory tested to 2.5 kPa without leakage.
- .2 Maximum relative pressure drop coefficient: 3.
- .3 Acoustical performance: Minimum attenuation (dB/m) to following table:

	Frequency (Hz)				
Duct Diam:	125	250	500	1000	2000
100	0.6	3	12	27	0
150	1.2	3	12	22	27
200	2.0	5	12	19	20
300	2.4	5	12	16	15

2.7 METALLIC - ACOUSTIC INSULATED - HIGH PRESSURE

- .1 Type 6: Spiral wound, flexible perforated aluminum [with factory applied 37 mm thick flexible mineral fibre thermal insulation and encased in spiral wound flexible aluminum jacket, as indicated.

.2 Performance:

- .1 Factory tested to 2.5 kPa without leakage.
- .2 Maximum relative pressure drop coefficient: 3.
- .3 Acoustical performance: minimum attenuation (dB/m) to following table:

	Frequency (Hz)				
Duct Diam:	125	250	500	1000	2000
100	0.6	3	12	27	[0]
150	1.2	3	12	22	[27]
200	2.0	5	12	19	[20]
300	2.4	5	12	16	[15]

2.8 NON-METALLIC - ACOUSTIC INSULATED

- .1 Type 7: non-collapsible, coated mineral base perforated fabric type helically supported by and mechanically bonded to steel wire with factory applied flexible mineral fibre acoustic insulation and encased in aluminum foil and mylar laminate vapour barrier.

.2 Performance:

- .1 Factory tested to 2.5 kPa without leakage.
- .2 Maximum relative pressure drop coefficient: 3.
- .3 Acoustical performance: Minimum attenuation (dB/m) to following table:

	Frequency (Hz)				
Duct Diam:	125	250	500	1000	2000
100	0.6	3	12	27	0
150	1.2	3	12	22	27
200	2.0	5	12	19	20
300	2.4	5	12	16	15

Part 3 Execution

3.1 DUCT INSTALLATION

- .1 Install in accordance with: NFPA 90A and NFPA 90B SMACNA.
- .2 Do trial test to demonstrate workmanship.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Supply, return and exhaust grilles and registers, diffusers and linear grilles, for commercial and residential use.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 61 00 - Common Product Requirements
 - .3 Section 01 74 11 - Cleaning
 - .4 Section 01 78 00 - Closeout Submittals

1.2 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Indicate following:
 - .1 Capacity.
 - .2 Throw and terminal velocity.
 - .3 Noise criteria.
 - .4 Pressure drop.
 - .5 Neck velocity.
- .2 Quality assurance submittals: submit following in accordance with Section [01 33 00 - Submittal Procedures].
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 The Contract Administrator will make available 1 copy of systems supplier's installation instructions.

1.4 QUALITY ASSURANCE

- .1 Health and Safety Requirements: do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

1.6 MAINTENANCE

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Include:
 - .1 Keys for volume control adjustment.
 - .2 Keys for air flow pattern adjustment.

Part 2 Products

2.1 GENERAL

- .1 To meet capacity, pressure drop, terminal velocity, throw, noise level, neck velocity as indicated.
- .2 Frames:
 - .1 Full perimeter gaskets.
 - .2 Plaster frames where set into plaster or gypsum board.
 - .3 Concealed fasteners.
- .3 Concealed manual volume control damper operators.
- .4 Colour: as directed by the Engineer.

2.2 MANUFACTURED UNITS

- .1 Grilles, registers and diffusers of same generic type, products of one manufacturer.

2.3 SUPPLY GRILLES AND REGISTERS

- .1 Refer to drawings.

2.4 RETURN AND EXHAUST GRILLES AND REGISTERS

- .1 Refer to drawings.

2.5 DIFFUSERS

- .1 Refer to drawings.

2.6 LINEAR GRILLES

- .1 Refer to drawings.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install in accordance with manufacturer's instructions.
- .2 Install with flat head stainless steel or cadmium plated screws in countersunk holes where fastenings are visible.
- .3 Provide concealed safety chain on each grille, register and diffuser in gymnasium.

3.3 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Mechanical louvers; intakes; vents; and reinforcement and bracing for air vents, intakes and gooseneck hoods.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 61 00 - Common Product Requirements
 - .3 Section 01 74 11 – Cleaning
 - .4 Section 09 90 00 - Painting

1.2 REFERENCES

- .1 American National Standards Institute (ANSI)/ National Fire Protection Association (NFPA)
 - .1 ANSI/NFPA 96-04, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations.
- .2 American Society for Testing and Materials International (ASTM)
 - .1 ASTM E90-04, Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements.
- .3 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .4 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
- .5 Society of Automotive Engineers (SAE)

1.3 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

1.4 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.

- .2 Indicate following:
 - .1 Pressure drop.
 - .2 Face area.
 - .3 Free area.
 - .4 Dimensions.
- .2 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 The Contract Administrator will make available 1 copy of systems supplier's installation instructions.
- .3 Test Reports:
 - .1 Submit certified data from independent laboratory substantiating acoustic and aerodynamic performance to ASTM E90.

1.5 QUALITY ASSURANCE

- .1 Health and Safety Requirements: do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.6 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

Part 2 Products

2.1 GRAVITY ROOF OUTSIDE AIR INTAKES AND RELIEF VENTS

- .1 Factory manufactured aluminum hinged at curb line.
 - .1 Complete with integral birdscreen of 2.7 mm diameter aluminum wire. Use 12mm mesh on exhaust 19mm mesh on intake.
 - .2 Vertical or Horizontal backdraft dampers on four faces.
 - .3 Maximum throat velocity: 3.3 m/s intake.
 - .4 Maximum loss through unit: 15 Pa exhaust static pressure.
 - .5 Maximum velocity through damper area: 1.5m/s.
 - .6 Shape: as indicated.

2.2 GOOSENECK HOODS

- .1 Thickness: to ASHRAE and SMACNA.
 - .1 Elsewhere: to ASHRAE and SMACNA.
- .2 Fabrication: to ASHRAE and SMACNA.
 - .1 Elsewhere: to ASHRAE and SMACNA.
- .3 Joints: to ASHRAE and SMACNA and or proprietary manufactured duct joint. Proprietary manufactured flanged duct joint considered class A seal.
- .4 Supports: as indicated.
- .5 Complete with integral birdscreen of 2.7 mm diameter copper aluminum wire. Use 12 mm mesh on exhaust 19 mm mesh on intake.
- .6 Vertical backdraft dampers.

2.3 FIXED LOUVRES - ALUMINUM

- .1 Construction: welded with exposed joints ground flush and smooth.
- .2 Material: extruded aluminum alloy 6063-T5.
- .3 Blade: stormproof pattern with centre watershed in blade, reinforcing bosses and maximum blade length of 1500mm.
- .4 Frame, head, sill and jamb: 100mm deep one piece extruded aluminum, minimum 3mm thick with approved caulking slot, integral to unit.
- .5 Mullions: at 1500 mm maximum centres.
- .6 Fastenings: stainless steel SAE-194-8F with SAE-194-SFB nuts and resilient neoprene washers between aluminum and head of bolt, or between nut, ss washer and aluminum body.
- .7 Screen: 12mm exhaust 19mm intake mesh, 2 mm diameter wire aluminum birdscreen on inside face of louvres in formed U-frame.
- .8 Finish: factory applied enamel. Colour: to Contract Administrator's approval.

2.4 FIXED LOUVRES

- .1 General: copper in welded steel frame, complete with anchors.
- .2 Blades:
 - .1 24 ounce cold rolled copper set at 45 degrees, Z-shaped with drip lips.
 - .2 Stormproof design for outside air intakes.
 - .3 Maximum length without mullions of same material: 1250 mm.
- .3 Frame: galvanized structural steel, welded construction. Paint welds after construction to Section 09 90 00 - Painting.

- .4 Screen: 12mm exhaust 19 mm intake mesh, 2 mm diameter wire aluminum birdscreen on inside face of louvres in formed U-frame.
- .5 Finish: factory applied enamel. Colour: to the Contract Administrator's approval.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 In accordance with manufacturer's and SMACNA recommendations.
- .2 Reinforce and brace as indicated.
- .3 Anchor securely into opening. Seal with caulking to ensure weather tightness.

3.3 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Filters for various types of mechanical air handling equipment.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 61 00 - Common Product Requirements
 - .3 Section 01 74 11 – Cleaning
 - .4 Section 01 78 00 - Closeout Submittals

1.2 REFERENCES

- .1 American National Standards Institute/National Fire Prevention Association (ANSI/NFPA)
 - .1 ANSI/NFPA 96-04, Ventilation Control and Fire Protection of Commercial Cooking Operations.
- .2 American Society of Heating, Refrigeration and Air-Conditioning Engineers (ASHRAE)
 - .1 ASHRAE 52.1-1992, Gravimetric And Dust Spot for Testing Air-Cleaning Devices Used in General Ventilation for Removing Particulate Matter (ANSI Approved).
- .3 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-115.10-M90, Disposable Air Filters for the Removal of Particulate Matter from Ventilating Systems.
 - .2 CAN/CGSB-115.18- M85, Filter, Air, Extended Area Panel Type, Medium Efficiency.
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .5 Underwriters' Laboratories of Canada ULC -S111-95, Standard Method of Fire Tests for Air Filter Units.
 - .1 ULC-S649-1993, Exhaust Hoods and Related Controls for Commercial and Institutional Kitchens.

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.

- .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
- .3 Closeout Submittals
 - .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 QUALITY ASSURANCE

- .1 Health and Safety Requirements: do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

1.6 MAINTENANCE

- .1 Extra Materials:
 - .1 Spare filters: in addition to filters installed immediately prior to acceptance by the Engineer, supply 1 complete set of filters for each filter unit or filter bank in accordance with section 01 78 00 - Closeout Submittals.

Part 2 Products

2.1 GENERAL

- .1 Media: suitable for air at 100% RH and air temperatures between minus 40 and 50 degrees C.
- .2 Number of units, size and thickness of panels, overall dimensions of filter bank, configuration and capacities: as indicated.
- .3 Pressure drop when clean and dirty, sizes and thickness: as indicated on schedule.

2.2 ACCESSORIES

- .1 Holding frames: permanent channel section construction of same material as casing/hood, 1.6mm thick, except where specified.
- .2 Seals: to ensure leakproof operation.
- .3 Blank-off plates: as required, to fit all openings and of same material as holding frames.
- .4 Access and servicing: through doors/panels on each side face of filter bank.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION GENERAL

- .1 Install in accordance with manufacturer's recommendations and with adequate space for access, maintenance and replacement.

3.3 REPLACEMENT MEDIA

- .1 Replace media with new upon acceptance.
- .2 Filter media new and clean at time of acceptance.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials, components and installation for heat reclaim devices.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures
 - .2 Section 01 61 00 - Common Product Requirements
 - .3 Section 01 74 11 – Cleaning
 - .4 Section 01 78 00 - Closeout Submittals
 - .5 Section 23 33 00 - Air Duct Accessories
 - .6 Section 26 05 00 - Common Work Results - Electrical

1.2 REFERENCES

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers (ASHRAE)
 - .1 ASHRAE 84-1991, Method of Testing Air-to-Air Heat Exchangers (ANSI approved).
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Shop Drawings:
 - .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Shop drawings: submit drawings stamped and signed by professional engineer registered or licensed in Canada.
- .3 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 The Contract Administrator will make available 1 copy of systems supplier's installation instructions.

- .4 Closeout Submittals:
 - .1 Provide operation and maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

- .5 Certificates:
 - .1 Catalogued or published ratings: obtained from tests carried out by manufacturer or those ordered from independent testing agency signifying adherence to codes and standards in force.
 - .2 Provide confirmation of testing.

1.4 QUALITY ASSURANCE

- .1 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with City's Safety & Health Requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 01 61 00 - Common Product Requirements.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with General Condition.

1.6 MAINTENANCE

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Furnish list of individual manufacturer's recommended spare parts for equipment include:
 - .1 Bearings and seals.
 - .2 Addresses of suppliers.
 - .3 List of specialized tools necessary for adjusting, repairing or replacing.

Part 2 Products

2.1 GENERAL

- .1 Comply with ASHRAE 84.

2.2 ENTHALPY TYPE AIR TO AIR ROTARY HEAT EXCHANGER

- .1 Capacity: as indicated.
- .2 Casing: minimum 18 gauge satin coat steel with baked on powder coat enamel finish.

- .3 Seals: adjustable at periphery of rotor, on duct divider and on purge sections.
- .4 Motor: as indicated.
- .5 Media: non-metallic and bacteriostatic with desiccant and coated with silicate.
- .6 Purge section, maximum cross contamination of particulates: 0.2% of supply air volume and 0.04% of exhaust air volume.
- .7 Performance characteristics: as indicated.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install in accordance with manufacturers recommendations.
- .2 Support independently of adjacent ductwork with flexible connections.
- .3 Install access doors in accordance with Section 23 33 00 - Air Duct Accessories for access to coils, dampers.

3.3 FIELD QUALITY CONTROL

- .1 Tests:
 - .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 23 09 33 - Electric and Electronic Control System for HVAC.
- .3 Section 26 05 00 - Common Work Results - Electrical.

1.2 PRODUCT DATA

- .1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product data to include:
 - .1 Replacement data for motor element, thermostat and switch.
 - .2 Mounting methods.
 - .3 kW rating, voltage, phase.
 - .4 Cabinet material thicknesses.
 - .5 Physical size.
 - .6 Finish.
 - .7 Thermostat, transformer, controls where integral.

1.3 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate and recycle waste materials in accordance with General Condition, and with the Waste Reduction Workplan.
- .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .3 Collect and separate for disposal paper plastic polystyrene corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
- .4 Divert unused metal and wiring materials from landfill to metal recycling facility approved by the Contract Administrator.

Part 2 Products

2.1 FORCED AIR HEATERS

- .1 Forced air heaters, wall or ceiling mounted, as indicated, commercial type as follows:
 - .1 Enclosure:
 - .1 Steel, 1.2 mm thick.
 - .2 Knockouts for 12 mm diameter conduit left, right, bottom and rear.
 - .3 Grill and frame finished.

- .2 Elements and Fan:
 - .1 Mineral insulated.
 - .2 Motor: totally enclosed, shaded pole, impedance protected motor.
- .2 Controls:
 - .1 Wall mounted thermostat: type low voltage, to Section 23 09 33 - Electric and Electronic Control System for HVAC.
 - .3 Built-in tamperproof controls. 'On-Off-Fan Only' selector switch and temperature control knob.

Part 3 Execution

3.1 INSTALLATION

- .1 Install heaters in accordance with manufacturer's instructions.
- .2 Make power and control connections.

3.2 FIELD QUALITY CONTROL

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical.

END OF SECTION