

CUSTOM PACKAGED, OUTDOOR, HEATING AND VENTILATING MAKE-UP AIR UNITS

1. GENERAL

1.1 Scope

.1 The existing make-up air unit located on the roof of the mechanical room shall have the following modifications.

.1 Speed up MUA

1.2 Quality Assurance

.1 Comply with local and Provincial Regulations and have CSA and CGA approval stickers.

.2 All components shall be product of manufacturer regularly engaged in production of such units who issues complete catalogue data on such products.

.3 Test operation of the unit after installation.

2. PRODUCTS

.1 Not used

3. EXECUTION

3.1 Installation

.1 Readjust make-up air unit VFD speed from 2900 L/s to 3020 L/s. Ensure MCV-HX-1 is fully operational injecting heat into HX-1 before increasing speed.

END OF SECTION