



**NOTES :**

LEGEND SHOWN ON SHEET E2.

THESE DRAWINGS SHALL NOT BE SCALED.

ALSO SEE SPECIFICATIONS ON SHEET E4.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL AND ELECTRICAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.

ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.

ALL PRODUCTS AND MATERIALS TO BE USED, INSTALLED AND/OR RELOCATED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.

WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

RELOCATE DATA (CABLING, DATA PORTS, JUNCTION BOXES, ETC.) TO CORRESPOND WITH NEW DATA PORT LOCATIONS SHOWN ON DRAWING. SEE DATA CABLING SPECIFICATIONS.

SUPPLY & INSTALL PHONE PORTS (BLACK RJ-45) & WIRING TO CORRESPOND WITH PHONE PORTS SHOWN ON DRAWING.

ALSO SEE ELECTRICAL AND FIRE ALARM SPECIFICATIONS DRAWING ON SHEET E4.

THE BUILDING FIRE ALARM SYSTEM SHALL REMAIN OPERABLE DURING THE RENOVATION. OBTAIN APPROVAL AND DIRECTION FROM CONTRACT ADMINISTRATOR IF SYSTEM IS BEING INTERRUPTED. TEMPORARY CONNECTION AND RELOCATIONS OF DEVICES SHALL NOT COMPROMISE THE BUILDING FIRE ALARM SYSTEM.

ALL DEVICES SHALL BE UPGRADED TO CONFORM WITH THE LATEST FIRE CODE, IF REQUIRED.

ALL WIRING (HOME RUNS, BETWEEN FLOORS, THROUGH FIRE SEPARATION) SHALL BE IN EMT CONDUIT AND CONCEALED IN ACCESSIBLE CEILING OR WALLS, EXCEPT WHERE DEVICE IS LOCATED ON ACCESSIBLE CEILING. SECUREX CABLE MAY BE USED FROM JUNCTION BOX AT CEILING TO DEVICE, IF WITHIN 5 FEET OF DEVICE. DO NOT SUPPORT CABLE OR CONDUIT TO CEILING SUPPORT SYSTEM.

| DRAWING LIST |   |
|--------------|---|
| SHEET No:    | SHEET TITLE   |
| E1           | PARTIAL MAIN FLOOR PLAN - REFLECTED CEILING: DEMOLITION; ELECTRICAL AND COMMUNICATION |
| E2           | PARTIAL MAIN FLOOR PLAN: RENOVATION; ELECTRICAL AND COMMUNICATION                     |
| E3           | PARTIAL MAIN FLOOR PLAN - REFLECTED CEILING: RENOVATION; ELECTRICAL LIGHTING          |
| E4           | SPECIFICATIONS: ELECTRICAL, FIRE PREVENTION, SECURITY                                 |

| 1     | DESIGN LEAD HAS CHANGED. | DTA | 2010  |
|-------|--------------------------|-----|-------|
|       |                          |     | 03.10 |
| NO.   | REVISION/DESCRIPTION     | BY  | DATE  |
| SEALS |                          |     |       |

**PARTIAL MAIN FLOOR PLAN - REFLECTED CEILING ELECTRICAL & COMMUNICATION DEMOLITION**  
DOORS, FIXTURES & OTHERS SHOWN FOR CLARITY  
SCALE: 1/4"=1'-0"

**ELECTRICAL & COMMUNICATION DEMOLITION NOTES:**  
ALSO SEE NOTES & SPECIFICATIONS.

- ① REMOVE & RELOCATE EXISTING FIRE DOOR OPERATOR & ELECTRICAL COMPONENTS. RELOCATE SECURITY & DOOR BUZZER WIRING TO NEW DOOR ASSEMBLY, SUPPLY & INSTALL WITH NEW SURFACE-MOUNT COMPONENTS. SEE ELECTRICAL & COMMUNICATION DRAWING.
- ② REFER TO ELECTRICAL RENOVATION DRAWING.
- ③ RELOCATE SERVICES TO NEW LOCATIONS AS SHOWN IN ELECTRICAL & COMMUNICATION RENOVATION DRAWING.
- ④ RELOCATE FIRE PULL STATION & FIRE BELL AS SHOWN IN ELECTRICAL & COMMUNICATION DRAWING.
- ⑤ RELOCATE AS SHOWN IN ELECTRICAL & COMMUNICATION RENOVATION DRAWING.
- ⑥ REMOVE EXISTING LIGHTING LUMINARIES & RETURN TO THE CITY OF WINNIPEG. SEE RENOVATION ELECTRICAL LIGHTING DRAWING.
- ⑦ RELOCATE EXISTING ELECTRICAL SERVICES, DATA SERVICES, PHONE SERVICES TO NEW LOCATIONS SHOWN IN ELECTRICAL & COMMUNICATION RENOVATION DRAWING. RELOCATED SERVICES SHALL BE CONNECTED WITH NEW DEVICE BOXES, RECEPTACLES, DATA & PHONE PORTS.
- ⑧ LOCAL BACK DOOR ALARM PANEL AND ARMDISARM BUTTON SHALL BE RELOCATED AS SHOWN IN RENOVATION DRAWING.
- ⑨ REMOVE LIGHT SWITCH & REWIRE CIRCUIT TO CONFORM WITH NEW CIRCUIT, SEE ELECTRICAL LIGHTING DRAWING.

|            |          |          |          |
|------------|----------|----------|----------|
| DRAWN      | CHECKED  | DESIGNED | APPROVED |
| DATE       | USER     | DATE     | DATE     |
| 2010.03.10 | APPROVAL |          |          |

THE CITY OF WINNIPEG  
PLANNING, PROPERTY AND  
DEVELOPMENT DEPARTMENT  
MUNICIPAL ACCOMMODATIONS DIVISION  
3-65 GARRY STREET, R3C 4K4

PROJECT  
FORT ROUGE LIBRARY  
INTERIOR UPGRADING  
NEW CIRCULATION DESK  
625 OSBORNE STREET

SHEET TITLE  
PARTIAL MAIN FLOOR PLAN-REFLECTED CEILING  
DEMOLITION  
ELECTRICAL AND COMMUNICATION

| SCALE    | PROJECT NO. | SHEET NO. |
|----------|-------------|-----------|
| AS SHOWN | 2008-019-01 | E1R1      |