



STRUCTURE ELEVATION – LOOKING SOUTH



SHAFT TO ARM COLLAR

NOTES:

1. THE CONTRACTOR SHALL REMOVE THE EXISTING LEVELLING SHIMS, LOCATED ON THE UNDERSIDE OF THE ARM AND BACK OF THE SHAFT AT THE SHAFT TO ARM COLLAR AND REPLACE WITH NEW ALUMINUM PLATE SHIMS.
2. TO REMOVE AND REPLACE THE EXISTING SHIMS, THE CONTRACTOR SHALL RAISE THE END OF THE ARM, ENSURING THAT THE ARM IS NOT RAISED EXCESSIVELY CAUSING DAMAGE TO THE SHAFT TO ARM COLLAR.
3. THE NEW SHIMS SHALL BE BENT TO FIT BASED ON THE CONTRACTOR'S FIELD MEASUREMENTS.
4. THE DEPTH OF SHIMS INSTALLED SHOULD PROVIDE, UNDER OPERATING CONDITIONS, A 90° ANGLE BETWEEN THE ARM AND THE SHAFT.






UNDERSIDE OF ARM



BACK OF SHAFT

STRUCTURE NO. A804 – PICTURES OF EXISTING LEVELLING SHIMS

B.M. ELEV.	DESIGNED BY: RJT			 THE CITY OF WINNIPEG PUBLIC WORKS DEPARTMENT		
	DRAWN BY: JGW			ALUMINUM OVERHEAD SIGN SUPPORT STRUCTURES – 2010 MAINTENANCE WORKS		CITY DRAWING NUMBER OHSS-10-09
	CHECKED BY: SSR					SHEET 9 OF 9
	APPROVED BY:					
	SCALE: HORZ. NTS VERT.			DATE: JULY 2010		
	AUTHORIZED BY:	DATE:	CONSULTANT PROJECT NO. 10-3545-1000	A804 STAFFORD STREET, S/B, WEST OF PEMBINA HIGHWAY – MISCELLANEOUS ALUMINUM WORKS		
NO. REVISIONS	DATE	BY				