

## REBUILD PEDESTRIAN ESCALATORS AT 365 MAIN STREET – PORTAGE & MAIN CONCOURSE

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: July 20, 2010  
BY: Coleen Groening  
TELEPHONE NO. (204) 986-2491

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20070419

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph ^ of Form A: Bid may render your Bid non-responsive.**

---

### **PART E – SPECIFICATIONS**

Revise: E1.2.4 to read:

E1.2.4 The following are applicable to the Work:

E1.2.5 Specification to rebuild a pair of Montgomery pedestrian escalators located at the Scotia Bank entrance of the Portage and Main Concourse, 365 Main Street.

E1.2.6 Supply all labour, materials, applicable permits and Manitoba Dept. of Labour inspections to remove and replace existing escalator components listed herein.

E1.2.7 Rebuild to be CSA – 2007 and B44 Code compliant.

E1.2.8 All replacement components to be compatible to Original Equipment Manufacturers Specifications.

- Remove and replace with all new escalator step boxes, complete with new spindles and rollers.
- Install new aluminum walk on plates complete with comb impact switches.
- Install "Zero speed" handrail **sensors**.
- **Supply and install 4 new handrails and handrail guides (incline, curve and roller sections).**
- Overhaul existing gearbox complete with new seals and bearings.
- Remove existing electric drive motors, clean & service as required, reinstall same.
- Install "Ecostart Controller" upgrade system.
- Resurface skirt sides with an application of black silicone resurfacer.
- Service and replace as necessary all skirt impact switches, adjust skirt/step clearance to meet B44 Code.
- Clean up debris and oil residue at the underside of both escalators.

E1.2.9 Work may proceed during normal business hours.

E1.2.10 Suitable barriers to be placed to protect all persons.