



PLUMBING SCHEDULE		
TAG	TYPE	DESCRIPTION
P1	↔	ZURN # Z1341-BFP. WALL FAUCET WITH BACK FLOW PREVENTER, GARDENA. SPIRAL WATERING HOSE KIT WITH QUICK-CLICK CONNECTIONS, ADJUSTABLE SPRAY WATER PISTOL & WALL BRACKET, MODEL #4646. MOUNTING HEIGHT OF NEW WALL BRACKET TO BE DETERMINED ON SITE.
P2	WF	WATER FILTER SYSTEM, MODEL # CBF1 WITH (4) CB1 REPLACEMENT CARBON BLOCK FILTER CARTRIDGES.
P3		WATTS. DUO-CLOSURE RECESSED WASHING MACHINE WALL BOX, MODEL 2M2 DWB, TOP INSTALLATION. TRIM PLATE COVER WHITE.
P4		AMERICAN STANDARD. ROXALYN # 0195 073 WALL HUNG LAVATORY, VITREOUS CHINA WITH 4" CENTERS FITTED WITH DELTA MIXING/SENSING ELECTRONIC FAUCET, DELTA MODEL 596-LGHGMHDF. CW TRANSFORMER, SOLENOID VALVE AND CONTROL BOX. CAST WHEELCHAIR LAVATORY WASTE, DELTA 33T290 CAST "P" TRAP, DELTA 33T311, CHROME ANGLE LAVATORY SUPPLIES, DELTA 47T2512SD. MOUNT TRANSFORMER IN-WALL CAVITY WITH ACCESS PANEL.
P5		HAWS MODEL # 8325 (FLOOR FLANGE MOUNT), COMBINATION EMERGENCY SHOWER & EYE/FACE WASH CW VALVING, IN-LINE STRAINER, SIGNAGE, TEMPERED WATER BLENDING SYSTEM MODEL TWBS.SH. INSTALL TO MANUFACTURERS RECOMMENDATIONS.
P6		ZURN SHOKTROL Z-1250A WATER HAMMER ARRESTOR.
P7		DROP-IN SINK WITH STRAINER, 18" X 36", ENCASTER PRODUCT CODE ACX 610 'ACQUARIO'. SWIVEL SPOUT 140° FAUCET WITH PULL-OUT SPRAY, SOLID STAINLESS STEEL/MATTE BLACK, KWC SUPRIMO MODEL # K.10.C1.33.736.
P8		INSTALL ON SITE (DFO) WATER RESERVOIR AS PER MANUFACTURERS INSTALLATION INSTRUCTIONS. CONTRACTOR TO PROVIDE ALL SUPPLY, DRAIN LINES & CONNECTIONS TO MAKE FULLY FUNCTIONAL.
P9		STEEL ACCESS HATCH, 8' X8". FINISH TO MATCH WALL.

NOTES :
ALSO SEE M1 NOTES

PLUMBING DEMOLITION NOTES:

- 1 REMOVE & DISCARD ABOVE CEILING VENT LINE TAKE OFF FROM MAIN VENT LINE TO EXISTING LAVATORY. CONTRACTOR TO VERIFY EXISTING MAIN VENT LINE SIZE COMPLIES WITH CURRENT PLUMBING CODES AND NUMBER OF NEW PLUMBING FIXTURES INSTALLED AS PER PARTIAL BASEMENT FLOOR PLAN PLUMBING RENOVATION DWG & PLUMBING SCHEDULE. REMOVE, DISCARD & REPLACE VENT LINE AS REQUIRED BY CURRENT PLUMBING CODES.
- 2 REMOVE & DISCARD ABOVE CEILING POLY SHEET DRIP BAGS & DEBRIS FROM ENTIRE MAJOR CRIME ROOM CEILING CAVITY. REMOVE & DISCARD EXISTING PIPE INSULATION & RE-INSULATE AS PER M1 NOTES.
- 3 REMOVE, DISCARD & CAP-OFF HOT & COLD WATER SUPPLY LINE TAKE-OFFS TO LAVATORY. EXISTING HOT & COLD SUPPLY LINES FROM MAJOR CRIME ROOM TO REMAIN. REMOVE & DISCARD (2) COLD WATER IN-LINE FILTER HOUSING UNITS & SUPPLY TUBES. MODIFY EXISTING MAJOR CRIME ROOM COLD WATER SUPPLY LINE TO ACCOMMODATE NEW WATER FILTER HOUSING UNIT LOCATION.
- 4 REMOVE & DISCARD LAVATORY, P-TRAP & DRAIN LINE TO STACK.
- 5 AREA OF CONCRETE SLAB REPLACEMENT. SAW CUT CONCRETE SLAB. REMOVE & DISCARD DEMOLISHED CONCRETE & EXCAVATE SOIL TO ACCOMMODATE NEW LAVATORY DRAIN LINE BELOW EXISTING BASEMENT CONCRETE FLOOR SLAB. SAW CUT WIDTH SHALL BE 18" MINIMUM. DEPTH & LOCATION OF EXISTING MAIN DRAIN LINE TO BE CONFIRMED BY CONTRACTOR.
- 6 REMOVE & DISCARD STEEL FRAME AROUND CONCRETE BLOCK OPENING & DEMOLISH OPENING TO ACCOMMODATE NEW SURFACE MOUNTED DRAIN LINE FOR (DFO) & LAVATORY SINK. PATH & PAINT WALL.
- 7 DEMOLISH SECTION OF CONCRETE BLOCK WALL TO ACCOMMODATE NEW DWV CLEAN-OUT & METAL ACCESS HATCH.
- 8 ROUTE 4" WIDE X 1'-6" MINIMUM LONG DRAIN CHANNEL INTO EXISTING BASEMENT CONCRETE FLOOR. SLOPE FROM EMERGENCY SHOWER DRAIN LINE TO EXISTING FLOOR DRAIN. DEPTH OF DRAIN CHANNEL TO BE 2" MINIMUM.
- 9 PUMP WATER, CLEAN CATCH BASIN & IN-FLOOR CONDENSATE DRAIN TRAY. FINISH STEEL CATCH BASIN COVER AND METAL FRAME AS PER ARCHITECTURAL DWG.
- 10 REMOVE, DISCARD ALL IN-WALL & CEILING REDUNDANT HOT & COLD SUPPLY LINES IN RENOVATION WORK AREA. PATCH WALLS / CEILINGS AS REQUIRED. RE-INSULATE ALL EXPOSED SUPPLY PLUMBING LINES.
- 11 REMOVE & DISCARD EXISTING PVC AND GALVANIZED TROUGHS & DRAIN TUBES BACK TO EXISTING FLOOR DRAIN. REMOVE & DISCARD ALL TUBE & DRIP PAN BRACKETS FROM CEILING & WALLS.

ORIGINAL STAMPED BY: D.A. PALEY, P.ENG
DATE: 2010.09.21

NO.	REVISION/DESCRIPTION	BY	DATE
SEALS			

DRAWN BY	RCP	CHECKED BY	APPROVED
DATE	2010.09.21	USER APPROVAL	

CITY OF WINNIPEG
PLANNING, PROPERTY AND
DEVELOPMENT DEPARTMENT
CIVIC ACCOMMODATIONS DIVISION
300 - 65 GARRY ST. R3C 4K4

PROJECT
PUBLIC SAFETY BUILDING
EXHIBIT PROCESSING AREA DEVELOPMENT

151 PRINCESS STREET
SHEET TITLE

PARTIAL BASEMENT FLOOR PLAN
PLUMBING
DEMOLITION

SCALE	PROJECT NO.	SHEET NO.
AS SHOWN	2008-067	M3

PARTIAL BASEMENT FLOOR PLAN - PLUMBING/FLOOR DEMOLITION
SCALE: 1/4"=1'-0"

