



NO.	REVISION/DESCRIPTION	BY	DATE
0	ISSUED FOR TENDER		KO 12/10



DRAWN BY	CHECKED BY	APPROVED
KOLO	USER APPROVAL	

CITY OF WINNIPEG
 PLANNING, PROPERTY AND
 DEVELOPMENT DEPARTMENT
 CIVIC ACCOMMODATIONS DIVISION
 300 - 65 GARRY ST. R3C 4K4

PROJECT
MANDARIN BUILDING
ALTERNATE EMERGENCY
COMMUNICATION CENTRE- DESIGN
 185 KING STREET

SHEET TITLE
MAIN FLOOR PLAN
EXISTING POWER AND SYSTEMS PLAN

SCALE	PROJECT NO.	SHEET NO.
AS SHOWN	2008-095-02	E-3

1 PARTIAL MAIN FLOOR PLAN - EXISTING POWER AND SYSTEMS- DEMOLITION
 E1 | SCALE: 1/8"=1'-0"

DRAWING NOTES:	
1.	REMOVE ALL EXISTING DROP POWER CABLES BACK TO THE JUNCTION BOX FOR EACH ABANDONED PACK POLE AND ALL UNUSED TELEPHONE AND DATA CABLING BACK TO THE LAN ROOM.
2.	REMOVE FIRE ALARM BELLS AND DEVICES TO SUIT NEW WALL CONSTRUCTION. KEEP FIRE ALARM SYSTEM ACTIVE DURING CONSTRUCTION.
3.	ENSURE ALL WIRING SUPPLYING POWER TO OTHER AREAS IS MAINTAINED THROUGHOUT THE PROJECT.
4.	EXISTING FIRE ALARM PANEL IS A MIRCUM 100, CONVENTIONAL STYLE SYSTEM.
5.	ENSURE ALL POWER SHUTDOWN IS COORDINATED WITH CITY OF WINNIPEG COMMUNICATION DEPT. AND CONTRACT ADMINISTRATOR.
6.	COORDINATE WITH MECHANICAL FOR ALL REMOVAL AND RELOCATION OF THERMOSTATS, ROOM SENSORS, ETC.
7.	NOT ALL EXISTING DEVICES AND EQUIPMENT ARE SHOWN. CONTRACTOR IS TO PROVIDE ALL NECESSARY DEMO TO ALL ELECTRICAL EQUIPMENT IN AREA OF WORK.
8.	NEWLY INSTALLED H/C DOOR OPERATORS ARE TO REMAIN. WIRING IS TO BE RECONNECTED TO A NEW PANEL.