

PART 1 GENERAL

1.1 REFERENCE

- .1 Comply with the General Conditions of the Contract, Supplementary General Conditions and the requirements of Division 1.

1.2 RELATED WORK SPECIFIED ELSEWHERE

- .1 Excavating, Backfilling and Grading Section 02200
- .2 Site Engineering

1.3 SCOPE OF WORK INCLUDED

- .1 Supply and installation of stone at perimeter of building and all aluminum landscape edging.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Aluminum Landscape Edging :1/8" thickness edging in 4" depths @ 16' lengths sections. Sections to come with 1 splicer & 4 line stakes. Tab punched at each end - horizontal undulations along both faces at edge - a horizontal LOC Ridge protruding along one side, 1/2" from the top. Stakes 14" long 2" wide with a 2" portion folded over. Line stakes - 12 1/2" long, 1" wide with a 2" portion folded over as manufacturer by Permaloc or equal (Tel 1-800-356-9660 or contact Interioscapes 519 681-9982). Follow the manufacturer's written instructions for installation.
- .2 Landscaping Fabric: Black woven sheet material to prevent growth of weeds yet allow drainage.
- .3 River Washed Stone: 4" to 6" particle size rounded beach stone to uniform grey colour.

PART 3 EXECUTION

3.1 INSTALLATION - PERIMETER STONE

- .1 Install aluminum edging around perimeter of building to separate all grassed areas from washed stone areas including patio area. Use joining units as required (T, L, angle). Install in warm weather to insure no crimping of material.

- .2 Supply and install landscape fabric below river washed stone to prevent weed and grass growth. Insure positive connection to building construction and aluminum edging.
- .3 Place River Washed Stone around entire perimeter of building between face of building and aluminum edging covering filter cloth to a depth of 8".
- .4 Place stone and aluminum edging around perimeter of site boundary which will occur on neighbour's side of new fencing to establish a mowing edge.

END OF SECTION