

---

**PART 1 GENERAL**

## 1.1 REFERENCE

- .1 Comply with the General Conditions of the Contract, Supplementary General Conditions and the requirements of Division 1.

## 1.2 RELATED WORK SPECIFIED ELSEWHERE

- .1 Rough Carpentry Section 06100
- .2 Masonry Section 04200

## 1.3 SCOPE OF WORK INCLUDED

- .1 Supply and installation of CRL Stand Off Display System for mounting the Fire Safety Plans Throughout the Building.

## 1.4 SUBMITTALS

- .1 Provide shop drawings.

## 1.5 PROTECTION / DELIVERY

- 1. Protect Display System. Install at project completion at locations selected by the architect.
- 2. **The Architect will provide the laminated Fire Safety Plans that will be housed in the display system ( no cost to General Contractor ).**

**PART 2 PRODUCTS**

2.1 Manufacturer : C.R. Lawrence Co Tel 800-421-6144

## MATERIALS

- .1 Other Manufacturers as approved by Architect

## Description :

Chromed 3/4" diameter stand off leg set into wall assembly ( 4 legs per glass panel ) c/w chromed top.

Safety Glass Size : approx 17"H x 23"L predrilled to accommodate holes @ 1 1/2" o.c. from perimeter of glass edge.

**Quantity : 3 required**

**PART 3 EXECUTION**

3.1 INSTALLATION

- .1 Install under Section 06100.
- .2 Install plumb and square to floor and wall assemblies.

END OF SECTION