



PHASE	NO.	CONSTRUCTION NOTES
1	1	INSTALL TEMPORARY FEEDER CABLE FOR PNL-2X.
	2	REMOVE EXISTING SPLITTER, DISCONNECT SWITCHES AND UPS IN ADMINISTRATION BUILDING.
2	3	INSTALL AND CONFIGURE UPS AS PER MANUFACTURERS INSTRUCTIONS. DO NOT INTERRUPT POWER TO PNL-2X WITHOUT APPROVAL OF THE CONTRACT ADMINISTRATOR.
	4	INSTALL NEW EXTERNAL MAINTENANCE BYPASS CABINET WITH INTERNAL 600:120V ISOLATION TRANSFORMER.
	5	REMOVE XFMR-2X AND TEMPORARY FEEDER CABLE.

- NOTES:**
- SUPERSEDES PART OF DWG. SEP-823
 - ALL CONNECTED AND DEMAND LOADS ARE BASED UPON EXISTING DOCUMENTATION AND HAVE NOT BEEN CONFIRMED.
 - ALL CONDUIT IS TO BE RIGID ALUMINUM UNLESS OTHERWISE NOTED.



NO.	REVISIONS	DATE	DESIGN	CHECK
01	ADDED UPS-M1	2011/03/11	TMC	CJR
00	ISSUED FOR TENDER, BID OPP 837-2009	2009/12/07	-	NB

		DESIGNED BY: EXISTING DRAWN BY: S. JUGANAS SCALE: NTS DATE: 2009/07/20 CONSULTANT NO.: 112577-0105-47DD-0101	CHECKED BY: N. BRADDOO APPROVED BY: C. REIMER RELEASED FOR CONSTRUCTION BY: J. VEILLEUX DATE: 2009/12/02
--	--	--	---

ENGINEER'S SEAL

ORIGINAL DRAWING SEALED BY:
 T. M. CHURCH
 SNC-Lavalin
 MEMBER #32682
 2011/03/25
 REV. 01
 CHANGES ONLY

THE CITY OF WINNIPEG
 WATER AND WASTE DEPARTMENT

SOUTH END WATER POLLUTION CONTROL CENTRE
 ESSENTIAL SYSTEM UPGRADES
 SINGLE LINE ELECTRICAL
 ADMINISTRATION BUILDING ELECTRICAL ROOM

CITY DRAWING NUMBER	SHEET	REV.	SIZE
1-0102M-E0007	001	01	A1

DRAWING NUMBER	REFERENCE DRAWINGS
----------------	--------------------