

Part 1 General

1.1 FIRE ALARM SYSTEM

1. The Electrical Subcontractor shall install new devices or relocate existing as indicated on the drawings. All audible, alarm or supervisory zones that have been altered or added to shall be reverified by an agent acceptable to the Consultant. The cost of this reverification shall be included in the contract price.
2. The Reverification Report shall accompany the record drawings.
3. All new fire alarm devices shall match existing.
4. Where fire alarm devices are deleted, provide red coverplate and ensure continued accessibility. Paint coverplates of all fire alarm junction boxes, this area red.
5. All new and/or relocated fire alarm devices shall be listed and locations shown on a separate drawing to be issued to Building Owner.
6. Provide separate zone where new fire wall shown and connect to new zone on existing system.

END OF SECTION