


- Supply and Install Concrete Apron and Curb Cut at entrance to path
- Supply and Install Metal Slat Waste Receptacles (x3)
- Supply and Install Soil & Sod over Former Pathway Area
- Supply and Install Cascade Style 1.8m Long Composite Benches w/ Arms (x2)
- Supply and Install Accessible Picnic Table
- Supply and Install Bollards
- Pick up and Install Double Sided Park name sign (location to be determined on site by C.A.)
- Relocate Park Name sign to park entrance off of Erlandson Dr
- Supply and Install 1.8m Wide Granular Path and Seating Areas
- Supply and Install Engineered Wood Fibre Safety Surfacing
- Supply and Install 1 Tiered Timber Edging w/ Pedra Cap
- Supply and Install subsurface drainage
- Supply and Install 2 Bay, 2 Belt, 2 Infant Seat Swings
- Supply and Install 600mm (2') Strip of Soil & Sod around Timber Edging and Granular Path
- Area to be regraded and sodded
- Grade to existing fence
- Supply and Install subsurface drainage and connect to existing catch basin
- Do not regrade around existing trees

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG
 Planning, Property and Development Department
 Planning and Land Use Division
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	CHECKED BY	MANAGER, PARK AND OPEN SPACES	DATE
DRAWN BY IL/ SP	APPROVED BY		
HORIZ. SCALE VERT. SCALE DATE	1:400 MAY 2011	MANAGER, PLANNING AND LAND USE DIVISION	DATE

DRAWING TITLE
**ERLANDSON PARK
 PLAYGROUND RENEWAL**
 Proposed Playground Improvements

SITE ADDRESS 82 Cortez Bay

DRAWING NO.
E.22-B2
 BID OPPORTUNITY NO.
36-2011