

DOMESTIC WATER PIPING COPPER

1. GENERAL

1.1 Section Includes

- .1 Materials and installation for copper domestic water service used in the following:
 - .1 Hard drawn copper domestic hot and cold water services inside building.
 - .2 Valves: Ball, globe, and check

1.2 Related Sections

- .1 Section 22 07 19 – Plumbing Piping Insulation
- .2 Section 23 05 05 - Installation of Pipework.
- .3 Section 23 05 23.01 - Valves - Bronze.
- .4 Section 23 05 29 – Hangers and Supports for HVAC Piping and Equipment
- .5 Section 23 05 83 - Balancing
- .6 Section 23 05 93 - Testing.

1.3 References

- .1 American National Standards Institute (ANSI)/American Society of Mechanical Engineers International (ASME).
 - .1 ANSI/ASME B16.15-11, Cast Copper Alloy Threaded Fittings, Classes 125 and 250.
 - .2 ANSI/ASME B16.18-01(R2005), Cast Copper Alloy Solder Joint Pressure Fittings.
 - .3 ANSI/ASME B16.22-01(R2010), Wrought Copper and Copper Alloy Solder Joint Pressure Fittings.
- .2 ASTM International, (ASTM).
 - .1 ASTM B 88M-05(R2011), Standard Specification for Seamless Copper Water Tube (Metric).
- .3 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .4 Manufacturer's Standardization Society of the Valve and Fittings Industry (MSS).
 - .1 MSS-SP-80-08, Bronze Gate, Globe, Angle and Check Valves.
- .5 National Research Council (NRC)/Institute for Research in Construction.

DOMESTIC WATER PIPING COPPER

- .1 NRCC 38728, National Plumbing Code of Canada (NPC) - 2010.

1.4 Submittals

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit product data for following: Valves.
- .3 Provide maintenance data for incorporation into Operating and Maintenance Manual as specified in Section 01 33 00 - Submittal Procedures.
- .4 Provide pressure test and disinfection certificates for incorporation into Operating and Maintenance Manual as specified in Section 01 33 00 - Submittal Procedures.

2. PRODUCTS

2.1 Piping

- .1 Domestic hot, cold and recirculation systems, within building.
 - .1 Above ground: copper tube, hard drawn, type K: to ASTM B 88M.

2.2 Fittings

- .1 Cast bronze threaded fittings, Class 125: to ANSI/ASME B16.15.
- .2 Cast copper, solder type: to ANSI/ASME B16.18.
- .3 Wrought copper and copper alloy, solder type: to ANSI/ASME B16.22.

2.3 Joints

- .1 Solder: 95/5 tin copper alloy.
- .2 Teflon tape: for threaded joints.
- .3 Dielectric connections between dissimilar metals: dielectric fitting to ASTM F 492, complete with thermoplastic liner.

2.4 Globe Valves

- .1 50mm and under, screwed:
 - .1 To MSS-SP-80, Class 150, 1 MPa, bronze body, screwed over bonnet, renewable composition disc as specified Section 23 05 23.01 - Valves - Bronze .
 - .2 Lockshield handles: on domestic hot water return.

2.5 Swing Check Valves

- .1 50mm and under, screwed:

DOMESTIC WATER PIPING COPPER

- .1 To MSS-SP-80, Class 125, 860 kPa, bronze body, bronze swing disc, screw in cap, re-grindable seat as specified Section 23 05 23.01 - Valves – Bronze..

2.6 Ball Valves

- .1 50mm and under, screwed:
 - .1 Class 150.
 - .2 Bronze body, stainless steel ball, PTFE adjustable packing, brass gland and PTFE seat, steel lever handle as specified Section 23 05 23.01 - Valves - Bronze.

3. EXECUTION

3.1 Installation

- .1 Install in accordance with NPC with Manitoba Amendments 2010 and the local authority having jurisdiction.
- .2 Install pipe work in accordance with Section 23 05 05 - Installation of Pipework, supplemented as specified herein.
- .3 Assemble piping using fittings manufactured to ANSI standards.
- .4 Install CWS piping below and away from HWS and HWC and other hot piping so as to maintain temperature of cold water as low as possible.
- .5 Connect to fixtures and equipment in accordance with manufacturer's written instructions unless otherwise indicated.

3.2 Valves

- .1 Isolate equipment, fixtures and branches with ball valves.
- .2 Balance recirculation system using lockshield globe valves. Mark settings and record on as-built drawings on completion.

3.3 Pressure Tests

- .1 Test pressure: greater of 1.5 times maximum system operating pressure or 860 kPa.

3.4 Pre-Start-Up Inspections

- .1 Systems to be complete, prior to flushing, testing and start-up.
- .2 Verify that system can be completely drained.
- .3 Ensure that pressure booster systems are operating properly.
- .4 Ensure that air chambers, expansion compensators are installed properly.

DOMESTIC WATER PIPING COPPER

3.5 Disinfection

- .1 Flush out all new pipework for 8 hours, disinfect and rinse all new pipework, fittings and equipment system to requirements of authority having jurisdiction and/or the approval of Contract Administrator
- .2 Add chlorine to water in system to 50 mg per litre and let stand for twenty-four (24) hours. Check chlorine content after twenty-four (24) hours and insure the content is not less than 20 mg per L. If chlorine content is less than 20 mg per L repeat process. Flush system until the chlorine content of water being drained is equal to the chlorine content of the make-up water
- .3 Upon completion, provide laboratory test reports on water quality for Contract Administrator approval.

3.6 Start-Up

- .1 Timing: Start up after:
 - .1 Pressure tests have been completed.
 - .2 Disinfection procedures have been completed.
 - .3 Certificate of static completion has been issued.
 - .4 Water treatment systems operational.
- .2 Provide continuous supervision during start-up.
- .3 Start-up procedures:
 - .1 Establish circulation and ensure that air is eliminated.
 - .2 Check pressurization to ensure proper operation and to prevent water hammer, flashing and/or cavitation.
 - .3 Monitor piping HWS and HWC piping systems for freedom of movement, pipe expansion as designed.
 - .4 Check control, limit, safety devices for normal and safe operation.
- .4 Rectify start-up deficiencies.

3.7 Performance Verification

- .1 Timing:
 - .1 After pressure and leakage tests and disinfection completed, and certificate of completion has been issued by authority having jurisdiction.
- .2 Procedures:

DOMESTIC WATER PIPING COPPER

- .1 Verify that flow rate and pressure meet Design Criteria.
 - .2 Test HWC in accordance with Section 23 05 93 - Testing.
 - .3 Balance HWC in accordance with Section 23 05 83 - Balancing.
 - .4 Adjust pressure regulating valves while withdrawal is maximum and inlet pressure is minimum.
 - .5 Sterilize HWS and HWC systems for Legionella control.
 - .6 Verify performance of temperature controls.
 - .7 Verify compliance with safety and health requirements.
 - .8 Confirm water quality consistent with supply standards, verifying that no residuals remain as a result of flushing and/or cleaning.
- .3 Reports:
- .1 Include certificate of water flow and pressure tests conducted on incoming water service, demonstrating adequacy of flow and pressure.

END OF SECTION